


Note:
See Civil Package 2: Early Grading for project reference points and project coordinate points.



Van W. Robbins
04-11-25

DATE PREPARED
04/11/2025

ROUTE STATE
1 - 70 MO

DISTRICT SHEET NO.
BR B03-01


COUNTY
JACKSON

JOB NO.
J411486D

CONTRACT ID.
240807-C01

PROJECT NO.

BRIDGE NO.
A9629



LOCATION SKETCH

INDEX OF DRAWINGS

- B03-01 Title Sheet and Index
- B03-02 General Plan and Elevation
- B03-03 General Notes
- B03-04 Substructure Layout
- B03-05 Details of End Bent No. 1
- B03-06 Details of End Bent No. 1
- B03-07 Vertical Drain at End Bents
- B03-08 Details of Intermediate Bents
- B03-09 Details of End Bent No. 5
- B03-10 Details of End Bent No. 5
- B03-11 Framing Plan
- B03-12 NU-Girders-Spans (1-2) & (4-5)
- B03-13 NU-Girders-Spans (2-3) & (3-4)
- B03-14 Concrete Diaphragm at Intermediate Bents
- B03-15 Camber Diagram & Theoretical Slab Haunching Diagram
- B03-16 Theoretical Bottom of Slab Elevations
- B03-17 Slab Plan Showing Top Reinforcement
- B03-18 Slab Plan Showing Bottom Reinforcement
- B03-19 Slab Details
- B03-20 Pedestrian Curb Details
- B03-21 Light Anchorage Details
- B03-22 Decorative Pedestrian Fence Details
- B03-23 Details of Conduit System on Structure
- B03-24 As-Built Pile and Drilled Shaft Data
- B03-25 Boring Logs
- B03-26 Boring Logs
- B03-27 Boring Logs
- B03-28 Boring Logs



REV	DESCRIPTION	DATE
0	REV 0 - RFC SUBMITTAL	04/11/25

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

CLARKSON RADMACHER JOINT VENTURE

715 KIRK DRIVE
KANSAS CITY, MO 64105-1310
CERTIFICATE OF AUTHORITY
NO. 001270

Released For Construction
Not to Scale
Revision: 0.0
Date: 04/11/2025
Package: BRD-03-25th_ST_PED

BRIDGE: 25TH STREET PEDESTRIAN BRIDGE
OVER ROUTE 1-70

ROUTE 1-70 FROM ROUTE 1-670 TO ROUTE 40
ABOUT 2.4 MILES EAST OF ROUTE 1-670
TIE STATION 190+65.00 (☺ 1-70)

Design Specifications:
 2020 AASHTO LRFD Bridge Design Specifications (9th Ed.) and 2023 AASHTO Guide Specifications for LRFD Seismic Bridge Design (3rd Edition)
 Seismic Design Category = A (Nonseismic)
 Design earthquake response spectral acceleration coefficient at 1.0 second period, $S_{D1} = 0.15$
 $A_s = N/A$
 2009 AASHTO LRFD Guide Specifications for the Design of Pedestrian Bridges and 2015 Interim Revisions.

Design Loading:
 Vehicular = H10 Truck minus lane load
 Pedestrian = 90 lb/sf
 Future Wearing Surface = 35 lb/sf
 Earth = 120 lb/cf
 Equivalent Fluid Pressure = 45 lb/cf (Min.)
 Superstructure: Simply-Supported, non-composite for dead load, Continuous composite for live load.

Design Unit Stresses:
 Class B Concrete (End Bents below Const. Jt.) $f'_c = 3,000$ psi
 Class B-1 Concrete (Intermediate Bents except Drilled Shafts) $f'_c = 4,000$ psi
 Class B-2 Concrete (Drilled Shafts) $f'_c = 4,000$ psi
 Class B-2 Concrete (Superstructure, except Prestressed Girders, and Pedestrian Curb) $f'_c = 4,000$ psi
 Class B-1 Concrete (Pedestrian Curb) $f'_c = 4,000$ psi
 Reinforcing Steel (ASTM A615 Grade 60) $f_y = 60,000$ psi
 Structural HP Steel Pile (ASTM A709 Grade 50) $f_y = 50,000$ psi
 For prestressed girder stresses, see Sheets No. B03-12 thru B03-13.

Neoprene Pads:
 Neoprene Bearing Pads shall be 60 durometer and shall be in accordance with Sec 716.

Joint Filler:
 All joint filler shall be in accordance with Sec 1057 for preformed sponge rubber expansion and partition joint filler, except as noted.

Reinforcing Steel:
 Minimum clearance to reinforcing steel shall be 1-1/2", unless otherwise shown.

All reinforcing in the pedestrian curb, light blisters, slab, concrete diaphragms, End Bents No. 1 and 5 and Intermediate Bents No. 2, 3 & 4 shall be epoxy coated. Reinforcing in the drilled shaft shall be uncoated.

Concrete Protective Coatings:
 Concrete and masonry protective coating shall be applied on bridge wingwall and end face of end bent to a minimum of 18" below finished ground line in accordance with Sec 711.


Sacrificial graffiti protective coating shall be applied on bridge wingwall and end face of end bent to a minimum of 18" below finished ground line in accordance with Sec 711.

Abbreviations:
 E.F. denotes Each Face
 N.F. denotes Near Face
 F.F. denotes Far face
 U.N.O. denotes Unless Noted Otherwise

Foundation Data							
Type	Design Data	Bent Number					
		1	2	3	4	5	
Load Bearing Pile	Pile Type and Size	HP 12x53	---	---	---	HP 12x53	
	Number	3	---	---	---	3	
	Approximate Length Per Each	18	---	---	---	18	
	Pile Point Reinforcement	All	---	---	---	---	
	Min. Galvanized Penetration (Elev.)	Full Length	---	---	---	Full Length	
	Minimum Tip Penetration (Elev.)	911	---	---	---	899	
	Criteria for Min. Tip Penetration	Min. Embed.	---	---	---	Min. Embed.	
Pile Driving Verification Method	DT	---	---	---	---	N/A	
	Resistance Factor	0.65	---	---	---	0.50	
Minimum Nominal Axial Compressive Resistance	kip	168	---	---	---	218	
	ea	---	1	1	1	---	
Drilled Shaft	Foundation Material	---	Limestone	Shale	Limestone	---	
	Elevation Range	---	900-895.5**	899-882	900-899**	---	
	Minimum Nominal Axial Compressive Resistance (Side Resistance)	ksf	---	19.6	4.5	19.6	---
	Foundation Material	---	Shale	Limestone	Shale	---	
	Elevation Range	ft	---	895.5-879	882-870	899-882	---
Minimum Nominal Axial Compressive Resistance (Side Resistance)	ksf	---	4.9	19.6	4.9	---	
Minimum Nominal Axial Compressive Resistance (Tip Resistance)	ksf	---	End bearing not required*	End bearing not required*	End bearing not required*	---	

Detailed DEC 2024
 Checked JAN 2025

Note: This drawing is not to scale. Follow dimensions.



STAY-IN-PLACE CORRUGATED STEEL FORM DETAIL


Stay-In-Place Corrugated Steel Form Notes:

Corrugated steel forms, supports, closure elements and accessories shall be in accordance with grade requirement and coating designation G165 of ASTM A653. Complete shop drawings of the permanent steel deck forms shall be required in accordance with Sec 1080.

Corrugations of stay-in-place forms shall be filled with an expanded polystyrene material. The polystyrene material shall be placed in the forms with an adhesive in accordance with the manufacturer's recommendations.

Form sheets shall not rest directly on the top of girder flanges. Sheets shall be securely fastened to form supports with a minimum bearing length of one inch on each end. Form supports shall be placed in direct contact with the flange. Welding on or drilling holes in the girder flanges will not be permitted. All steel fabrication and construction shall be in accordance with Sec 1080 and 712. Certified field welders will not be required for welding of the form supports.

The design of stay-in-place corrugated steel forms is per manufacturer which shall be in accordance with Sec 703 for false work and forms. Maximum actual weight of corrugated steel forms allowed shall be 4 psf assumed for girder loading.



DRILLED SHAFT OVER EXCAVATION DETAIL

Load Bearing Piles:


Minimum Nominal Axial Compressive Resistance = Maximum Factored Loads/Resistance Factor
 Prebore for piles at End Bent No. 1 to elevation 913. End Bent No. 1 HP piles are anticipated to be driven to refusal on rock. Review all borings for depth of rock and restrict driving as appropriate to comply with hard rock driving criteria in accordance with Sec 702. When pile refusal on rock occurs, as approved by the engineer, the minimum nominal axial compressive resistance is verified and no additional pile driving verification method is required.
 Prebore for piles at End Bent No. 5 to elevation 899. At End Bent No. 5 verify the bottom of the prebore is clean and contains no loose rubble. Set pile and seat with tap of backhoe bucket or equivalent method. Prebore shall be backfilled with Class B concrete to elevation 904. Backfill remaining length of prebore per Sec 702. All piles shall be galvanized down to minimum galvanized penetration (elevation).
 Pile point reinforcement need not be galvanized. Shop drawings will not be required for pile point reinforcement.
 The contractor shall make every effort to achieve the minimum galvanized penetration (elevation) shown on the plans for all piles. Deviations in penetration less than 5 feet of the minimum will be considered acceptable provided the contractor makes the necessary corrections to ensure the minimum penetration is achieved on subsequent piles.
 DT = Dynamic Testing

For Drilled Shaft Details see Intermediate Bent Details

Drilled Shafts:
 Minimum Nominal Axial Compressive Resistance (Side Resistance + Tip Resistance) = Maximum Factored Loads/Resistance Factors
 Uncased drilled shaft used for constructability. Layer 1 data shown in table is top most layer used for design and may not correspond to top of drilled shaft shown elsewhere in plans.
 Sonic logging testing shall be performed on all drilled shafts.
 Drilled shafts shall be constructed in accordance with project Drilled Shaft AAS.
 * Drilled shaft length for drilled shafts is controlled by lateral design. End bearing not required.
 ** Top of elevation range corresponds to 18" below future WB I-70 lane construction by others and EB I-70 lane construction with this project at Bents No. 2 and 4, respectively.

GENERAL NOTES

Released For Construction
 Not to Scale
 Revision: 0.0
 Date: 04/11/2025
 Package: BRD-03-25th_ST_PED



Van W. Robbins
 04-11-25

DATE PREPARED
 04/11/2025

ROUTE 1-70 STATE MO

DISTRICT BR SHEET NO. B03-03

COUNTY JACKSON

JOB NO. J411486D

CONTRACT ID. 240807-C01

PROJECT NO.

BRIDGE NO. A9629


DATE	DESCRIPTION
04/11/25	REV 0 - RFC SUBMITTAL

DATE 04/11/25

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL JEFFERSON CITY, MO 65102


1-888-ASK-MODOT (1-888-275-6636)




CLARKSON RADMACHER JOINT VENTURE


715 KIRK DRIVE KANSAS CITY, MO 64105-1310

CERTIFICATE OF AUTHORITY NO. 001270






DATE PREPARED 04/11/2025	
ROUTE 1 - 70	STATE MO
DISTRICT BR	SHEET NO. B03-04
COUNTY JACKSON	
JOB NO. J411486D	
CONTRACT ID. 240807-C01	
PROJECT NO.	
BRIDGE NO. A9629	



SUBSTRUCTURE LAYOUT



BRIDGE APPROACH SLAB DETAIL
(1 required at End Bents No. 1 and 5)

Bridge Approach Slab Notes:
All concrete for bridge approach slab shall be in accordance with Sec 503 ($f'c=4,000$ psi).

The reinforcing steel in the bridge approach slab shall be epoxy coated Grade 60 with $f_y=60,000$ psi.

The reinforcing steel in the bridge approach slab shall be continuous. The transverse reinforcing steel may be made continuous by providing a minimum lap splice of 23" for #4 bars.

Provide 3/4" joint filler between edge of approach slab and inside vertical face of bridge wingwall. Provide 2" joint filler at end of bridge approach slab adjacent to trail approach. All joint filler shall be in accordance with Sec 1057 for preformed fiber expansion joint filler except as noted.

Released For Construction
Not to Scale
Revision: 0.0
Date: 04/11/2025
Package: BRD-03-25th_ST_PED

Note:
All dimensions are horizontal.

SUBSTRUCTURE LAYOUT

DATE	DESCRIPTION
04/11/25	REV 0 - RFC SUBMITTAL


MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

CLARKSON RADMACHER JOINT VENTURE

715 KIRK DRIVE
KANSAS CITY, MO 64105-1310
CERTIFICATE OF AUTHORITY
NO. 001270

Released For Construction
 Not to Scale
 Revision: 0.0
 Date: 04/11/2025
 Package: BRD-03-25th_ST_PED



Gina D. Horner
 4/11/2025


DATE PREPARED 04/11/2025	
ROUTE 1-70	STATE MO
DISTRICT BR	SHEET NO. B03-05
COUNTY JACKSON	
JOB NO. J411486D	
CONTRACT ID. 240807-C01	
PROJECT NO.	

BRIDGE NO. A9629


DATE	DESCRIPTION
04/11/25	REV 0 - RFC SUBMITTAL

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
 105 WEST CAPITOL JEFFERSON CITY, MO 65102
 1-888-ASK-MODOT (1-888-275-6636)


CLARKSON RADMACHER JOINT VENTURE
 715 KIRK DRIVE KANSAS CITY, MO 64105-1310
 CERTIFICATE OF AUTHORITY NO. 001270
HNTB




PLAN OF BEAM



SECTION NEAR END BENT
 (Looking Backstation)




SECTION THRU KEY




STEEL PILE SPLICE
 (If required)


* Galvanizing material shall be omitted or removed one inch clear of weld locations in accordance with Sec 702.



PLAN OF BEAM SHOWING REINFORCING
 (Keys and Steps not shown for Clarity)



PART PLAN
 (Symmetrical about C 25th St. Ped. Bridge)




TYPICAL SECTION THRU LAMINATED NEOPRENE BEARING PAD (TAPERED)
 2 Required at each End Bent

Notes:
 Work this sheet with Sheet No. B03-06.
 For Sections A-A, B-B, C-C, D-D and Elevation E-E, see Sheet B03-06.
 Reinforcing steel shall be shifted to clear piles. U bars shall clear piles by at least 1 1/2 inches.
 All concrete above the construction joint shall be Class B-2.
 For location of coil tie rods, see Sheet No. B03-12.
 Strands at end of the girders shall be field bent or, if necessary, cut in field to maintain 1 1/2-inch minimum clearance to fill face of end bent.
 The #6-F bars shall be bent in the field to clear girders.
 For details of bridge approach slab, see Sheet No. B03-04.

(X) Denotes girder number

DETAILS OF END BENT NO. 1



DATE PREPARED 04/11/2025	
ROUTE 1-70	STATE MO
DISTRICT BR	SHEET NO. B03-06
COUNTY JACKSON	
JOB NO. J411486D	
CONTRACT ID. 240807-C01	
PROJECT NO.	

BRIDGE NO. A9629

DATE	DESCRIPTION
04/11/25	REV 0 - RFC SUBMITTAL

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION


MoDOT

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)


CLARKSON RADMACHER JOINT VENTURE

715 KIRK DRIVE
KANSAS CITY, MO 64105-1310
CERTIFICATE OF AUTHORITY
NO. 001270


HNTB



ELEVATION E-E
(South wingwall shown, North wingwall similar)




TYPICAL SECTION THRU WING
#8 Bars at 3" cts. (Each face) (Place with grade) See Elevation E-E for number of bars




CHAMFER DETAIL

Released For Construction
Not to Scale
Revision: 0.0
Date: 04/11/2025
Package: BRD-03-25th_ST_PED




SECTION A-A


(1) U3 & #4 stirrup bar vertical leg = 2'-10"



SECTION B-B








SECTION C-C



SECTION D-D

General Notes:
Work this sheet with Sheet No. B03-05.
For location of Sections A-A, B-B, C-C and D-D and Elevation E-E, see Sheet No. B03-06.
For reinforcement of the pedestrian curb, see Sheet No. B03-20.

DETAILS OF END BENT NO. 1




OPTIONAL TURNED DRAIN
(Use only when straight drain is not practical.)

Released For Construction
Not to Scale
Revision: 0.0
Date: 04/11/2025
Package: BRD-03-25th_ST_PED

General Notes:

- All drain pipe shall be sloped 1 to 2 percent.
- Drain pipe may be either 6-inch diameter corrugated metallic-coated steel pipe underdrain, 4-inch diameter corrugated polyvinyl chloride (PVC) drain pipe, or 4-inch diameter corrugated polyethylene (PE) drain pipe.
- Drain pipe shall be placed at fill face of end bent and inside face of wings. The pipe shall slope to lowest grade of ground line, also missing the lower beam of end bent by a minimum of 1 1/2 inches.
- Perforated pipe shall be placed at fill face side and inside face of wings at the bottom of end bent and plain pipe shall be used where the vertical drain ends to the exit at ground line.

VERTICAL DRAIN AT END BENTS



DATE PREPARED 04/11/2025	
ROUTE 1 - 70	STATE MO
DISTRICT BR	SHEET NO. B03-07
COUNTY JACKSON	
JOB NO. J411486D	
CONTRACT ID. 240807-C01	
PROJECT NO.	
BRIDGE NO. A9629	


DATE	DESCRIPTION
04/11/25	REV 0 - RFC SUBMITTAL

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

CLARKSON RADMACHER JOINT VENTURE

715 KIRK DRIVE
KANSAS CITY, MO 64105-1310
CERTIFICATE OF AUTHORITY
NO. 001270



DATE PREPARED 04/11/2025	
ROUTE 1-70	STATE MO
DISTRICT BR	SHEET NO. B03-08
COUNTY JACKSON	
JOB NO. J411486D	
CONTRACT ID. 240807-C01	
PROJECT NO.	

BRIDGE NO. A9629

DATE	DESCRIPTION
04/11/25	REV 0 - RFC SUBMITTAL

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION


MoDOT

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)


CLARKSON RADMACHER
JOINT VENTURE

715 KIRK DRIVE
KANSAS CITY, MO 64105-1310
CERTIFICATE OF AUTHORITY
NO. 001270


HNTB




ELEVATION



- ① 5-#6-U2 @ 12" cts.
- ② 5-#6-U1 @ 12" cts.
- ③ 5-#8-D @ Eq. Spa.




PLAN OF CAPBEAM




SECTION A-A


SECTION B-B




TYPICAL SECTION THRU LAMINATED NEOPRENE BEARING PAD (TAPERED)
4 Required per Bent



SECTION THRU KEY



SECTION C-C




SECTION D-D

Bent	'A'	'B'	'C'	'D'	'E'	'G'	'H'
2	4' - 7 1/2"	13' - 1 1/2"	26' - 0"	927.78	927.66	910.0	884.0
3	4' - 7 1/2"	18' - 3 3/4"	25' - 6"	923.42	923.31	900.5	875.0
4	4' - 7 1/2"	15' - 1 1/8"	16' - 0"	919.72	919.59	900.0	884.0

Notes:
 Prior to placing concrete for columns, position of vertical reinforcement shall be verified so as to provide clearance for capbeam reinforcement as applicable.
 For location of drilled shafts, see Sheet No. B03-04.
 Hoop splices shall be staggered around the drilled shaft at 90 degree intervals.

DETAILS OF INTERMEDIATE BENTS

Released For Construction
Not to Scale
Revision: 0.0
Date: 04/11/2025
Package: BRD-03-25th_ST_PED



DATE PREPARED 04/11/2025	
ROUTE 1-70	STATE MO
DISTRICT BR	SHEET NO. B03-09
COUNTY JACKSON	
JOB NO. J411486D	
CONTRACT ID. 240807-C01	
PROJECT NO.	

BRIDGE NO. A9629


DATE	DESCRIPTION
04/11/25	REV 0 - RFC SUBMITTAL

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION


105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

CLARKSON
RADMACHER
JOINT VENTURE


715 KIRK DRIVE
KANSAS CITY, MO 64105-1310
CERTIFICATE OF AUTHORITY
NO. 001270




PLAN OF BEAM




PLAN OF BEAM SHOWING REINFORCING
(Keys and Steps not shown for Clarity)




SECTION NEAR END BENT



PART PLAN
(Symmetrical about C 25th St. Ped Bridge)



SECTION THRU KEY



STEEL PILE SPLICE
(If required)


Released For Construction
Not to Scale

Revision: 0.0
Date: 04/11/2025
Package: BRD-03-25th_ST_PED

Notes:
Work this sheet with Sheet No. B03-10.
For Sections A-A, B-B, C-C, D-D and Elevation E-E, see Sheet B03-10.
All concrete above the construction joint shall be Class B-2.
Reinforcing steel shall be shifted to clear piles. U bars shall clear piles by at least 1 1/2 inches.
For laminated neoprene bearing detail, see Sheet No. B03-05.
For Location of coil tie rods, see Sheet No. B03-12.
Strands at end of the girders shall be field bent or, if necessary, cut in field to maintain 1 1/2-inch minimum clearance to fill face of end bent.
The #6-F bars shall be bent in the field to clear girders.
For details of bridge approach slab, see Sheet No. B03-04.

(X) Denotes girder number

DETAILS OF END BENT NO. 5



Kaleb S. Hawk
9-11-25

DATE PREPARED 04/11/2025	
ROUTE 1-70	STATE MO
DISTRICT BR	SHEET NO. B03-11
COUNTY JACKSON	
JOB NO. J411486D	
CONTRACT ID. 240807-C01	
PROJECT NO.	


BRIDGE NO.
A9629

DATE	DESCRIPTION
04/11/25	REV 0 - RFC SUBMITTAL

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

 105 WEST CAPITOL
 JEFFERSON CITY, MO 65102
 1-888-ASK-MODOT (1-888-275-6636)

CLARKSON RADMACHER JOINT VENTURE
 715 KIRK DRIVE
 KANSAS CITY, MO 64105-1310
 CERTIFICATE OF AUTHORITY
 NO. 001270



FRAMING PLAN


Released For Construction
 Not to Scale
 Revision: 0.0
 Date: 04/11/2025
 Package: BRD-03-25th_ST_PED

Notes:
 Longitudinal dimensions shown are horizontal.
 All bents are parallel.


FRAMING PLAN

(1) Fabricator shall apply a bond breaker to the region.

(2) Outer strands tensioned to 2.02 kips/strand and inner strands to 8 kips/strand. Placed symmetrical about \bar{C} Girder. May be moved laterally in pairs.




DIMENSIONS




STRAND ARRANGEMENT


- + Indicates prestressing strand.
- ▲ Indicates strands debonded 3'-0" from each end of girder.
- ⊕ Indicates cut & shop bend with 3'-0" projection.



STRANDS AT GIRDER ENDS



LEFT EXTERIOR GIRDER AT INTERMEDIATE BENT



EXTERIOR GIRDER AT END BENT TOP FLANGE BLOCKOUT

Bill of Reinforcing Steel - Each Girder

No.	Size/Mark	Length	Shape	Bending Diagrams
C	5 B1	4'-4"	11S	
D	4 D1	4'-0"	9S	
2	4 G3	3'-10 1/4"	20	
2	4 G4	2'-3"	20	
2	4 G5	2'-8"	20	

Welded Wire Reinforcement - Each Girder




TABLE OF DIMENSIONS

Span No.	Girder No.	Bent No.	A	B	C	D
1-2	1 and 2	1	16 1/2"	---	74	94
1-2	1 and 2	2	11"	9"	---	---
4-5	1 and 2	4	7"	5 1/2"	66	86
4-5	1 and 2	5	20"	---	---	---

All dimensions are out to out.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Actual bar lengths are measured along centerline of bar to the nearest inch.

Minimum clearance to reinforcing shall be one inch.

All bar reinforcement shall be Grade 60

The two D1 bars may be furnished as one bar at the fabricator's option.

All B1 bars shall be epoxy coated.

Half no. of G3, G4 and G5 not required for ext. girders of end spans.

General Notes:

Concrete for prestressed girders shall be Class A-1 with $f'c = 10000$ psi and $f'ci = 7500$ psi.

Use 8 strands, 0.6"Ø Grade 270, with an initial prestress force of 352 kips.


Pretensioned members shall be in accordance with Sec 1029.

Fabricator shall be responsible for location and design of lifting devices.


The contractor shall provide bracing necessary for lateral and torsional stability of the girders during construction of the concrete slab and remove the bracing after the slab has attained 75% design strength. Contractor shall not drill holes in the girders.

For Girder Camber Diagram, see Sheet No. B03-15.


For location of coil ties at concrete diaphragms and integral bents, see Sheets No. B03-05, B03-09 and B03-14.



HALF ELEVATION



BEARING PLATE



COIL TIES

Exclude coil tie at exterior face of exterior girders except at integral end bents.

(3) 12" at exterior face of exterior girders at end bents


Detailed DEC 2024
Checked JAN 2025

Note: This drawing is not to scale. Follow dimensions.

Sheet No. B03-12 of B03-28

NU-GIRDERS - SPANS (1-2) & (4-5)

Released For Construction
Not to Scale
Revision: 0.0
Date: 04/11/2025
Package: BRD-03-25th_ST_PED



DATE PREPARED: 04/11/2025

ROUTE: I-70 STATE: MO

DISTRICT: BR SHEET NO.: B03-12

COUNTY: JACKSON

JOB NO.: J411486D

CONTRACT ID.: 240807-C01

PROJECT NO.:

BRIDGE NO.: A9629

DESCRIPTION

REV 0 - REF SUBMITTAL

DATE: 04/11/25

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION


105 WEST CAPITOL JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

CLARKSON RADMACHER JOINT VENTURE


715 KIRK DRIVE KANSAS CITY, MO 64105-1310
CERTIFICATE OF AUTHORITY NO. 001270

(1) Fabricator shall apply a bond breaker to this region.

(2) Outer strands tensioned to 2.02 kips/strand and inner strands to 8 kips/strand. Placed symmetrical about \bar{C} Girder. May be moved laterally in pairs.




DIMENSIONS




STRAND ARRANGEMENT

+ Indicates prestressing strand. ○ Indicates cut & shop bend with 3'-0" projection.



STRANDS AT GIRDER ENDS



LEFT EXTERIOR GIRDER AT INTERMEDIATE BENT Rotate 180° for right ext.

Bill of Reinforcing Steel - Each Girder

No.	Size/Mark	Length	Shape	Bending Diagrams
C	5 B1	4'-4"	11S	16 1/2" Shape 20
D	4 D1	4'-0"	9S	5" Shape 9S
2	4 G4	2'-3"	20	2'-2" Shape 11S
2	4 G5	2'-8"	20	9 1/2" Shape 11S

Welded Wire Reinforcement - Each Girder




TABLE OF DIMENSIONS

Span No.	Girder No.	Bent No.	A	B	C	D
2-3	1 and 2	2	7 1/2"	5 1/2"	134	154
2-3	1 and 2	3	9"	11"		
3-4	1 and 2	3	7 1/2"	5 1/2"	118	138
3-4	1 and 2	4	9"	11"		

All dimensions are out to out.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Actual bar lengths are measured along centerline of bar to the nearest inch.

Minimum clearance to reinforcing shall be one inch.

All bar reinforcement shall be Grade 60

The two D1 bars may be furnished as one bar at the fabricator's option.

All B1 bars shall be epoxy coated.

G3 not required for exterior girders of intermediate spans.

General Notes:

Concrete for prestressed girders shall be Class A-1 with f'c = 10000 psi and f'ci = 7500 psi.

Use 32 strands, 0.6"Ø Grade 270, with an initial prestress force of 1406 kips


Pretensioned members shall be in accordance with Sec 1029.

Fabricator shall be responsible for location and design of lifting devices.

For Girder Camber Diagram, see Sheet No. B03-15.


For location of coil ties at concrete diaphragms and integral bents, see Sheet No. B03-14.

The contractor shall provide bracing necessary for lateral and torsional stability of the girders during construction of the concrete slab and remove the bracing after the slab has attained 75% design strength. Contractor shall not drill holes in the girders.




HALF ELEVATION

Reinforcement support strands not shown for clarity.




SECTION A-A

Strands not shown for clarity.




SECTION B-B

Strands not shown for clarity.




BEARING PLATE



COIL TIES

Exclude coil tie at exterior face of exterior girders except at integral end bents.

Released For Construction
Not to Scale
Revision: 0.0
Date: 04/11/2025
Package: BRD-03-25th_ST_PED



Kaleb S. Hawk
9-11-25



DATE PREPARED
04/11/2025


ROUTE 1-70 STATE MO
DISTRICT BR SHEET NO. B03-13

COUNTY JACKSON
JOB NO. J411486D
CONTRACT ID. 240807-C01
PROJECT NO.

BRIDGE NO. A9629

DATE	DESCRIPTION
04/11/25 <td>REV 0 - RFC SUBMITTAL</td>	REV 0 - RFC SUBMITTAL





Kaleb S. Hawk
9-11-25

DATE PREPARED 04/11/2025	
ROUTE 1-70	STATE MO
DISTRICT BR	SHEET NO. B03-14
COUNTY JACKSON	
JOB NO. J411486D	
CONTRACT ID. 240807-C01	
PROJECT NO.	


BRIDGE NO. A9629

DATE	DESCRIPTION
04/11/25	REV 0 - RFC SUBMITTAL


MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
 105 WEST CAPITOL JEFFERSON CITY, MO 65102
 1-888-ASK-MODOT (1-888-275-6636)

CLARKSON RADMACHER JOINT VENTURE
 715 KIRK DRIVE KANSAS CITY, MO 64105-1310
 CERTIFICATE OF AUTHORITY NO. 001270


HNTB




SECTION NEAR INTERMEDIATE BENT




END DETAIL




SECTION B-B



EDGE DETAIL




ELEVATION C-C



SECTION A-A

Notes:
 Diaphragms shall be built vertical.
 For location of #5 Strand Tie Bars, see Sheets No. B03-12 thru B03-13.
 For location of coil ties, see Sheets No. B03-12 thru B03-13.
 For Bearing Details, see Sheet No. B03-08.
 For Bent Details for cap beam step geometry, bearing location, dowel placement, shear key details, roofing felt details, joint filler details, and notes not shown here, see Sheet No. B03-08.

Released For Construction
 Not to Scale
 Revision: 0.0
 Date: 04/11/2025
 Package: BRD-03-25th_ST_PED



Kaleb S. Hawk
9-11-25

DATE PREPARED 04/11/2025	
ROUTE 1-70	STATE MO
DISTRICT BR	SHEET NO. B03-15
COUNTY JACKSON	
JOB NO. J411486D	
CONTRACT ID. 240807-C01	
PROJECT NO.	


BRIDGE NO.
A9629

DATE	DESCRIPTION
04/11/25	REV 0 - RFC SUBMITTAL

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

 105 WEST CAPITOL
 JEFFERSON CITY, MO 65102
 1-888-ASK-MODOT (1-888-275-6636)

CLARKSON RADMACHER
 JOINT VENTURE
 715 KIRK DRIVE
 KANSAS CITY, MO 64105-1310
 CERTIFICATE OF AUTHORITY
 NO. 001270




Girder	Span (1-2)			Span (2-3)			Span (3-4)			Span (4-5)		
	A	B	C	A	B	C	A	B	C	A	B	C
1	1/4"	3/8"	1/4"	2 1/2"	4 3/8"	2 7/8"	2 3/4"	3 5/8"	2 1/2"	1/4"	1/4"	1/8"
2	1/4"	3/8"	1/4"	2 1/2"	4 3/8"	2 7/8"	2 3/4"	3 5/8"	2 1/2"	1/4"	1/4"	1/8"

GIRDER CAMBER DIAGRAM

Conversion Factors for Girder Camber (Estimated at 90 days)

Span 2-3 & 3-4
 0.1 pt. = 0.314 x 0.5 pt.
 0.2 pt. = 0.593 x 0.5 pt.
 0.3 pt. = 0.813 x 0.5 pt.
 0.4 pt. = 0.952 x 0.5 pt.
 Span 1-2 & 4-5
 0.25 pt. = 0.7125 x 0.5 pt.



THEORETICAL SLAB HAUNCHING DIAGRAM

Released For Construction
 Not to Scale
 Revision: 0.0
 Date: 04/11/2025
 Package: BRD-03-25th_ST_PED


Notes:
 If girder camber is different from that shown in the camber diagram, in order to maintain minimum slab thickness, adjustment of the slab haunches, or a raise in grade uniformly throughout the structure shall be necessary.

CAMBER DIAGRAM & THEORETICAL SLAB HAUNCHING DIAGRAM

Theoretical Bottom of Slab Elevations at Centerline of Girder
(Prior to forming for slab)**

Girder Number	Span (1-2) (43'-6" C Brg. - C Brg.)										
	C Brg.	.25	.50	.75	C Brg.						
1	933.27	932.76	932.24	931.71	931.18						
2	933.15	932.64	932.12	931.59	931.06						
Girder Number	Span (2-3) (88'-6" C Brg. - C Brg.)										
	C Brg.	.10	.20	.30	.40	.50	.60	.70	.80	.90	C Brg.
1	931.11	930.73	930.35	929.95	929.55	929.13	928.70	928.25	927.80	927.33	926.86
2	930.99	930.61	930.23	929.83	929.43	929.01	928.58	928.13	927.68	927.21	926.74
Girder Number	Span (3-4) (76'-6" C Brg. - C Brg.)										
	C Brg.	.10	.20	.30	.40	.50	.60	.70	.80	.90	C Brg.
1	926.79	926.45	926.10	925.75	925.40	925.03	924.66	924.29	923.90	923.51	923.12
2	926.67	926.33	925.98	925.63	925.28	924.91	924.54	924.17	923.78	923.39	923.00
Girder Number	Span (4-5) (35'-6" C Brg. - C Brg.)										
	C Brg.	.25	.50	.75	C Brg.						
1	923.05	922.62	922.20	921.77	921.34						
2	922.93	922.50	922.08	921.65	921.22						


**Elevations are based on a constant slab thickness of 6.5" and include allowance for theoretical dead load deflections due to weight of slab (including pedestrian curb and decorative pedestrian fence).



TYPICAL SLAB ELEVATIONS DIAGRAM

Released For Construction
Not to Scale
Revision: 0.0
Date: 04/11/2025
Package: BRD-03-25th_ST_PED

THEORETICAL BOTTOM OF SLAB ELEVATIONS



Kaleb S. Hawk
9-11-25

DATE PREPARED	04/11/2025
ROUTE	1 - 70
STATE	MO
DISTRICT	BR
SHEET NO.	B03-16
COUNTY	JACKSON
JOB NO.	J411486D
CONTRACT ID.	240807-C01
PROJECT NO.	
BRIDGE NO.	A9629



DATE	DESCRIPTION
04/11/25	REV 0 - RFC SUBMITTAL

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

CLARKSON RADMACHER JOINT VENTURE

715 KIRK DRIVE
KANSAS CITY, MO 64105-1310
CERTIFICATE OF AUTHORITY
NO. 001270




TOP REINFORCEMENT

Released For Construction
Not to Scale

Revision: 0.0
Date: 04/11/2025
Package: BRD-03-25th_ST_PED

Notes:
Work this sheet with Sheet No. B03-18.
For Typical Section and Slab Pouring Sequence, see Sheet No. B03-19.
For Pedestrian Curb Details, see Sheet No. B03-20.
For Camber Diagram and Theoretical Slab Haunching Diagram, see Sheet No. B03-15.
For Theoretical Bottom of Slab Elevations, see Sheet No. B03-16.
Longitudinal slab dimensions are measured horizontally.
For Light Blister Reinforcing and Details, see Sheet No. B03-21.

SLAB PLAN SHOWING TOP REINFORCEMENT



04-11-2025

DATE PREPARED 04/11/2025	
ROUTE 1-70	STATE MO
DISTRICT BR	SHEET NO. B03-17
COUNTY JACKSON	
JOB NO. J411486D	
CONTRACT ID. 240807-C01	
PROJECT NO.	

BRIDGE NO.
A9629



DATE	DESCRIPTION
04/11/25	REV 0 - RFC SUBMITTAL

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

CLARKSON RADMACHER JOINT VENTURE

715 KIRK DRIVE
KANSAS CITY, MO 64105-1310
CERTIFICATE OF AUTHORITY
NO. 001270



BOTTOM REINFORCEMENT

STATE OF MISSOURI
 BENJAMIN LICHTY
 NUMBER PE-2023038803
 PROFESSIONAL ENGINEER
Benjamin Lichty
 04-11-2025
 DATE PREPARED
 04/11/2025
 ROUTE 1-70 STATE MO
 DISTRICT BR SHEET NO. B03-18
 COUNTY JACKSON
 JOB NO. J411486D
 CONTRACT ID. 240807-C01
 PROJECT NO.
 BRIDGE NO. A9629

DATE	DESCRIPTION
04/11/25	REV 0 - RFC SUBMITTAL

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
 MoDOT
 105 WEST CAPITOL JEFFERSON CITY, MO 65102
 1-888-ASK-MODOT (1-888-275-6636)

CLARKSON RADMACHER
 JOINT VENTURE
 715 KIRK DRIVE
 KANSAS CITY, MO 64105-1310
 CERTIFICATE OF AUTHORITY NO. 001270
HNTB

Released For Construction
 Not to Scale
 Revision: 0.0
 Date: 04/11/2025
 Package: BRD-03-25th_ST_PED

Notes:
 Work this sheet with Sheet No. B03-17.

SLAB PLAN SHOWING BOTTOM REINFORCEMENT



04-11-2025

DATE PREPARED
04/11/2025

ROUTE 1-70 STATE MO
DISTRICT BR SHEET NO. B03-19

COUNTY JACKSON

JOB NO. J411486D

CONTRACT ID. 240807-C01


PROJECT NO.

BRIDGE NO. A9629



DATE	DESCRIPTION
04/11/25 <td>REV 0 - RFC SUBMITTAL</td>	REV 0 - RFC SUBMITTAL

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)


CLARKSON RADMACHER JOINT VENTURE
715 KIRK DRIVE KANSAS CITY, MO 64105-1310
CERTIFICATE OF AUTHORITY NO. 001270
HNTB




TYPICAL SECTION



DETAIL A
(High side of slab)




DETAIL B
(Low side of slab)



HAUNCH REINFORCING DETAIL
(Prestressed Girders)

*** Contractor shall provide #4 Bars and #4 S-Bars as necessary where the haunch exceeds 4 inches measured at centerline of girder. See Theoretical Slab Haunching Diagram on Sheet No. B03-15 for haunch thickness.



SLAB CONSTRUCTION JOINT

	Sequence of Pours				Min. Rate of Pour Cu. Yds./Hr.
	Direction				
Basic Sequence	4 End to 3	3 4 to 2	2 3 to 1	1 2 to End	25
Alternate pours to the basic sequence are subject to the approval of the engineer in accordance with Sec 703.					
Alternate A Pours	4+3 End to 2	2 3 to 1	1 2 to End		25
Alternate B Pours	4 + 3 End to 2		2 + 1 3 to End		25
Alternate C Pours	4 + 3 + 2 + 1 End to End				25

The contractor shall furnish an approved retarder to retard the set of the concrete to 2.5 hours, and shall pour and satisfactorily finish the slab pours at the rate given.



The concrete diaphragm at the intermediate bent and integral end bents shall be poured a minimum of 30 minutes and a maximum of 2 hours before the slab is poured.

SLAB POURING SEQUENCE

Notes:
For Plan of Slab Showing Top and Bottom Reinforcement, see Sheets No. B03-17 and B03-18.
For reinforcement of Pedestrian Curb not shown, see Sheet No. B03-20.
For Details of Conduit System of Structure, see Sheet No. B03-23.
For Decorative Pedestrian Fence Details, see Sheet No. B03-22.

Released For Construction
Not to Scale
Revision: 0.0
Date: 04/11/2025
Package: BRD-03-25th_ST_PED


SLAB DETAILS




ELEVATION OF PEDESTRIAN CURB
(Left curb shown, right curb similar)
Longitudinal dimensions are horizontal and measured along the outside of slab.

*Right pedestrian curb only.


4-#4 U1-bars @ 12" Centered at Light Pole Locations




U1-BAR DETAIL AT LIGHT POLE
(At light locations, U1-Bars to be used in lieu of #4 U-bars shown in Section B-B)




ALTERNATE CURB REINFORCING DETAIL
(Alt for Section B-B shown, alt for Section A-A similar)




PART ELEVATION OF PEDESTRIAN CURB



PLASTIC WATERSTOP DETAIL
Plastic waterstop shall be placed in all pedestrian curb filled joints, except structures with superelevation, use on lower joints only.



SECTION A-A



SECTION B-B


Use a minimum lap of 2'-7" for #4 horizontal curb bars.

PART ELEVATION AT CURB JOINT

Notes:

- Conventional forming shall be used for all pedestrian curb.
- Locating and pre-setting fence post u-bolts with tack welded #4 bars prior to slab pour is recommended.
- Top of curb shall be built parallel to grade and curb joints (except at end bents) normal to grade.
- All exposed edges of pedestrian curb shall have either a 1/2-inch radius or a 3/8-inch bevel, unless otherwise noted.
- Concrete in the pedestrian curb shall be Class B-1.
- Center of posts shall clear curb joints or ends by at least 6 inches.
- Slab reinforcement not shown for clarity.
- For details of decorative pedestrian fence not shown, see Sheet No. B03-22.
- For details of Decorative Lighting, see Lighting plans.

PEDESTRIAN CURB DETAILS



Benjamin Lichty
04-11-2025

DATE PREPARED
04/11/2025

ROUTE 1-70 STATE MO
DISTRICT BR SHEET NO. B03-20

COUNTY JACKSON
JOB NO. J411486D
CONTRACT ID. 240807-C01
PROJECT NO.

BRIDGE NO. A9629

DATE	DESCRIPTION
04/11/25	REV 0 - RFC SUBMITTAL


MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)


CLARKSON RADMACHER JOINT VENTURE

715 KIRK DRIVE KANSAS CITY, MO 64105-1310
CERTIFICATE OF AUTHORITY NO. 001270

Released For Construction
Not to Scale
Revision: 0.0
Date: 04/11/2025
Package: BRD-03-25th_ST_PED



LIGHT POLE PART ELEVATION



SECTION A-A

Released For Construction
Not to Scale
Revision: 0.0
Date: 04/11/2025
Package: BRD-03-25th_ST_PED

Notes:
 Base plate provided by light pole manufacturer.
 All base plates, U-bolts, hex nuts and washers shall be galvanized in accordance with ASTM A123 and Sec 1081.
 All light poles shall be vertical.
 Grout shall be placed under the post base plates in accordance with Sec 1066.
 U-bolts shall be ASTM F1554 Grade 36.
 For locations of lights, see Sheet No. B03-17.
 For details of pedestrian curb, see Sheet No. B03-20.
 For details of decorative pedestrian fence at light locations, see Sheet No. B03-22.
 Locating and pre-setting u-bolts with tack welded #4 bars prior to slab pour is recommended.
 *Bars can be field cut to place around slab #4-U-bars. In this case, galvanization at cut locations shall be repaired per Sec 1081. Additional #4x18" galvanized bar shall be lapped with each cut bar.
 **Dimensions based on assumed bolt circle of 8 5/8". Contractor shall confirm dimensions with light pole supplier.

LIGHT ANCHORAGE DETAILS



Benjamin Lichty
04-11-2025

DATE PREPARED
04/11/2025

ROUTE 1-70 STATE MO

DISTRICT BR SHEET NO. B03-21

COUNTY JACKSON

JOB NO. J411486D

CONTRACT ID. 240807-C01

PROJECT NO.

BRIDGE NO. A9629

DATE	DESCRIPTION
04/11/25	REV 0 - RFC SUBMITTAL

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
 105 WEST CAPITOL JEFFERSON CITY, MO 65102
 1-888-ASK-MODOT (1-888-275-6636)

CLARKSON RADMACHER JOINT VENTURE
 715 KIRK DRIVE KANSAS CITY, MO 64105-1310
 CERTIFICATE OF AUTHORITY NO. 001270



Notes:

These details are a general representation of a Decorative Pedestrian Fence. The actual fence components and component positions may be different than what is shown.

Fence shall have a gloss black finish (Federal Standard #17038). See special provisions.

Base plate shall be ASTM A709, Grade 50.

All base plates, U bolts, hex nuts and washers shall be galvanized in accordance with ASTM A123 and Sec 1081.

All fence posts shall be vertical.

Grout shall be placed under the post base plates in accordance with Sec 1066.

Decorative pedestrian fencing shall be in accordance with 2020-AASHTO LRFD Bridge Design Specifications, 9th Ed.

Shop drawings and structural calculations will not be required for the decorative pedestrian fences on the Bridge Pre-qualified Products List.

All materials used in fabrication and construction of the decorative pedestrian fencing shall be in accordance with the manufacturer's specifications, except as modified in the contract documents.

Decorative pedestrian fencing system shall be supplied by only one manufacturer. Decorative pedestrian fencing system shall include all components except the anchor bolts and hardware, and #4 bars welded to the rails and the anchor bolts. The assembly of the pickets to the rails and the rails to the posts shall be the same as the style mentioned for the manufacturer.

See Bridge Pre-qualified Products List (BPPL) for a list of approved manufacturers.

Substitution for the U-bolt cages will not be permitted.


U-bolts shall be ASTM F1554 Grade 36.

For details of pedestrian curb, see Sheet No. B03-20.


Longitudinal dimensions of fence are horizontal.

Locating and pre-setting fence post u-bolts with tack welded #4 bars prior to slab pour is recommended.


* Bars can be field cut to place around slab #4-U-bars. In this case, galvanization at cut locations shall be repaired per Sec 1081. Additional #4x18" galvanized bar shall be lapped with each cut bar.



TYPICAL PART ELEVATION




PART PLAN SHOWING BASE PLATE



SECTION A-A

1/2-inch diameter hole in base plate not shown for clarity.



TYPICAL DETAIL OF FENCE AT LIGHT STANDARDS



Benjamin Lichty
04-11-2025

DATE PREPARED
04/11/2025

ROUTE 1-70 STATE MO

DISTRICT BR SHEET NO. B03-22

COUNTY JACKSON

JOB NO. J411486D

CONTRACT ID. 240807-C01

PROJECT NO.

BRIDGE NO. A9629

DATE	DESCRIPTION
04/11/25 <td>REV 0 - RFC SUBMITTAL</td>	REV 0 - RFC SUBMITTAL


MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
MoDOT
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

CLARKSON RADMACHER JOINT VENTURE
715 KIRK DRIVE
KANSAS CITY, MO 64105-1310
CERTIFICATE OF AUTHORITY
NO. 001270




Released For Construction
Not to Scale
Revision: 0.0
Date: 04/11/2025
Package: BRD-03-25th_ST_PED


DECORATIVE PEDESTRIAN FENCE DETAILS




PLAN OF CONDUIT SYSTEM



DETAIL A



PART SECTION A-A




PART WINGWALL ELEVATION

Released For Construction
Not to Scale

Revision: 0.0
Date: 04/11/2025
Package: BRD-03-25th_ST_PED

Notes:
 All conduit shall be rigid non-metallic schedule 40 heavy wall PVC (polyvinyl chloride plastic) with 3" minimum cover in concrete. Each section of conduit shall bear the Underwriters laboratories (UL) label.
 Shift reinforcing steel in field where necessary to clear conduit and junction boxes.
 Expansion fittings shall be placed as shown and set in accordance with the manufacturer's requirements and based on the air temperature at the time of setting given an estimated total movement of 1 inch at filled joints using a maximum temperature range of 120°F and a maximum temperature of 110°F.
 All end bent junction boxes shall be PVC molded in accordance with Sec. 1062 and designed for flush mounting. The conduit terminations shall be permanent or separable. The terminations and covers shall be of watertight construction and shall meet requirements for NEMA 4X enclosure.
 Drainage shall be provided at low points or other critical locations of all conduits and all junction boxes in accordance with Sec 707. All conduits shall be sloped to drain where possible.

DETAILS OF CONDUIT SYSTEM ON STRUCTURE



04-11-2025

DATE PREPARED
04/11/2025

ROUTE 1-70 STATE MO
DISTRICT BR SHEET NO. B03-23

COUNTY JACKSON
JOB NO. J411486D
CONTRACT ID. 240807-C01
PROJECT NO.


BRIDGE NO. A9629

DATE	DESCRIPTION
04/11/25	REV 0 - RFC SUBMITTAL


MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
 105 WEST CAPITOL JEFFERSON CITY, MO 65102
 1-888-ASK-MODOT (1-888-275-6636)

CLARKSON RADMACHER JOINT VENTURE
 715 KIRK DRIVE KANSAS CITY, MO 64105-1310
 CERTIFICATE OF AUTHORITY NO. 001270

HNTB



DATE PREPARED 04/11/2025	
ROUTE 1-70	STATE MO
DISTRICT BR	SHEET NO. B03-24
COUNTY JACKSON	
JOB NO. J411486D	
CONTRACT ID. 240807-C01	
PROJECT NO.	
BRIDGE NO. A9629	



PART PLAN SHOWING PILE AND DRILLED SHAFT NUMBERING FOR RECORDING AS-BUILT PILE DATA AND AS-BUILT DRILLED SHAFT DATA

As-Built Pile Data					
Pile No.	Length in Place (ft)	PDA Nom. Axial Compressive Resistance (kips)	PDA End of Drive Blow Count (blows/in.)	Actual End of Drive Blow Count (blows/in.)	Remarks
					End Bent No. 1
1					
2					
3					
					End Bent No. 5
4					
5					
6					

As-Built Drilled Shaft Data				
Shaft No.	Top of Sound Rock (Elev.)	Tip of Casing (Elev.)	Bottom of Drilled Shaft (Elev.)	Remarks
				Intermediate Bent No. 2
1				
				Intermediate Bent No. 3
2				
				Intermediate Bent No. 4
3				

Note:
 Indicate in remarks column:
 A. Pile type and grade.
 B. Batter
 C. Driven to practical refusal
 D. PDA test pile
 E. Minimum tip elevation controlled
 (Use when actual blow count is less than PDA blow count due to minimum tip elevation requirement. A plus sign (+) shall be placed after the PDA nominal axial compressive resistance value indicating actual value is higher than PDA value.)

Released For Construction
 Not to Scale
 Revision: 0.0
 Date: 04/11/2025
 Package: BRD-03-25th_ST_PED

Note:
 This sheet to be completed by design-builder.

AS-BUILT PILE AND DRILLED SHAFT DATA

DATE	DESCRIPTION
04/11/25	REV 0 - RFC SUBMITTAL

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL JEFFERSON CITY, MO 65102
 1-888-ASK-MODOT (1-888-275-6636)

CLARKSON RADMACHER JOINT VENTURE

715 KIRK DRIVE
 KANSAS CITY, MO 64105-1310
 CERTIFICATE OF AUTHORITY
 NO. 001270



SOIL BORING NUMBER: 25Ped_B3_1

PROJECT Improve I 70 KC Design Build **NORTHING/EASTING** 1061103.2 / 2777688.1
DRILLING FIRM PPI **DRILLER** David Allen **DATE STARTED** 12/10/2024
LOGGED BY Pradip Adhikari **DATE COMPLETED** 12/10/2024
SURFACE ELEVATION 902.5' **RIG TYPE** CME-55
METHOD Water Rotary **TOOLING** 4-1/2" Continuous Flight Auger

Depth (ft)	Depth of Sample	Sample Type	Sample ID	Recovery Length (in)	Blow Counts (N-Value)	% Recovery	RQD (%)	Pocket Pen (tsf)	Graphic Log	Groundwater Data		Lab							
										During Drilling (ft):	N/A	Atterberg Limits (LL-PL-Pi)	Moisture Content (%)	Dry Density (PCF)	UCS (tsf)				
37.5 ft	38.5 ft		C-5			100													
40			C-6			100	96												
43.5																			
Bottom of Boring at 43.5' Boring backfilled with cuttings and patched with asphalt 12/10/2024																			

* Survey not possible due to boring location. Coordinates estimated from visual inspection. Elevation estimated from contour map.



SOIL BORING NUMBER: 25Ped_B4_1


PROJECT Improve I 70 KC Design Build **NORTHING/EASTING** 1061150.4 / 277772.1
DRILLING FIRM PPI **DRILLER** Josh Starkey **DATE STARTED** 12/18/2024
LOGGED BY Cameron Dupont **DATE COMPLETED** 12/18/2024
SURFACE ELEVATION 915.3' **RIG TYPE** CME-55LC
METHOD Water Rotary **TOOLING** 4-1/2" Continuous Flight Auger

Depth (ft)	Depth of Sample	Sample Type	Sample ID	Recovery Length (in)	Blow Counts (N-Value)	% Recovery	RQD (%)	Pocket Pen (tsf)	Graphic Log	Groundwater Data		Lab							
										During Drilling (ft):	N/A	Atterberg Limits (LL-PL-Pi)	Moisture Content (%)	Dry Density (PCF)	UCS (tsf)				
2.5																			
5	3.5 ft		J-1	14	5-10-16 (26)	78		>4.5											
5	5.3 ft		C-1	60		100	87												
10	10.3 ft		C-2	60		100	88												
15	15.3 ft		C-3	50		83	8												
20	20.3 ft		C-4	59		98	52												
25	25.3 ft		C-5	60		100	97												
30	30.3 ft		C-6	60		100	54												
35	35.3 ft		C-7	60		100	90												

Released For Construction
 Not to Scale
 Revision: 0.0
 Date: 04/11/2025
 Package: BRD-03-25th_ST_PED

Notes:
 For locations of borings, see Sheet No. B03-02 and Geotechnical Report.

BORING LOGS



DATE PREPARED 04/11/2025	
ROUTE 1 - 70	STATE MO
DISTRICT BR	SHEET NO. B03 - 27
COUNTY JACKSON	
JOB NO. J411486D	
CONTRACT ID. 240807 - C01	
PROJECT NO.	
BRIDGE NO. A9629	

DATE	DESCRIPTION
04/11/25	REV 0 - RFC SUBMITTAL

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
 JEFFERSON CITY, MO 65102
 1-888-ASK-MODOT (1-888-275-6636)

CLARKSON RADMACHER
 JOINT VENTURE

715 KIRK DRIVE
 KANSAS CITY, MO 64105-1310
 CERTIFICATE OF AUTHORITY
 NO. 001270

