

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	1	53

PROJ. NO. 078 C-5229-01
FED. AID PROJ. NO. STP-C522(901)


GRADING
BRIDGE
SEEDING
LTS

C1217

STATE OF KANSAS
DEPARTMENT OF TRANSPORTATION
PLAN AND PROFILE OF PROPOSED
RENO COUNTY
78 C-5229-01
FEDERAL AID PROJECT

INDEX OF SHEETS

1. TITLE SHEET
2. TYPICAL GRADING SECTION
3. PLAN AND PROFILE SHEET
4. SECTION CORNER MONUMENT
- 5-11. GUARDRAIL DETAILS
12. PIPE END SECTIONS
13. SUMMARY OF PIPE END SECTIONS
- 14-23. BRIDGE DETAILS
24. BRIDGE EXCAVATION
25. STANDARD PILE DETAILS
26. SUPPORTS AND SPACERS FOR REINFORCING STEEL
27. SUMMARY OF QUANTITIES
28. PROJECT SURFACING
- 29-37. TEMPORARY EROSION AND POLLUTION CONTROL
38. SEEDING
- 39-44. TRAFFIC CONTROL PLAN
- 45-50. CROSS SECTIONS
- 51-53. CHANNEL CROSS SECTIONS



*DESIGN DESIGNATION

AADT 40 2023
V 50 M.P.H.

*MEETS DESIGN CRITERIA OF
THE VERY LOW-VOLUME
LOCAL ROADS GUIDELINES.

CONVENTIONAL SIGNS

COUNTY LINE	-----	CENTER LINE OF PROJECT	-----
CITY LIMITS	=====	TERRACE	-----
STATE OR NATIONAL LINE	-----	CULVERTS	-----
TOWNSHIP, SECTION or GRANT LINE	-----	DROP INLET & STORM SEWER	-----
PROPERTY LINE	-----	ACCESS CONTROL	-----
HIGHWAY FENCE	-----	POWER POLE	-----
EXISTING FENCE	-----	TELEPHONE POLE	-----
GUARDRAIL	-----	MARSH	-----
CONSTRUCTION LIMITS	-----	HEDGE	-----
RIGHT OF WAY LINE	-----	TREES	-----
TRAVELED WAY	-----	PROFILE ELEVATION	-----
RAILROADS	-----	STREAM or CREEK	-----

GROSS LENGTH OF PROJECT 550.00 FT. (Includes Equations)

EXCEPTIONS

NET LENGTH OF PROJECT 550.00 FT. 0.104 MILES
NET LENGTH OF BRIDGES 162.90 FT. 0.031 MILES
NET LENGTH OF ROAD 387.10 FT. 0.073 MILES



Manhattan, KS 66502
Salina, KS 67401
Wichita, KS 67212
Topeka, KS 66606

RECOMMENDED FOR APPROVAL DATE

WABAUNSEE COUNTY PUBLIC WORKS




Approved: Sep 11, 2024
Date



By: M. D. Wil
State Transportation Engineer

By: Dawn Mphuska
Interim Chief, Bureau of Local Projects


KANSAS DEPARTMENT OF TRANSPORTATION



NOTE: For overbreakage in limestone, sandstone or shale see Special Provisions





SUPERELEVATED SECTION




PROFILE SHOWING METHOD OF ATTAINING SUPERELEVATION

Sta. P.I. Curve	Radius	Design Speed	Super %	Transition - (Lin.Ft.)		
				L	A	B




TYPICAL INTERSECTION DETAILS

SUMMARY OF INTERSECTIONS AND SIDEROADS												
STATION	SIDE OR QUADRANT	TYPE	W	W1	W2	W3	Rad. South	Rad. North	C	S	D	BS
38+37.50	Rt.	C		24'		24'	20'	25'	4 5/16"	Exist.	Exist.	Exist.



TYPICAL 1/2 SECTION SURFACING



TYPICAL SIDE ROAD OR ENTRANCE DETAIL

* On side roads and entrances which slope toward the roadway, construct a low point approx. 6" deep to divert surface drainage into the roadway ditch.

* On ditch plugs and side roads or entrances without drainage structures use 8 : 1 slopes where feasible.

GENERAL NOTES


All signs shown on the plans, and other signs furnished and installed by the LPA with their own forces and funds will be installed in conformance with the Manual on Uniform Traffic Control Devices (latest edition).

LPA to furnish all easements and additional right of way (unless otherwise noted).

Public and private utility facilities will be adjusted by others as needed to fit the new construction unless noted otherwise on the plans or in the proposal.

Refer to KDOT Standard Drawing No. BR 100 for excavation limits for constructing box culverts.

OBJECT MARKER



All Sign, Fastener, and Post materials must meet the requirements of the latest edition of the KDOT Standard Specifications for State Road and Bridge Construction.

Install Object Markers Type OM3-(R)(L) at each corner of all span bridges and when indicated on the plans at box structures. Install with the inside edge of the marker in line with the inside clearance line of the structure.

SUMMARY OF OBJECT MARKERS AND SIGNS						
STATION TO STATION	SIDE	TYPE OF STRUCT.	TYPE OF SIGN	OBJECT MARKER		REMARKS
				TYPE	NO.	
36+00	Rt.	Bridge		OM-3R	1	Type 3
36+14	Lt.	Bridge		OM-3L	1	Type 3
37+66	Rt.	Bridge		OM-3L	1	Type 3
37+80	Lt.	Bridge		OM-3R	1	Type 3
Ø As you face bridge end from approach					4	
*Back-to-Back [Sign(s) on Both Sides of Post]						

7	01-08-15	Revised superelevation diagram, updated misc. notes.	TLS	RJS
6	11-9-04	Changed 'Culvert' to 'Structure'	DMK	RJS
5	12-1-03	Rev. Detail/s/Add Typ. Sect./Changed OM notes	DMK	RJS
4	5-14-03	Rev. Contractor note in Gen. Notes	DMK	RJS
NO.		REVISIONS	BY	APP'D

KANSAS DEPARTMENT OF TRANSPORTATION				
TYPICAL GRADING SECTION				
LP907				
FHWA APPROVAL		APP'D.		
DESIGNED	DETAILED	TLS	QUANTITIES	RJS
DESIGN CK.	DETAIL CK.	RJS	TRACED	TRACE CK.

DATE	
BY	
REFERENCES NOTED	
REFERENCES CHECKED	

UTILITIES:
Pipeline - Phillips 66 Pipeline

Power - Ark Valley Electric COOP

Telephone - Brightspeed

- @P.O.T. Sta. 30+00.00
1. ½" bar with SE control cap 0.4' deep
2. 20d nail with bottle cap in top roof fence post
3. 20d nail with bottle cap in top wood fence post
4. Top center telephone pedestal
5. Centerline N-S. road

46.9' N.E.
47.3' S.E.
78.5' S.S.W.
0.0

Marlin A. & Karen A. Yoder, Trust
Tract of Land in
N.E. ¼ Sec. 28, T22S., R4W.

@Sta. 36+90.00 Construct
Br. No. 000780775005601
48'-64'-48' RCSH Cont. Spans
Bridge, Pile Bent Abuts. and
Piers, Skew 30° Rt.
with a 24'-0" Roadway

@Sta. 36+90 @Project =
Sta. 50+00 @Channel
Improvement

- @P.O.T. Sta. 42+00.00
1. ½" bar with SE control cap 0.3' deep
2. 20d nail with bottle cap in power pole
3. 20d nail with bottle cap in power pole
4. Top metal guy anchor
5. Centerline N-S. road

85.5' S.E.
81.0' S.W.
64.2' S.E.
0.0

@Sta. 37+00 Remove (Br. No.
000780775005600) 7 @ 19'
Timber Beam Spans Bridge (TBMS)
Skew 15° Rt. with a 23' Roadway.

Darrell, Marlin, Larry & James Regehr
Tract of Land in
S.E. ¼ Sec. 21, T22S., R4W.

@Sta. 39+50.00 END
KDOT Project No.
78 C-5229-01

NOTE:
Construct shoulder widening and install
Guardrail, Steel Plate and Guardrail.
See Sheet No. 5 for details.

Datum Bench Mark USGS JF0829 - USGS Brass Disk in the
Center of the East Headwall of a RCB along K-61, ¼ Mile
South of the intersection of K-61 and 69th Ave. and 40'
South of a driveway on the West Side of the highway.
Elev. = 1556.93

Horizontal Control
W. ¼ Cor. Sec. 27, T.22S., R.4W. = @Sta. 10+00.54, 19.24' Lt.,
N.W. Cor. Sec. 27, T.22S., R.4W. = @Sta. 36+60.06, 12.20' Lt.,
W. Cor. Sec. 22, T22S., R.4W. = @Sta. 62+99.11, 15.76' Lt.,
Project Centerline.

- W. ¼ Cor. Sec. 27, T.22S., R.4W. (@Sta. 10+00.54, 19.24' Lt.)
1. ⅝" Rebar found 0.4' deep
2. Mag nail in top of 8" corner fence post
3. Spike in top of fence corner post
4. Spike in top of fence post
5. Top center of a 4" metal brace post
6. In line of gravel road North South road

31.5' W.
31.7' E.
36.3' S.E.
33.6' E.N.E.
0.0

- N.W. Cor. Sec. 27, T.22S., R.4W. (@Sta. 36+60.09, 2.20' Lt.)
1. Mag nail and washer in the wood bridge deck
2. Mag nail in North face power pole
3. South end of wood bridge deck
4. 60D nail in S.S.E. face of cottonwood tree
5. North end of wood bridge deck
6. In line of gravel road North South road

80.5' S.S.E.
26.1' S.
37.8' S.W.
107.5' N.
0.0'

BM #9 R.R. Spike in N. face of power pole
29.95' Rt., @Sta. 35+86.45, Elev. = 1457.91

Little River Township
QCD
Book 150, Page 334

@Sta. 38+37 Extend
30" x 40' CRP (CSP)
12' South with End
Section. See Sh. No. 13

@Sta. 37+72 to @Sta. 38+08, Rt.
Construct Slope Protection
(Riprap Stone)
53 Cu. Yds.

JLR Family Farm LLC
Tract of Land in
S.W. ¼ Sec. 22, T22S., R4W.


- W. ¼ Cor. Sec. 22, T.22S., R.4W. (Sta. 62+99.11, 15.76' Rt.)
1. ⅝" Rebar 0.4' deep
2. South end of 24" corrugated metal pipe
3. North end of 24" corrugated metal pipe
4. Mag and nail in top corner fence post
5. "+" cut in the center East headwall

26.2' S.E.
27.7' N.E.
32.5' W.
305.3' S.S.E.

PLAN: Lat. & Long.
PROFILE: Horiz. same as above
Vert. _____

SCALE

50' 0 50' 100'



Drawn By : sallen
File : 003_PlanProfile50Scale.dgn
Plotted : 06-SEP-2024 10:25


NOTE: All disposal sites must be approved by the Kansas Department of Health
and Environment. Material either stockpiled or disposed of in a flood plain
would require a Kansas State Board of Agriculture permit. Any material
dumped in the waters of the United States or wetlands is subject to the
U.S. Corps of Engineers permitting regulations. Any material buried or
stockpiled beyond approved construction limits would require additional
archeological investigations, unless buried in a previously approved borrow
location.

Excavation shown to be wasted shall be wasted on sites provided by the
Contractor. These sites shall be approved by the Engineer as to suitability,
appearance, and site location. Location that in the opinion of the Engineer
will leave an unsightly appearance will not be approved.

Dt. Lt. Trans. 4' x Sp. Dt. Lt. No Dt. Lt. 4' x Sp. Dt. Lt. Trans. Dt. Lt.
Dt. Rt. Trans. 4' x Sp. Dt. Rt. No Dt. Rt. Var. x Sp. Dt. Exist. Dt. Rt. Trans. Dt. Rt.

*1154 cu. yds. Common Excavation (V.M.F. = 0.75)
348 cu. yds. Embankment

*Includes 752 cu. yds. from Channel Improvement
Lt. and Rt. of Sta. 36+90 and 690 cu. yds. to be
Wasted on Sites Provided by the Contractor and
approved by the Engineer.



KANSAS DEPARTMENT OF TRANSPORTATION
BR. VICTORY ROAD 27.01

PLAN AND PROFILE


STA. 33+00.00 TO STA. 39+50.00

BR. NO. 000780775005601

CADconform Certify This File

CADconform Certify This File

EXHIBIT		
2" DIA. PRE-STAMPED ALUMINUM CAPS		
KDOT - DISTRICT 1	KDOT - DISTRICT 2	KDOT - DISTRICT 3
KDOT - DISTRICT 4	KDOT - DISTRICT 5	KDOT - DISTRICT 6
KDOT STATE SURVEY CREW BUREAU OF RIGHT OF WAY	SURVEY COMPANY WITH A VALID CORPORATION LICENSE	INDEPENDENT SURVEYOR OR SOLE PROPRIETOR COMPANY



Use the proper identification cap for the party installing the monument, as shown on the exhibit.

Make all stampings, forgings, and impressions legible. The stampings, forgings, and impressions will properly identify the location of the monument within the Public Land Survey System (PLSS).

A "System of Marking" is available in the current "Manual of SURVEYING INSTRUCTION", which is published by the United States Department of the Interior, Bureau of Land Management.






Reset all PLSS corners in accordance with KDOT's Standard Specifications.

In addition to monumentation of the PLSS corner, the Engineer may direct or select specific locations for offset monumentation, as shown.

Use Type A-1 or Type A-2 monuments as directed by the Surveyor or the Engineer.


Type A monumentation may be used on a project as specified in the plans or as directed by the Engineer. Typically, Type A monuments are used on high traffic volume roadways, in urban areas, or as required by local governmental codes. Otherwise, use Types B-D monumentation. Avoid installing monument boxes in vehicle wheelpaths where practicable.

All work and materials required to install the Type A-1 and Type A-2 monument boxes will be paid under the bid item "Monument Box (Each)" and will be included in the plan quantities. All work and materials required to install Types B-D monumentation will be subsidiary to the bid item "Contractor Construction Staking (Lump Sum)". See KDOT's Standard Specifications for details.




04	08-24-18	Rev. Det. Mon. Box AND Rev. Gen. Note	A.L.R.	T.T.R.
03	01-15-16	Add. Det. Retrofit & Rev. Gen. Note	T.T.R.	S.W.K.
02	10-17-13	Revised Detail, Recessed Bar	S.W.K.	J.O.B.
NO.	DATE	REVISIONS	BY	APPD
KANSAS DEPARTMENT OF TRANSPORTATION				
SECTION CORNER MONUMENTATION DETAIL SHEET				
RD990				
FHWA APPROVAL		08-07-19	APPD.	Scott W. King
DESIGNED	DETAILED	QUANTITIES	TRACED	
DESIGN CK.	DETAIL CK.	QUAN. CK.	TRACE CK.	


Drawn By : bfranz
File : 005_lp620.dgn
Plotted : 10-JUN-2024 16:18




FLARED DESIGN - RUB RAIL (Layout 1)



FLARED DESIGN - THRIE BEAM (Layout 3)



PARALLEL DESIGN - RUB RAIL (Layout 2)



LAYOUT NORTHEAST QUADRANT

Offset Guardrail Post 3'-11/2" Lt. and Rt. Of P.T.
and drill holes in the Proposed Guardrail to attach
Proposed Guardrail to the two offset Guardrail Posts.
All labor, equipment and materials shall not be paid
for directly but shall be subsidiary to the Bid item
"Guardrail, Steel Plate".

ALLOWABLE END TERMINALS							
TYPE	Layout						Required Standard Drawing
	1	2	3	4	5	6	
<i>SRT</i>	X		X		X		<i>RD606</i>
<i>FLEAT</i>	X		X		X		<i>RD606</i>
<i>SKT</i>		X		X		X	<i>RD606</i>

SUMMARY OF STEEL PLATE GUARDRAIL											
Location (Quadrant)	Side	Layout		Additional Standard Sections Lin. Ft.	Total Pay Length Lin. Ft.	Layout 1 or 3			Layout 2, 4, or 6	Layout 5	
						Gd. Rail End Term. (SRT) Alt. #1 Each	Gd. Rail End Term. (FLEAT) Alt. #2 Each	Gd. Rail End Term. Type II Each	Gd. Rail. End Term. (SKT) Each	Gd. Rail End Term. (SRT) Alt. #1 Each	Gd. Rail End Term. (FLEAT) Alt. #2 Each
		No.	Lin. Ft.*								
Southeast	Rt.		25'-0"	25'-0"	25'-0"	1	1				
Southwest	Lt.		25'-0"	25'-0"	25'-0"	1	1				
Northeast	Rt.		25'-0"	53'-1½"	☉ 78'-1½"			1			
Northwest	Lt.		25'-0"	25'-0"	25'-0"	1	1				
TOTAL LENGTH					153'-1½"	3	3	(For Information Only)			

*See Guardrail Auxiliary Details (RD606) for Measurement Details.
Does Not Include End Terminal.

Includes 31.25 Lin. Ft. with a Bent Radius of 19.89'.

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	5	53

NOTE: Layouts 1, 2, 3, and 4 will be symmetric for any quadrant unless otherwise shown in the plans.

When using Rubrail, attach Std. Drawings No. RD611, RD616 and RD615 (parallel) or RD615A (flared).

When using Thrie beam, attach Std. Drawings no. RD611 and RD608 or RD613.

Attach Std. Drawing No. RD617 (parallel) or RD 617A (flared) for post over box less than full depth.

Radius = 625.08'

12	02-21-19	Updated per Road Memo 18-02	WFL	MJS
11	10-30-17	Removed X-Lite	WFL	MJS
10	01-06-15	Added X-Lite, Removed ET-PLUS	TLA	RJS
9	11-9-05	Added length for Thrie Beam transition	REA	RJS
NO.	DATE	REVISIONS	BY	APP'D
KANSAS DEPARTMENT OF TRANSPORTATION				
TYPICAL ALIGNMENT OF GUARDRAIL INSTALLATIONS				
LP620				
FHWA APPROVAL			APP'D.	
DESIGNED CK.			MJS	
DESIGN CK.			TRACED	
			TRACE CK.	





CADconform Certify This File

CADconform Certify This File

Note to Designer - Design guardrail installations using guidance shown on KDOT's 'Guardrail Typical Alignments' Standard Drawings. 'Flared' guardrail installations are preferred over 'Parallel' or 'Zero Flare' installations. Where 'Flared' or 'Parallel' installations are used, the flare rate of the guardrail end terminal typically matches the flare rate of the remaining guardrail installation. For 'Zero Flare' installations, 'Parallel' guardrail end terminals should be designed using typical flare rates of 50:1 or flatter for the length of the end terminal. However, while 50:1 or flatter flare rates are typical for 'Parallel' guardrail end terminals, these end terminals may be flared as steep as 26:1 or flatter in order to offset the end terminal head as far from the edge of the through traveled lane as practicable.

Plotted : 10-JUN-2024 16:18

Drawn By : bfranz
File : 006_rld606.dgn



MIDWEST GUARDRAIL SYSTEM (MGS) END TERMINALS									
END TERMINAL BID ITEM	FLARED OR PARALLEL	MOUNTING HEIGHT	CRASH TESTING CRITERIA	STEEL POST DESIGN AVAILABLE	WOOD POST DESIGN AVAILABLE	ENERGY ABSORBING	MANUFACTURER	DESIGN LENGTH	MANUFACTURER SYSTEM LENGTH
Guardrail End Terminal (MGS-FLEAT)	Flared	31"	NCHRP 350	Yes	Yes	Yes	Road Systems	40'-7½"	37'-6"
Guardrail End Terminal (MGS-SRT)	Flared	31"	NCHRP 350	Yes	Yes	No	Valtir	40'-7½"	37'-6"
Guardrail End Terminal (MGS-MSKT)	Parallel	31"	MASH	Yes	No	Yes	Road Systems	46'-10½"	46'-10½"
Guardrail End Terminal (MGS-SOFTSTOP)	Parallel	31"	MASH	Yes	No	Yes	Valtir	46'-10½"	50'-9½"

CONVENTIONAL GUARDRAIL SYSTEM (CGS) END TERMINALS									
END TERMINAL BID ITEM	FLARED OR PARALLEL	MOUNTING HEIGHT	CRASH TESTING CRITERIA	STEEL POST DESIGN AVAILABLE	WOOD POST DESIGN AVAILABLE	ENERGY ABSORBING	MANUFACTURER	DESIGN LENGTH	MANUFACTURER SYSTEM LENGTH
Guardrail End Terminal (FLEAT)	Flared	28"	NCHRP 350	Yes	Yes	Yes	Road Systems	37'-6"	37'-6"
Guardrail End Terminal (SRT)	Flared	28"	NCHRP 350	Yes	Yes	No	Valtir	37'-6"	37'-6"
Guardrail End Terminal (SKT)	Parallel	28"	NCHRP 350	Yes	Yes	Yes	Road Systems	50'-0"	50'-0"

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	6	53

GENERAL NOTES

Install the guardrail end terminals according to the Manufacturer's Installation Manual. The Contractor will furnish a copy of the Manufacturer's Installation Manual to the Engineer prior to the start of the installation.

Use approved steel (preferred) or wood posts provided by the Manufacturer. The guardrail end terminal post type may be independent of the post type used in the remainder of the installation. However, no mixing of post types is permitted in the remaining w-beam and thrie-beam installation.

Use approved polymer (preferred) or wood blockouts provided by the Manufacturer. The guardrail end terminal blackout size and type may be independent of the blackout size and type used in the remainder of the installation. For blackout size and types for the remaining w-beam and thrie-beam portion of the installation see the details shown on KDOT's 'Guardrail Post Details' and 'Guardrail Thrie-Beam Transition Details' Standard Drawings.

Apply retroreflective sheeting to the end terminal impact head before installation.

Tighten all cable anchor assemblies as per the Manufacturer's Installation Manual.

Lap w-beam and thrie-beam guardrail splices, in the direction of permanent traffic, even where temporary traffic may be carried in the opposite direction of the final traffic configuration. Lap end terminal splices per the Manufacturer's Installation Manual in the direction of permanent traffic, even where temporary traffic may be carried in the opposite direction of the final configuration.

The minimum length of w-beam guardrail required between the thrie-beam transition and the guardrail end terminal is 12'-6" for all installations; unless otherwise stated in the Manufacturer's Installation Manual.





Where pavement with a thickness less than or equal to 8" is encountered during installation, use the details shown on KDOT's 'Guardrail Post Details' Standard Drawings to provide openings in the pavement for the guardrail posts. Where pavement with a thickness greater than 8" or geologic rock is encountered during installation, follow the Manufacturer's Installation Manual for guidance. Where the Manufacturer's Installation Manual does not address pavement with a thickness greater than 8" or geologic rock, contact the manufacturer for instructions or install the guardrail posts as directed by the Engineer.

All work and materials required for w-beam and thrie-beam guardrail installations are paid for under the appropriate bid items for either CGS or MGS guardrail depending on the type of installation.

All work and materials required for guardrail end terminal installations are paid for under the bid item for the selected guardrail end terminal. See the table on this sheet for the appropriate end terminal bid item information.


02	09-05-18	ADD. OMITTED POST AND TRANS. DETAILS	A.L.R.	T.T.R.
01	06-05-18	INITIAL RELEASE	A.L.R.	T.T.R.
NO.	DATE	REVISIONS	BY	APPD
KANSAS DEPARTMENT OF TRANSPORTATION				
GUARDRAIL AUXILIARY DETAILS				
RD606				
FHWA APPROVAL 09-25-18 APPD. Scott W. King				
DESIGNED	DETAILED	QUANTITIES	TRACED	
DESIGN CK.	DETAIL CK.	QUAN. CK.	TRACE CK.	

Drawn By : bfranz
File : 007_rd611.dgn
Plotted : 10-JUN-2024 16:18



- ☑ Slurry Grout (Low Strength). See
KDOT's Standard Specifications
- ⊗ Diameter may vary from 1'-6" (min.)
to 2'-0".


BOLT SIZE SCHEDULE	
Bolt	L
A	8 ½"
B	1 ¼"
C	18"




13	09-05-18	Added Det., Post In Pavement	A.L.R.	T.T.R.
12	12-14-10	Revised notes, 28' w-be	S.W.K.	J.O.B.
11	06-30-04	Remove steel blackout and notes	S.W.K.	J.O.B.
NO.	DATE	REVISIONS	BY	APP'D
KANSAS DEPARTMENT OF TRANSPORTATION				
<h1 style="text-align: center;">GUARDRAIL POST DETAILS</h1>				
RD611				
FHWA APPROVAL		09-25-18	APP'D.	Scott. W. King
DESIGNED	DETAILED	QUANTITIES	TRACED	
DESIGN CK.	DETAIL CK.	QUAN. CK.	TRACE CK.	

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	7	53

⊗ See Standard Drawing RD613 for Thrie-Beam Transition Section Details.



Note: All holes $1\frac{3}{16}$ " dia.



Note: All holes $^{13}/_{16}$ " dia.

☆ Non-Metallic (Polymer) or
Treated Wood Block

Give all wood posts and wood blocks a preservative treatment, see standard specifications. Thoroughly saturate all cuts, injuries and bolt holes on wood posts and blocks with preservative. Use only one type of preservative treatment on a project. Use SAS rectangular posts and wood blocks, see standard specifications. Use only one post/blockout type within guardrail run, this excludes the the guardrail end terminals. Set guardrail posts by digging or by driving. Use post caps to protect the post from crushing during driving operations. Contractor must notify Engineer at the earliest time when a non-removable manmade object (footing, pipe, etc.) is encountered and prevents installation of a full length post. Contractor must obtain Engineer approval prior to cutting post shorter than 6'-6". Approved polymer blockouts may be substituted for wood blockouts. Only one type of blockout is permitted on each guardrail installation. This excludes the guardrail end terminals unless certified by the manufacturer. All dimensions are nominal and are subject to manufacturing tolerances. Excavation including rock, shale, and other materials for erection of Guardrail is subsidiary to various bid items for which payment is made. Where guardrail posts are installed in pavement, form openings in the pavement for the guardrail posts.


Use grade of steel for steel posts that meets the requirements of the standard specifications. Hot dip galvanize the posts after fabrication, see standard specifications. Use only one post/blockout type within guardrail run, this excludes the guardrail end terminals. For wood/polymer blockout requirements see standard specifications. Approved polymer blockouts may be substituted for wood blockouts. Only one type of blockout is permitted on each guardrail installation. This excludes the guardrail end terminals. Set guardrail posts by digging or by driving. Use post caps to protect the post from crushing during driving operations. Contractor must notify Engineer at the earliest time when a non-removable manmade object (footing, pipe, etc.) is encountered and prevents installation of a full length post. Contractor must obtain Engineer approval prior to cutting post shorter than 6'-6" except as allowed on Standard Drawing RD617. All dimensions are nominal and are subject to manufacturing tolerances. Excavation including rock, shale, and other materials for erection of Guardrail is subsidiary to various bid items for which payment is made. Where guardrail posts are installed in pavement, form openings in the pavement for the guardrail posts.

Galvanize all bolts, nuts, and washers in accordance with the KDOT's Standard Specifications.


Notes to Designer: Guardrail length of need shall be determined in accordance with the AASHTO Roadside Design Guide using $L_1 = 25'$ for flare rate of a:b and $L_1 = 12.5'$ for flare rate of 2a:b for a typical installation as shown on this sheet. This sheet shall be used when the flared guardrail design for typical layout shown (FLEAT or SRT) is selected. Material for asphalt widening shall be included in the plan quantities.

Plotted : 10-JUN-2024 16:18

Drawn By : bfranz
File : 008_rdb15a.dgn




TWO LANES



FOUR LANES - DIVIDED


- ✱ See table on this sheet for radius and flare rate.
- ▲ Normal project side slope. See typical sections.
- ◆ See KDOT's 'Guardrail Auxiliary Details' Standard Drawing.
- ψ 4" Asphalt material placed on 4'-0" embankment widening unless flume inlet and slope drain is constructed.

DESIGN PARAMETERS				
Design Speed (mph)	Flare Rate (a:b)	Radius (R)	Flare Rate (2a:b)	Radius (R)
70	15:1	375.55'	30:1	375.14'
60	14:1	350.59'	26:1	325.16'
55	12:1	300.69'	24:1	300.17'
50	11:1	275.76'	21:1	262.70'
45	10:1	250.83'	18:1	225.23'
40	8:1	201.04'	16:1	200.26'




ALTERNATE TREATMENT - TWO LANES


Flare Rate = 2a:b
(GUARDRAIL LENGTHS OF 62.5' AND 75')




PLAN VIEW TWO LANE



DETAILS OF GUARDRAIL PROTECTION AT ROADSIDE OBSTACLE




PLAN VIEW FOUR LANE




ENLARGEMENT - AREA OF CONCERN

08	06-05-18	Removed Flare-beyond-the-Flare	A.L.R.	T.T.R.
07	05-15-17	Removed X-LITE	A.L.R.	S.W.K.
06	07-02-09	Added roadside obstacle details	S.W.K.	J.O.B.
NO.	DATE	REVISIONS	BY	APPD
KANSAS DEPARTMENT OF TRANSPORTATION				
W-BEAM WITH RUBRAIL BRIDGE APPROACH TRANSITION TYPICAL ALIGNMENTS (FLARED)				
RD615A				
FHWA APPROVAL		06-19-18	APPD. Scott W. King	
DESIGNED	DETAILED	QUANTITIES	TRACED	
DESIGN CK.	DETAIL CK.	QUAN.CK.	TRACE CK.	


STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	9	53




PLAN




ELEVATION




TYPICAL END RUB RAIL DETAILS



SECTION A-A




SECTION B-B




SECTION C-C

WOOD POSTS


* See Standard Drawing RD611 for details of Bolts A, & C.



SECTION A-A




SECTION B-B




SECTION C-C

STEEL POSTS


⊗ Blocks used with steel posts shall be grooved to fit over the flange of the post and may be Wood or Polymer.




PLAN OF RUBRAIL ON WOOD POSTS




PLAN OF RUBRAIL ON STEEL POSTS




SHOP WELDED OPTION




SHOP BENT OPTION




SECTION THRU TYPICAL W-BEAM RAIL ELEMENT




ELEVATION WITH RUBRAIL




ELEVATION WITH RUBRAIL




SECTION D-D



BEVELED WASHER




RECTANGULAR WASHER
(Other approved washer may be used.)



PLAN SPECIAL END SHOE

×× One section of the two shall be considered as subsidiary to the bid item "Steel Plate Guardrail".



ELEVATION SPECIAL END SHOE

14	12-14-10	Revised notes 28" rail height	S.W.K.	J.O.B.
13	04-02-08	Removed Galvanized callout	S.W.K.	J.O.B.
12	02-06-07	Corrected spelling error	S.W.K.	J.O.B.


KANSAS DEPARTMENT OF TRANSPORTATION				
W-BEAM WITH RUBRAIL BRIDGE APPROACH TRANSITION DETAILS				
RD616				
DESIGNED	01-11-11	APPD.	James O. Brewer	
DETAIL	DETAIL CK.	QUANTITIES	QUAN.	TRACE CK.

Note to Designer: Use Guardrail End Terminal, Type II on the traffic departing end of barriers where end on impacts are not a consideration and at the end of entrance return.

Plotted : 10-JUN-2024 16:19

Drawn By : bfranz
File : 010_rdd18.dgn

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	10	53



GENERAL NOTE

Terminal end posts consist of a wood post inserted into a steel tube see details on this sheet.









The steel soil tubes may be driven with an approved driving head. Set steel tube and soil plate before installing wood anchor post assembly. Do not drive steel soil tubes with wood post in the tube. Backfill and satisfactorily compact around steel soil tubes placed in drilled holes to prevent tube settlement.

Galvanize all steel parts after fabrication.

Lap guardrail splices, including terminal connector, in the direction of traffic. Where traffic is temporarily carried in the opposite direction of final configuration, lap rail splices in the direction of the permanent traffic.

All work and materials required for the installation of Barrier Terminal Type II are considered subsidiary to the bid item "Steel Plate Guardrail".

Include Type II end terminal in pay length of "Steel Plate Guardrail".





CABLE ASSEMBLY (1 each)
(40,000 lbs. min. breaking strength)
Tighten cable to taut tension.


06	12-14-10	Rev. notes, details & 28" rail height	S.W.K.	J.O.B.
05	07-20-04	Changed Guard Fence to Guardrail	S.W.K.	J.O.B.
04	05-18-00	Added note for temporary traffic	R.J.S.	J.O.B.
NO.	DATE	REVISIONS	BY	APPD
KANSAS DEPARTMENT OF TRANSPORTATION				
GUARDRAIL END TERMINAL TYPE II				
RD618				
FHWA APPROVAL 01-11-11 APPD. James O. Brewer				
DESIGNED	DETAIL	QUANTITIES	TRACED	
DESIGN CK.	DETAIL CK.	QUAN. CK.	TRACE CK.	

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	11	53


General notes:
The curved rail element is 12 ga, and shop bent.
See Standard Drawing RD611 for notes applying to guardrail posts.
See Standard Drawing RD618 for details of Type II End Terminal.
Use wood Breakaway Posts through curved section of guardrail, all other posts may be either wood or steel with no mixing of types.
Set steel tube and soil plate in place prior to the installation of the wood anchor assembly post.
Use Type II Terminal at entrances or locations where end-on impacts with the terminal are not considered likely to occur.
Use a crashworthy end terminal at sideroad locations and appropriate length of guardrail to satisfy length of need requirements.




L	R	Required Area Free of Fixed Objects
12.50	7.96	25 X 15
18.75	11.94	25 X 15
25.00	15.92	30 X 15
31.25	19.89	30 X 15
37.50	23.87	40 X 20
43.75	27.85	40 X 20
50.00	31.83	40 X 20
56.25	35.81	50 X 20
62.50	39.79	50 X 20



ANCHOR ASSEMBLY




SOIL PLATE




SECTION A-A

(Typical through curved portion of guardrail.)




ANCHOR PLATE


MODIFIED SECTION B-B



BEARING PLATE



ANCHOR ASSEMBLY POST



STEEL TUBE

07	12-14-10	Rev. notes, details & 28" rail height	S.W.K.	J.O.B.
06	07-20-04	Rev. layout, notes, gd. fc. to guardrail	R.J.S.	J.O.B.
05	03-05-01	Add sideroad detail	R.J.S.	J.O.B.
NO.	DATE	REVISIONS	BY	APPD

KANSAS DEPARTMENT OF TRANSPORTATION

DETAILS FOR GUARDRAIL INSTALLATION AT INTERSECTING ROADWAY


RD619

DESIGNED	01-11-11	APPD.	James O. Brewer
DESIGN CK.	DETAIL CK.	QUANTITIES	TRACED
		QUAN. CK.	TRACE CK.

Note to Designer: KDOT Pipe Policy provides guidance in identifying the prohibited and/or restricted uses of CSP, ACSP, PEP, PVCP, CAP & RCP. Provide end sections of the same type and coating as the pipe. Exceptions to this are noted in the Standard Specifications. Refer to the KDOT Design Manual, Volume I (Part C), Road Section, "Elements of Drainage & Culvert Design" for structural pipe design information which includes: corrugations, sizes, gauges, maximum/minimum fill heights and classes of pipe.


Plotted : 10-JUN-2024 16:19

Drawn By : bfranz
File : 012_rdp660.dgn




PLAN


(Illustrated with Type #3 Connection)



FRONT



FRONT




TYPE 1

Available in sizes 12" through 24" only.


TYPE 2

Available in sizes 30" and 36" Round and 17"x13" through 57"x38" Pipe-Arches.



TYPE 3


Available in sizes 42" through 96" Round and 60"x46" through 81"x59" Pipe-Arches.



TYPE 5

Available for all Round and equivalent Pipe-Arch sizes, (Type 1 and Type 2 connections are recommended for the smaller sizes with annular ends).

Note: Type 3 connection may be furnished instead of Type 1 or Type 2 for smaller round or arch pipe.



SPIRAL (HELICAL) CORRUGATION


For all sizes of round and arch culvert pipes having Spiral (Helical) corrugations, the end sections and connecting bands shall be as shown above.

Thickness CSP/ACSP	Thickness CAP	Gauge
0.064"	0.060"	16 ga.
0.079"	0.075"	14 ga.
0.109"	0.105"	12 ga.
0.138"	0.135"	10 ga.
0.168"	0.164"	8 ga.

Pipe Dia. (In.)	CS, ACS or CA Gauge	Dimensions in Inches					Approx. Slope
		A (min.)	B (max.)	H (min.)	L (±2")	W (min.)	
12"	16	5	7	6	21	22	2½: 1
15"	16	6	8	6	26	28	2½: 1
18"	16	7	10	6	31	34	2½: 1
21"	16	8	12	6	36	40	2½: 1
24"	16	9	13	6	41	46	2½: 1
30"	14	11	16	8	51	55	2½: 1
36"	14	13	19	9	60	70	2½: 1
42"	12	15	25	10	69	82	2½: 1
48"	12	17	29	12	78	88	2½: 1
54"	12	17	33	12	84	100	2½: 1
60"	12/10	17	36	12	87	112	2: 1
66"	12/10	17	39	12	87	118	2: 1
72"	12/10	17	44	12	87	120	2: 1
78"	12/10	17	48	12	87	130	1½: 1
84"	12/10	17	52	12	87	136	1½: 1
90"	12/10	17	58	12	87	142	1½: 1
96"	12/10	17	58	12	87	144	1½: 1

Bid Designation Sq. Ft.	Nom. W.W. Area Sq. Ft.	Pipe Arch	Dimensions in Inches 2½" x ½" Corrugations						Dimensions in Inches 3" x 1" or 5" x 1" Corr.						Approx. Slope
		Span & Rise	CS, ACS or CA Gauge	A (min.)	B (max.)	H (min.)	L (±2")	W (min.)	CS, ACS or CA Gauge	A (min.)	B (max.)	H (min.)	L (±2")	W (min.)	
1.0	1.1	17" x 13"	16	5	9	6	20	28							2½: 1
1.5	1.6	21" x 15"	16	6	11	6	24	34							2½: 1
2.0	2.2	24" x 18"	16	7	12	6	28	40							2½: 1
2.5	2.9	28" x 20"	16	7	16	6	32	46							2½: 1
3.0 or 4.0	4.5	35" x 24"	14	9	16	6	39	58							2½: 1
5.0 or 6.0	6.5	42" x 29"	14	11	18	7	46	73							2½: 1
7.0 or 8.5	8.9	49" x 33"	12	12	21	9	53	82							2½: 1
10.0 or 11.0	11.7	53" x 41"							12	17	26	12	63	88	2: 1
10.0 or 11.0	11.6	57" x 38"	12	16	26	12	62	88							2: 1
12.5 or 14.0	15.6	60" x 46"							12	17	36	12	70	100	2: 1
12.5 or 14.0	14.7	64" x 43"	12	17	30	12	69	100							2: 1
16.5	19.3	66" x 51"							12/10	17	36	12	70	112	1½: 1
16.5	18.1	71" x 47"	12/10	17	36	12	77	112							1½: 1
21.0	23.2	73" x 55"							12/10	17	36	12	77	124	1½: 1
21.0	21.9	77" x 52"	12/10	17	36	12	77	124							1½: 1
25.0	27.4	81" x 59"							12/10	17	44	12	77	136	1½: 1
25.0	26.0	83" x 57"	12/10	17	44	12	77	130							1½: 1
32.0	32.1	87" x 63"							12/10	17	44	12	77	136	1½: 1
36.0	37.0	95" x 67"							12/10	17	44	12	87	160	1½: 1
42.0	42.4	103" x 71"							12/10	17	44	12	87	172	1½: 1
47.0	48.0	112" x 75"							12/10	17	44	12	87	172	1½: 1


(Information listed in these tables are nominal and may vary by manufacturer.)



CONNECTION DETAIL H-7 or H-10 BAND

UNIVERSAL REFORMED END with H-7 or H-10 HUGGER BAND

DETAILS FOR H-7 HUGGER BAND (12" thru 36") or H-10 HUGGER BAND (12" thru 120")




CONNECTION DETAIL SINGLE HARNESS

UNIVERSAL REFORMED END with HUGGER BAND

DETAILS FOR H-12 or H-13 HUGGER BAND

Pipe Dia. Inches	Minimum Gauge of Round Pipe				
	2½" x ½" Corr. CSP or ACSP	3" x 1" Corr. CSP or ACSP	5" x 1" Corr. CSP or ACSP	2½"x ½" Corr. CAP	3" x 1" Corr. CAP
12"	14			16	
15"	14			16	
18"	14			16	
21"	14			16	
24"	14			16	
30"	14			14	
36"	14			14	16
42"	14			12	16
48"	12	14	16	14	16
54"	12	14	16	14	16
60"	10	14	16	14	16
66"	10	14	16	14	16
72"	10	14	16	14	16
78"	8	14	14	14	14
84"	8	14	14	14	14
90"		14	14	14	14
96"		12	12	12	12
102"		12	12	12	10
108"		12	12	12	10
114"		12	12	12	8
120"		10	10	10	8



CONNECTION DETAIL DOUBLE HARNESS

Bid Designation Sq. Ft.	Pipe Dimension Span & Rise	Sq. Ft.	Equiv. Round Pipe Diameter	Minimum Gauge of Arch Pipe				
				2½"x ½" Corr. CSP or ACSP	3" x 1" Corr. CSP or ACSP	5" x 1" Corr. CSP or ACSP	2½"x ½" Corr. CAP	3" x 1" Corr. CAP
1.0	17" x 13"	1.1	15"	14			16	
1.5	21" x 15"	1.6	18"	14			16	
2.0	24" x 18"	2.2	21"	14			16	
2.5	28" x 20"	2.9	24"	14			14	
3.0 or 4.0	35" x 24"	4.5	30"	14			14	
5.0 or 6.0	42" x 29"	6.5	36"	14			12	
7.0 or 8.5	49" x 33"	8.9	42"	14			12	
10.0 or 11.0	53" x 41"	11.7	48"		14			
10.0 or 11.0	57" x 38"	11.6	48"	12			10	
12.5 or 14.0	60" x 46"	15.6	54"		14			14
12.5 or 14.0	64" x 43"	14.7	54"	12			10	
16.5	66" x 51"	19.3	60"		14			14
16.5	71" x 47"	18.1	60"	10			8	
21.0	73" x 55"	23.2	66"		14			14
21.0	77" x 52"	21.9	66"	8				
25.0	81" x 59"	27.4	72"		14	12		12
25.0	83" x 57"	26.0	72"	8				
32.0	87" x 63"	32.1	78"		12	12		12
36.0	95" x 67"	37.0	84"		12	12		12
42.0	103" x 71"	42.4	90"		12	12		10
47.0	112" x 75"	48.0	96"		12	12		8
54.0	117" x 79"	54.2	102"		10	10		
60.0	128" x 83"	60.5	108"		10	10		
67.0	137" x 87"	67.4	114"		10	10		
74.0	142" x 91"	74.5	120"		8	8		

GENERAL NOTE for METAL PIPE

Culvert "Type" listed may be CSP, ACSP, CAP, RCP, PVCP & PEP within guidelines of KDOT Pipe Policy for geographic location. More than one pipe "Type" may be acceptable for a design location with allowable types listed for each site.

There shall be no payment for gain in pipe length due to fit of pipe at connecting band.

When Hugger Bands are used, the H-7 Hugger Band may be used on circular pipes 36" diameter and smaller or pipe arches 42"x 29" and smaller. The H-10 Hugger Band may be used on 12" thru 120" pipe. The H-12 or H-13 Hugger Band are for pipe sizes larger than 36" diameter or 42"x29" arch pipe.

⊗ Pipe gauge listed in the tables on this sheet are minimum for E=750 p.s.i. soil. Pipe gauge will be determined for each site based on the Design Manual Volume I- Part C Fill Height Tables and shall be listed in the Pipe Culvert Summary. Gauges shown on this Standard Drawing are KDOT minimum and may not be industry minimum gauge.

In geographic areas that allow CSP (24" or smaller arched or round pipe) for entrance and side road installation with less than 3,000 AADT, 16 gauge ACSP may be substituted for 14 gauge CSP.

Aluminum or aluminized pipes or end sections shall be coated with an asphaltic paint when in contact with fresh concrete in accordance with the Standard Specifications.

04	09-10-09	Rev. Round and Arch tables, add. Alum.	S.W.K.	J.O.B.
03	01-20-09	Rev. Round and Arch tables, add. Alum.	S.W.K.	J.O.B.
02	04-18-08	Rev. layout, details, tables and notes	S.W.K.	J.O.B.
NO.	DATE	REVISIONS	BY	APPD

KANSAS DEPARTMENT OF TRANSPORTATION				
METAL END SECTION FOR ROUND & ARCH METAL CULVERTS (TYPE I) & PIPE GAUGE TABLES				
RD660				
FHWA APPROVAL		12-16-09	APPD.	James O. Brewer
DESIGNED	DETAILED	QUANTITIES	TRACED	
DESIGN CK.	DETAIL CK.	QUAN. CK.	TRACE CK.	
KDOT Graphics Certified 05-16-2022 Sh. No. 12				

Note to Designer:

KDOT Pipe Policy provides guidance in identifying the prohibited and/or restricted uses of CSP, ACSP, PEP, PVCPI, PPP, SSPE, CAP & RCP. Provide end sections of the same type and coating as the pipe. Exceptions to this are noted in the Standard Specifications. Refer to the KDOT Design Manual, Volume I (Part C), Road Section, "Elements of Drainage & Culvert Design" for structural pipe design information which includes: corrugations, sizes, gauges, maximum/minimum fill heights and classes of pipe.


Drawn By : bfranz
File : 013_rd659.dgn

05-09-22	Added Pipe Types PP & SRPE		A.L.R.	S.W.K.
07-17-17	Added footnote for Shop Drawing		A.L.R.	S.W.K.
02-23-16	Rev. Table, Added Floor Elev.		T.T.R.	S.W.K.
DATE	REVISIONS		BY	APP'D
KANSAS DEPARTMENT OF TRANSPORTATION				
<h1>SUMMARY of PIPE CULVERTS</h1>				
D0659				
VA APPROVAL		06-08-22	APPD: Scott W. King	
SIGNED IGN CK.	DETAILED DETAIL CK.	QUANTITIES QUAN.CK.	TRACED TRACE CK.	

★ Only include floor elevations for embedded pipes. See RD668 for details. For structures not embedded, the floor elevations may be omitted.

- ✱ When inside diameter of pipe is 36" or less.
- ⚠ Unless otherwise specified in the plans. Some pipe types may not be allowed at a location if the fill height exceeds the maximum allowable or is less than the minimum allowable cover.
- 📏 When inside diameter of pipe is 60" or less.
- ≈ For inside diameter: $\geq 30"$

◆ Type IV End Sections are only made of CS or ACS
 ♪ Submit Shop Drawing of connection for review



Plotted By: sallen

File: 014 BR200.dgn

Plot Date: 06-SEP-2024 10:27

Plot Location:

SUMMARY OF QUANTITIES											
Item Location	Excavation		Concrete		Reinforcing Steel		* Piles (Steel) (HP 10x42) Lin. Ft.	* Piles (Steel) (HP 12x53) Lin. Ft.	Contractor Furnished PDA Each	Slope Protection (Riprap Stone) (200 Lb.) Cu. Yds.	● Bridge Project Marker Each
	Class I	Class II	(Grade 4.0) (AE) (SW)	(Grade 4.0) (AE)		(Grade 60)					
	Cu. Yds.	Cu. Yds.	Cu. Yds.	Cu. Yds.		Lbs.					
Abutment No. 1	49		**			**	479		1	140	1
Pier No. 1		38		38.6		1,335		656			
Pier No. 2		38		38.6		1,335		690	1		
Abutment No. 2	49		**			**	476			141	
Substr. Total	98	76		77.2		2,670					
Superstr. Total			336.5			93,980					
Total	98	76	336.5	77.2		96,650	955 †	1,346 †	2 ††	281	1

* NOTE: Only steel pile HPI0X42 on the Abutments and HPI2x53 on the Piers shall be used on this project.

**Quantities are included in the Superstructure Total Quantity.

† Summary of Piling
Abutment No. 1 6 @ 67', 1 @ 77'
Pier No. 1 8 @ 82'
Pier No. 2 7 @ 85', 1 @ 95'
Abutment No. 2 7 @ 68'

†† Summary of Contractor Furnished PDA
Abutment No. 1 Use with 77' HPI0x42 Pile
Pier No. 2 Use with 95' HPI2x53 Pile

⦿ Non-participating item. See Sht. 22

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	14	53

INDEX TO BRIDGE DRAWINGS	
Sheet No.	Drawing
14	General Notes and Quantities
15	Contour Map
16	Construction Layout
16	Engineering Geology
17	Abutment Details
18	Pier Details
19-20	Superstructure Details
21	Rail Details
22	Bridge Plate
23	Bill of Reinforcing Steel and Bending Diagrams
Standards	
24	Bridge Excavation
25	Standard Pile Details
26	Supports and Spacers for Reinforcing Steel

DESIGN DATA

DESIGN SPECIFICATIONS:
AASHTO Specifications, 9th Edition 2020 and latest Interim Specifications. Load and Resistance Factor Design.

DESIGN LOADING:
HL-93

Design Dead Load includes an allowance of 25 psf for a future wearing surface.

UNIT STRESSES:		
Concrete (Grade 4.0)(AE)	f'c =	4 ksi
Concrete (Grade 4.0)(AE)(SW)	f'c =	4 ksi
Reinforcing Steel (Grade 60)	fy =	60 ksi
Steel Piles	fy =	50 ksi

LRFD DESIGN PILE LOAD:			
Design Loading (Tons/Pile)	Strength I	Service I	Phi
Abutments:	50	38	0.45
Piers:	57	47	0.45

LFD & LRFR RATING FACTORS		
Rating Level		
Truck	Inventory	Operating
HS-20 (36T)	1.58	2.65
Type HET (110T)		2.28
2002 LFD Rating, 17th Edition AASHTO		
HL-93 Loading	1.40	1.82
2008 Manual for Bridge Evaluation		

KANSAS DEPARTMENT OF TRANSPORTATION			
Br. No. 000780775005601		Sta. 36+90.00	
GENERAL NOTES AND QUANTITIES			
Proj. 78 C-5229-01		Reno County	
SHEET NO.	OF	SCALE	APP'D
DESIGNED		DETAILED	QUANTITIES
DESIGN CK.		DETAIL CK.	QUAN. CK.
			CADD CK.

CADconform Certify This File

EMBANKMENT: Complete the embankment at the abutments as shown on the Bridge Excavation sheet prior to driving the abutment piling or commencing with the abutment footing excavation.

BRIDGE EXCAVATION: Elevation 1440.50 shall designate the Excavation Boundary Plane of Class I and Class II Excavation; Class I above the plane, Class II below the plane. See the Bridge Excavation sheet for the limits of pay excavation.

BACKFILL COMPACTION: Compact backfill at the abutments.

PILING: Drive all piling to achieve plan bearing capacity from side friction. Driving shall stop when in the opinion of the Engineer additional driving may damage the piling. Drive all piling to the Pile Driving Formula Load of:

Abutment No. 1	38 Tons
Pier No. 1	47 Tons
Pier No. 2	47 Tons
Abutment No. 2	38 Tons

As a minimum drive each pile to the load and penetration, but in no case shall the pile be driven to more than 110% of Pile Driving Formula Driving Load. At any location where problems are experienced, pile damage is suspected, or the Pile Driving Formula Load occurs significantly above the design pile tip elevation, the Engineer may request that the Pile Driving Analyzer (PDA) equipment be used.

CONTRACTOR FURNISHED PDA: Use the Pile Driving Analyzer equipment at the locations shown on the Construction Layout sheet. Use Pile Driving ANALYZER equipment and methods compliant with KDOT Special Provisions. The piling shall remain in place as permanent piling. Drive the piling to the resistance value of (Strength I divided by Phi shown on the plans).

PILING SPLICE LOCATION: Integral pile splice locations and weld testing criteria for, Abutments 1 and 2 and Piers 1 and 2 will follow the "Standard Pile Details" Sheet (BR110).

CORRAL RAIL: Build the corral rail after the falsework is struck.

REMOVAL OF EXISTING STRUCTURE: Removal of existing structure is included in the bid item, "Removal of Existing Structure", Lump Sum. All materials removed from the existing structure shall become the property of the Contractor. Remove this material from the site.

SLOPE PROTECTION (Riprap Stone)(200 Lb.): Place the Slope Protection (Riprap Stone)(200 Lb.) to the limits and thickness shown on the plans or as directed by the Engineer.

CONCRETE: Superstructure concrete is bid as Concrete (Grade 4.0)(AE) (SW). Substructure concrete is bid as Concrete (Grade 4.0)(AE). Bevel all exposed edges of all concrete with a 3/4" triangular molding, except as otherwise noted on the plans. Construction joints are optional with the Contractor, but if used, place only at locations shown, or at locations approved by the Engineer.

REINFORCING STEEL: All reinforcing steel dimensions are to the centerline of bars unless otherwise noted. All reinforcing steel bars, shall conform to the requirements of ASTM A615, Grade 60.

CAMBER: Provide camber as shown on the Camber Diagram unless the Contractor uses either long span steel beam falsework (concrete dead load deflection greater than 1/4") or timber falsework with greater than 12'-0" clear span. If either case exists, submit falsework plans that show the additional required camber.

FALSEWORK PLANS: A licensed Professional Engineer shall design the falsework details. Details shall bear the seal of a licensed Professional Engineer. Submit electronic plans conforming to Section 105 of the Standard Specification with details in compliance with KDOT Specifications to the Field Engineer for review.

FALSEWORK INSPECTION: This project has falsework plan requirements which are considered "Category 2" by KDOT specifications. If falsework deficiencies or variations from the approved and sealed plans are found, the falsework design Engineer of Record will provide written approval of the changes. If for the convenience of the Contractor the falsework becomes "Category 1" by the use of non-typical supports; then the inspection and review requirement of "Category 1" will be fully enforced, but at no cost to the State. "Category 2" falsework inspection is not paid for directly, but is subsidiary to other bid items.

FALSEWORK: Leave the falsework in place for the entire unit until 15 days after the last concrete pour for the unit or longer as directed by the Engineer.

DEMOLITION PLANS: This is a Category A Demolition. Submit detailed Demolition Plans to the Field Engineer per KDOT Specifications. No Demolition work will begin without approved Demolition Plans. A Licensed Professional Engineer is not required.

DRIP LINE PROTECTION: Place a 10 foot wide mat of geotextile under the rock/rubble embankment on the berm and berm slopes and centered on the drip lines of the slab.

CONCRETE PLACING SEQUENCE: The sequence of placing concrete in the slab and curbs shall be as shown, or the Contractor may submit an alternate placing sequence for review. Submit the alternate placing sequence to the Engineer at the Preconstruction Conference. Include the proposed rate of concrete placement in C.Y./h, the plant capacity, placement direction, construction joint location, a description of the equipment used in placing the concrete, proposed admixtures, and the quantity of concrete in each placing segment. Any additional cost for the Contractor's alternate plan of placing concrete, including admixtures, shall be at the Contractor's expense and shall be considered subsidiary to the bid item, "Concrete (Grade 4.0)(AE)(SW)". Approval of the Contractor's alternate sequence is required prior to placement of concrete in the deck.

CONSTRUCTION LOADS: Limited traffic is permitted on the new sub-deck, one-course deck or any concrete overlay during the curing period, keep any exposed deck wet during the curing period. See KDOT Specifications Section 710 Tables 710-1 & 710-2 for additional information.

QUANTITIES: Items not listed separately in the Summary of Quantities are subsidiary to other items in the proposal.

DIMENSIONS: All dimensions shown on the design plans are horizontal dimensions unless otherwise noted. Make necessary allowances for roadway grade and cross slope.

CONSTRUCTION JOINTS: The construction joints shown are optional with the Contractor. If used, place the construction joints only at locations shown or at locations approved by the Engineer.

CONTRACTOR CONSTRUCTION STAKING: Contractor Construction Staking for clear span bridges requires two independent surveys. See KDOT Specifications.

DECK FINISHING: Set the finishing machine normal to the centerline of the structure for striking off and screeding the concrete.

TEMPERATURE: The design temperature for all dimensions is 60 F.

EWS HEADER: Place bolts and attach header at the EWS in accordance with subsection 710.3c. All materials and labor required for this work will not be paid directley, but shall be subsidiary to other bid items. See Sheet No. 17 for Details.

CADconform Certify This File

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	15	53

UTILITIES:
 Pipeline - Phillips 66 Pipeline
 (918) 977-7816
 Power - Ark Valley Electric COOP
 (620) 662-6661
 Telephone - Brightspeed
 (800) 778-9140

<p> 1. 1/2" bar with SE control cap 0.4' deep 2. 20d nail with bottle cap in top roof fence post 3. 20d nail with bottle cap in top wood fence post 4. Top center telephone pedestal 5. Centerline N.-S. road </p>		<p> 46.9' N.E. 47.3' S.E. 78.5' S.S.W. 0.0 </p>
--	--	--

@P.O.T. Sta. 42+00.00	
1. 1/2" bar with SE control cap 0.3' deep	
2. 20d nail with bottle cap in power pole	85.5' S.E.
3. 20d nail with bottle cap in power pole	81.0' S.W.
4. Top metal guy anchor	64.2' S.E.
5. Centerline N-S. road	0.0

LIMITS OF EROSION CONTRL _CLASS I, TYPE C MAT

Ditch 2:1 Backslope

- (A) Sta. 34+00 to Sta. 36+35, Lt., Length = 235', Width = Varies
(B) Sta. 34+00 to Sta. 36+10, Rt., Length = 210', Width = Varies
(C) Sta. 37+76 to Sta. 39+50, Lt., Length = 174', Width = Varies

Behind Guardrail

- (D) Sta. 35+54 to Sta. 35+99, Rt., Length = 45', Width = Varies
 (E) Sta. 35+68 to Sta. 36+19, Lt., Length = 51', Width = Varies
 (F) Sta. 37+81 to Sta. 36+26, Lt., Length = 45', Width = Varies

Channel 2:1 Backslope

- (G) Sta. 49+38 to Sta. 49+45, Lt., Length = 7', Width = Varies
 (H) Sta. 49+58 to Sta. 50+01, Rt., Length = 43', Width = Varies
 (I) Sta. 50+59 to Sta. 50+84, Rt., Length = 25', Width = Varies

LIMITS OF EROSION CONTRL _CLASS II, TYPE E MAT

Channel Bottom

- ⓐ Sta. 49+62 to Sta. 49+82, Rt., Length = 20', Width = Varies
- ⓑ Sta. 50+59 to Sta. 50+84, Rt., Length = 25', Width = Varies

LIMITS OF RIPRAP

Abutment No. 1
Sta. 36+18, 30' Lt. to Sta. 36+67, 30' Lt. to
Sta. 35+98, 30' Rt. to Sta. 36+31, 30' Rt.

Abutment No. 2
Sta. 37+63, 30' Lt. to Sta. 37+81, 30' Lt. to
Sta. 36+27, 30' Rt. to Sta. 36+62, 30' Rt.

Marlin A. & Karen A. Yoder, Trust
Tract of Land in
N.E. ¼ Sec. 28, T22S., R4W.

@Sta. 36+90.00 Construct
 Br. No. 000780775005601
 48'-64'-48' RCSH Cont. Spans
 Bridge, Pile Bent Abuts. and
 Piers, Skew 30° Rt.
 with a 24'-0" Roadway

Note:
Sta. 37+95 Place one of the Temporary
Ditch Check (Rock) from the Temporary
Erosion and Pollution Control Quantities.
For Information Only.

Darrell, Marlin, Larry & James Regehr
Tract of Land in
S.E. ¼ Sec. 21, T22S., R4W.

JLR Family Farm LLC
Tract of Land in
E.W. ¼ Sec. 22, T22S., R4W.

Sta. 36+90 @Project =
Sta. 50+00 @Channel
Improvement

@Sta. 37+00 Remove (Br. No.
 000780775005600) 7 @ 19'
 Timber Beam Spans Bridge (TBMS)
 Skew 15° Rt. with a 23' Roadway.

KANSAS DEPARTMENT OF TRANSPORTATION
BR. VICTORY ROAD 27.01

CONTOUR MAP


BR. NO. 000780775005601
CADconform Certify This File

BM #9 R.R. Spike in N. face of power pole
29.95' Rt., @Sta. 35+86.45, Elev. = 1457.91



BM #10 "T" post 13.75' Rt., @Sta. 40+23.30, Elev. = 1454.94
--

Drawn By : bfranz
 File : 015_ContourMap30Scale.dgn
 Plotted : 10-JUN-2024 16:19

	BY	DATE
REFERENCES NOTED		
REFERENCES CHECKED		



STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	17	53




ANGLE IRON AT EDGE OF WEARING SURFACE
Not to Scale
(Subsidiary to Bid Item "Concrete (Grade 4.0)(AE)(SW)

Reinforcing Steel in Top of Abutment
Reinforcing Steel in Bottom of Abutment
PLAN
Scale: 1/2" = 1'-0"


Note: Top of piling elevations are based on 2'-0" maximum embedment.

NOTE: Slide #8A1 bar to avoid conflict with Header Plate.



TYPICAL SECTION
Scale: 3/4" = 1'-0"

LEGEND
EF = Each Face



ELEVATION
Scale: 1/2" = 1'-0"
Note: EF = Each Face

LRFD DESIGN PILE LOAD:	Strength I	Service I	Phi
Design Loading (Tons/Pile)			
Abutments:	50.0	38.0	0.45

KANSAS DEPARTMENT OF TRANSPORTATION
Br. No. 000780775005601Sta. 36+90.00

ABUTMENT DETAILS

Proj. No. 78 C-5229-01Reno County

SHEET NO.	OF	SCALE	1/2" = 1'-0"	APP'D	
DESIGNED	XXX	DETAILED	william	CADD	william
DESIGN CK.	XXX	DETAIL CK.	SAI	QUAN. CK.	SAI





Plotted By: bfranz
File: 017_AbutmentDetails.dgn
Plot Date: 10-JUN-2024 16:19

IsLab-Ir60r501.dgn
LHD
Roadway Width = 32'-0"
Skew and Direction = 0
Number of Piles = 4

Note to designer: Do not remove this information

Plotted By: bfranz
File: 018_PierDetails.dgn
Plot Date: 10-JUN-2024 16:19

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	18	53



LRFD DESIGN PILE LOAD:	Design Loading (Tons/Pile)	Strength I	Service I	Phi
Piers:	57.0	47.0	0.45	

4				
3				
2				
1				
NO.	DATE	REVISIONS		BY APP'D
KANSAS DEPARTMENT OF TRANSPORTATION				
Br. No. 000780775005601			Sta. 36+90.00	
PIER DETAILS				
Proj. No. 78 C-5229-01			Reno County	
SHEET NO.	OF	SCALE	% = 1'-0"	APP'D
DESIGNED	DGB	DETAILED	william	QUANTITIES william CADD william
DESIGN CK.	DGB	DETAIL CK.	SA	QUAN. CK. SA CADD CK. SA


1rfvbr522.dgn	Plot 2
Roadway Width = 32'	Longest Span Length = 56'
Skew and Direction = 0	Total No. of Spans = 3
Loading = HL-93	Railing Type = Corral

LFD & LRFR RATING FACTOR		3'	
Truck	Cr.	Im.	Oper.
17.5-20	1.55	2.58	1.61
LFD	1.45	1.45	1.44
LRFR	1.30	1.69	1.35

Note to designer: Do not remove this information

Plotted By: bfranz	Plot Location:
File: 019_DeckPlanDetails.dgn	
Plot Date: 10-JUN-2024 16:19	


STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	19	53



Note:
See longitudinal section for
transverse reinforcing steel.

HALF PLAN

Scale: 1/4" = 1'-0"



DEAD LOAD CAMBER DIAGRAM AT TENTH POINTS

Long Term Deflections = Initial Deflections x 3.5
(Initial Deflections Based on $E_c = 3.644 \times 10^6$ p.s.i.)
(camber values in feet)

NOTE: The Bridge Camber has been Reduced
by 30% to account for the Skew.

CONCRETE PLACING SEQUENCE DIAGRAM

CONCRETE PLACING SEQUENCE

When long span steel beams having a concrete dead load deflection greater than 1/4" are used or when timber falsework with greater than 12'-0" clear span is used, follow the placing sequence shown. Segmental, combined or continuous pours are allowed, but stop a discontinuous pour at a construction joint short of a pier.

When timber falsework with 12'-0" or less clear span is used, the Contractor, subject to the approval of the Engineer, may use a continuous pour or may discontinue the pour at any construction joint shown.

The Contractor may place the corral rail continuously from one end of the bridge to the other.

KANSAS DEPARTMENT OF TRANSPORTATION			
Br. No. 000780775005601		Sta. 36+90.00	
SUPERSTRUCTURE DETAILS			
Proj. No. 78 C-5229-01		Reno County	
SHEET NO. OF	SCALE	1/4" = 1'-0"	APP'D
DESIGNED	xxx	DETAILED	william
DESIGN CK.	xxx	DETAIL CK.	xxx
QUANTITIES	william	CADD	william
QUAN. CK.	xxx	CADD CK.	xxx


CADconform Certify This File

Sheet No. 19

117dbr526.dgn	Plot 3
Roadway Width = 28'	Longest Span Length = 64'
Skew and Direction = 0	Total No. of Spans = 3
Loading = HL-93	Railing Type = Corral


Plotted By: bfranz	Plot Location:
File: 020_DeckTypicalSectionDetails.dgn	
Plot Date: 10-JUN-2024 16:20	

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	20	53




HAUNCH ORDINATES

Scale: 1/4" = 1'-0"



HALF LONGITUDINAL SECTION ALONG C BRIDGE

Scale: 1/2" = 1'-0"




TRANSVERSE SLAB
CONSTRUCTION JOINT
(Optional)

3					
2					
1					
NO.	DATE	REVISIONS	BY	APP'D	
KANSAS DEPARTMENT OF TRANSPORTATION					
Br. No. 000780775005601 S+a. 36+90.00					
SUPERSTRUCTURE DETAILS					
Proj. No. 78 C-5229-01 Reno County					
SHEET NO. OF	SCALE	1/4" = 1'-0"	APP'D		
DESIGNED	XXX	DETAILED	william	QUANTITIES	william
DESIGN CK.	XXX	DETAIL CK.	XXX	CADD CK.	XXX



CADconform Certify This File

20


STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	21	53




BRIDGE NUMBER PLATE PLACEMENT DETAIL
(If Required)



DETAIL A
(For bridges w/o an approach slab curb, detail top of wing at curb line as shown)




ELEVATION
(Dimensions at traffic face of rail.)




PLAN


PARTIAL ELEVATION
(Along Traffic Face)




SECTION A-A




SECTION C-C



SECTION B-B



TYPICAL INTERIOR POST



SECTION THRU POST

LEGEND
NF = Near Face
FF = Far Face
EF = Each Face









3					
2	12-3-21	Changed Bridge Number Plate detail	MLL	MAH	
1	6-30-05	Current Release			
NO.	DATE	REVISIONS	BY	APP'D	
KANSAS DEPARTMENT OF TRANSPORTATION					
Br. No. 000780775005601 Sta. 36+90.00					
27" KANSAS CORRAL RAIL					
(W-BEAM WITH RUBRAIL)					
R.C. HAUNCHED SLAB (Without Curb)					
Proj. No. 78 C-5229-01 Reno County					
SHEET NO.	OF	SCALE	APP'D		
DESIGNED		DETAILED	QUANTITIES	william	CADD
DESIGN CK.		DETAIL CK.	QUAN. CK.	CADD	CK.

CADconform Certify This File

Sheet No. 21

Std. Base File: br183a.dgn
Plotted By: bfranz
File: 021 br183a.dgn
Plot Date: 10-JUN-2024 16:20

Plotted : 10-JUN-2024 16:20
Drawn By : bfranz
File : 024_br100b.dgn




Plotted : 10-JUN-2024 16:20
Drawn By : bfranz
File : 025_br110.dgn

OD	10 $\frac{3}{4}$ "	T. = ∇
OD	12 $\frac{3}{4}$ "	T. = ∇
OD	14"	T. = ∇


∇ See the Geology Report or "Summary of Quantities" for Pipe Pile wall thickness

Note:
Pile shall be driven with a steel head having a projecting ring fitting inside the pipe. Clearance between ring and pipe should be $\frac{1}{4}$ ".

Note:
Pile pipe may be spiral welded, longitudinal welded, or seamless steel pipe.




PLAIN ROUND CAST-IN-PLACE CONCRETE PILES




PICK-UP POINTS FOR PRESTRESSED PILING

Max. length - 55' single point pick-up
Max. length - 80' double point pick-up

Note: Piles shall be marked at Pick-up points to indicate proper points for attaching handling lines.




Outside Flange



Inside Flange


SHELL PILE POINT




H-Pile Point

CAST STEEL PILE POINT


The pile point shall be a one-piece unit of cast steel. Weld pile points in accordance with manufacturer's recommendations to each steel pile before driving.



BUILD UP SECTION



BUILD UP SECTION



FOR INFORMATION ONLY EQUIVALENT POINT BEARING PILES		
STEEL PILES	CONCRETE PILES	
	Pipe	Pre-stress
HP10x42	10 $\frac{3}{4}$ "	
HP12x53	12 $\frac{3}{4}$ "	
HP14x73	14	12
HP14x102		14
HP14x117		16

SPICES: Splices for steel piles and shell piling shall be in accordance with details shown on this sheet and the Standard Specifications.

For integral pile bent abutments and piers, if a pile splice is required, do not locate the pile splice within a region extending 2'-0" above and 10'-0" below the bottom of the concrete web wall. For abutments, locate the pile splice at least 10'-0" below top of fill.


With the approval of the Engineer, one splice per bent may be allowed in the region described above without testing. If additional splices are anticipated, based on the geology, the Contractor prior to driving, will locate the splice so that the splice will not fall within the regions described above.

For integral pile bent abutments and piers, if a splice is located within the regions described above, then the Contractor will test the welds by Radiograph (RT) test methods. Repair and retest any welds not passing the test(s). Each weld tested will have written confirmation of results. Report these results to the Engineer. This work is not paid for directly, but is subsidiary to "Piles".

* Minimum as required by welding process.

BG = Backgouge

PILE SPLICE DETAILS



GENERAL NOTES

PRESTRESSED PILES: Fabricate prestressed concrete pile splices in accordance with the Manufacturer's recommendations subject to the approval of the Engineer.

Method of attachment of pile to build-up may be by any of the methods given in the notes on "Alternate Methods." If mild reinforcing steel is used for attachment, the area shall be no less than that used in the build-up.

ALTERNATE METHODS: Method of attachment of a pile to build-up may be by any of the following methods:

1. Cut off at least 2'-0" of pile and expose a minimum of 2'-0" of strands.
2. Cast 8-#6, or 8-#5 bars (equally spaced) into pile head. All bars shall extend into pile head and project from pile head a minimum of 2'-0".
3. Drill 8 holes in pile head (equally spaced) for installation of 8 grouted dowel bars of same size and length as in 2.
4. Provide cored holes for bars as in 3.

No bars or strands are to extend from head of pile or build-up into footing or pile cap unless approved by the Engineer.

TEST PILES: Drive test piles where called for on the bridge plans. The test piles located within the limits of the substructure will become a part of the bridge pile system.

DRIVING FORMULA: Driving formula shall conform to the Standard Specifications.

MEASUREMENT AND PAYMENT: Measurement and payment for all piles shall comply with the Standard Specifications.

REINFORCEMENT: Use reinforcing steel conforming to ASTM A615, Grade 60. Hoops and spirals may be either plain or deformed bars.

PRESTRESSING STEEL: Use uncoated seven-wire low relaxation prestressing strand conforming to ASTM A416, Gr. 270.

STEEL PILE: Steel pile shall conform to the requirements of the Standard Specifications.

PILE POINTS: Pile points shall conform to the dimensions shown and to requirements of the Standard Specifications.

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	25	53

SPECIFICATIONS: Standard Specifications for State Road and Bridge Construction as currently used by the Kansas Department of Transportation.

CONCRETE: Concrete for cast-in-place shall be f'c = 3,500 PSI. Concrete for prestressed shall be f'c = 5,000 PSI.

WELDING: All field welding shall meet the requirements of the Standard Specifications.

Use only Shielded Metal Arch Welding SMAW (stick welding) for pile splices.

Use only low hydrogen E7018, 7016, or 7015 series welding rod (electrode) for all welding applications during pile splicing.

New electrodes are to be purchased for each KDOT project. The electrodes shall arrive on the project in factory hermetically sealed containers, opened and labeled with indelible ink in front of the engineer. The label shall include the current date and the project number. If the container seal is questionable or shows signs of damage the electrode is to be dried in an oven at least one hour at a temperature of 700°F to 800°F.

Upon removal from intact hermetically sealed factory packaging or the drying oven the electrode is to be placed in a storage oven with a minimum temperature of 250°F.

When electrodes are removed from the hermetically sealed container or storage oven and exposed to the atmosphere for less than 4 hours place into the storage oven for at least 4 hours before removing for use.

If electrode is exposed to the atmosphere for 4 hours or more (or 9 hours for moisture resistant electrodes designated with an R in their labeling) then electrode can be dried in a drying oven at a temperature of 450°F to 550°F.

If the electrode is exposed to the atmosphere for 4 hours or more a second time or the rod becomes wet discard rod.

CAST-IN-PLACE SHELLS: Steel shells for cast-in-place concrete piles shall conform to the requirements of the Standard Specifications.

All piles driven without a mandrel shall be of the minimum thicknesses shown. Piles driven with a mandrel shall be of sufficient strength and thickness to withstand driving without injury and to resist harmful distortion and/or buckling due to soil pressure after the mandrel is removed.

Remove, replace or correct to the satisfaction of the Engineer improperly driven, broken or otherwise defective pipe piles. Otherwise drive an additional pile at no extra cost.

The Contractor shall maintain a light suitable for visual inspection of the pile on the job at all times prior to and during the filling of the pipe.

PAINT: All paint shall comply with the Standard Specifications, or as specified on the plans.

MILL TEST REPORTS: Steel piles test reports and steel shell test reports shall comply with the Standard Specifications.

04	08-16-18	Add splice web section, clarify note	M.L.L.	J.P.J.
03	09-15-15	Clarify Notes	J.P.J.	C.E.R.
02	06-18-12	Clarify f'c, rod type, use and weld	J.P.J.	T.L.F.
NO.	DATE	REVISIONS	BY	APPD
KANSAS DEPARTMENT OF TRANSPORTATION				
STANDARD PILE DETAILS				
BR110				
FHWA APPROVAL		10-04-12	APPD.	Terry L. Fleck
DESIGNED	J.P.J.	DETAILED	QUANTITIES	TRACED
DESIGN CK.	DETAIL CK.	QUAN. CK.	TRACE CK.	
KDOT Graphics Certified		06-20-2022	Sh. No. 25	

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	26	53

GENERAL NOTES

Reference is made to the latest edition of the CRSI "Manual of Standard Practice" for recommended industry practices concerning reinforcing steel.

Use only the following types of bar supports:

- Wire Bar Supports:
 - Epoxy coated reinforcing: Class 1 Protection
 - Non-epoxy coated reinforcing: Class 1, 2, or 3 Protection
- Plastic Bar Supports
- Supplementary bars

When securing epoxy coated reinforcement, use tie wires or metal clips that are epoxy or plastic coated.

Do not weld reinforcing steel to bar supports or to other reinforcing steel. Shop weld spacer frames for haunched slabs.

Tie bars at all intersections around the perimeter of each mat and at not less than 2'-0" centers or at every intersection, whichever is greater.


Where more than one length of bar support is required, lap the end legs so they are locked or tied together.

Use proper height supports to maintain the distance between the reinforcing and the formed surface or the top surface of deck slabs within 1/4" of that indicated on the plans.

Spacings shown are maximums. Use sufficient supports, as determined by the Engineer, to retain the reinforcing steel in position.

Construct any platforms, required for the support of workers and/or equipment during concrete placement, directly on the forms and not on the reinforcing steel.

Designs and arrangements of Supports or Spacers other than as shown on this sheet, may be used with the permission of the Engineer.



SECTION A-A

05	11-10-10	Column Bar Supports Required	J.P.J.	T.L.F.
04	12-01-05	Drilled Shaft Spiral Steel Placement	J.P.J.	K.F.H.
03	08-21-00	Added Pre-Cast Panel Detail	R.A.M.	K.F.H.
NO.	DATE	REVISIONS	BY	APPD

KANSAS DEPARTMENT OF TRANSPORTATION


SUPPORTS AND SPACERS FOR REINFORCING STEEL

BR120


DESIGNED	R.A.M.	DETAILED	R.A.A.	QUANTITIES	TRACED	R.A.A.
DESIGN CK.	L.R.R.	DETAIL CK.	R.A.M.	QUAN. CK.	TRACE CK.	R.A.M.

KDOT Graphics Certified 06-20-2022


Sh. No. 26




CONTINUOUS HAUNCHED SLAB




DECK GIRDERS




PIER




ABUTMENT



BOX CULVERT



DRILLED SHAFT



* Note: Longitudinal reinforcing steel is placed on the bottom of the rock socket. Maintain 3" clearance from the bottom of rock socket to the first spiral or tie bar.

Required Shaft Supports		
Diameter (in.)	Circumference (in.)	No. of Spacers
18	56	3
24	75	3
30	94	4
36	113	4
42	131	5
48	150	6
54	169	6
60	188	7
66	207	7
72	226	8
78	244	9
84	263	9
90	282	10
96	301	11
102	320	11
108	339	12

GENERAL NOTE:

On surfacing projects, the 6" of Compaction Type AA, shown for the center portion on the roadbed, is for the purpose of restoring the original Compaction Type AA which may have been lost since grading operations. The exact locations of this Compaction Type AA, which will be required, is to be determined by the Engineer at the time of construction. This work shall be paid under the bid item "Compaction of Earthwork (Type AA)(MR) -".

Over all structures, unless otherwise directed by the Engineer, where the top of the hubguard is level with or above the finished shoulder grade, the earth cover over the structure slab shall be removed and backfilled with _____ material as directed by the Engineer. The removal of this material will be subsidiary.

~~The _____ material used to backfill over the structure shall be paid for at the prices shown in the contract.~~

~~The earth shoulders shall be compacted full depth (Type MR) except~~
~~ordered by the Engineer, the top 3" shall be left uncompacted for seeding.~~

All side roads and house entrances shall be surfaced with _____ to the R/W line as indicated on the detail. All side roads and house entrances with existing asphalt surface shall be surfaced with _____ at least to the _____

R/W line or to the end of construction, as directed by the Engineer. Each mailbox _____
turnout (ON PROJECTS WHERE STABILIZED SHOULDERS ARE NOT SPECIFIED) shall be surfaced
with _____ to the limits shown on the detail. _____

Surfacing material (SA-_____) shall be used for surfacing house entrances and side roads (____ C.Y./SQ. YD.) beyond the limits of the asphalt surface to the limits of construction as determined by the Engineer.

~~The thickness of side road and entrance surfacing may be increased to the same thickness as the stabilized shoulder within the approximate limits of the shoulder~~

On projects which specify both asphalt base and surface course materials, side roads, house entrances and mailbox turnouts may be surfaced with both materials at the contractors option, with the approval of the Engineer.


Quantities for aggregate for shoulders, AS-1, are calculated on the ba

lbs. per cu. ft. Quantities for stabilized base course, AB-3, are calculated on the basis of 156 lbs. per cu. ft. Weight/cu. ft. includes moisture allowed by specification.

The base course shall be constructed to the plan thickness as shown.

Thicknesses indicated for all construction which is paid for on a weight or volume basis are approximate and may vary to correct for unevenness in the foundations or for other normal unevenness encountered in placement operations.

A tack coat of SS-1HP shall be provided between each lift of all base courses and surface courses and under the first lift of base or surface courses when they are placed on an existing asphalt, brick, or concrete surface, when so ordered by the Engineer and at the rate designated by him. Quantities are included for these tacks calculated at the rate of 0.06 gal./sq. yd.



TYPICAL PROFILE AT GRADE CONTROL POINTS

The Contractor shall cut the subgrade in accordance with this profile at all grade control points, i.e. ; existing pavements, grade bridges and R.R. crossings, also at changes in thickness of base or surface courses. Corresponding dimensions of "D" and "L" shall be as given in the table below.

The work of cutting the subgrade and disposing of excess excavated material shall be subsidiary to other items in the contract.

D	L	D	L	D	L	D	L	D	L	D	L
1"	25'	3"	75'	5"	125'	7"	175'	9"	225'	11"	275'
2"	50'	4"	100'	6"	150'	8"	200'	10"	250'	12"	300'

[illegible]


Note:
Quantities have been increased $\frac{3}{8}$ " for Contingencies.

[illegible]

† Computed at the rate of
†† Computed at the rate of


[illegible]

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	28	53




SECTION A-A

Note: The face of Mail Box should be no closer to the roadway than the edge of the shoulder. Align with edge of turnout when turnout width is greater than shoulder width.



DETAIL FOR SURFACING OF MAIL BOX TURNOUTS



WITH DRAINAGE STRUCTURE



DETAIL FOR SURFACING OF SIDE ROADS & HOUSE ENTRANCES

▲ 8:1 Slope at the appropriate clear zone shall apply to all mound entrances and mound side roads to 10' fill height. Normal Slope (but not steeper than 6:1) for over 10' fill height.


- Normal Slope (but not steeper than 6:1) at approximate \mathbb{C} Structure or appropriate clear zone width.

On side roads and entrances which slope toward the highway, a low point approx. 6" deep shall be constructed to divert surface drainage into the highway ditch, unless otherwise shown on the plans.

12	01-10-07	Changed bituminous to asphalt	S.W.K.	J.O.B.
11	08-30-06	Changed tack type/rate	S.W.K.	J.O.B.
10	03-24-05	Revised compaction, tack type/rate	S.W.K.	J.O.B.
NO.	DATE	REVISIONS	BY	APP'D

KANSAS DEPARTMENT OF TRANSPORTATION			
<h1 style="margin: 0;">SUMMARY OF QUANTITIES</h1> <h2 style="margin: 0;">(Surfacing)</h2>			
RD051			
FHWA APPROVAL	09-06-06	APP'D. James O. Brewer	
DESIGNED	DETAILED	QUANTITIES	TRACED
DESIGN CK.	DETAIL CK.	QUAN. CK.	TRACE CK.

Drawn By : sallen
File : 029_la852a.dgn
Plotted : 06-SEP-2024 10:30



FERTILIZER: A ratio and application rate that equals or exceeds the required minimum rate per acre of N, P₂O₅, K₂O listed in Summary of Quantities will be acceptable.

- * - N = Nitrogen Rate of Application
- ** - P₂O₅ = Phosphorous Rate of Application
- *** - K₂O = Potassium Rate of Application

The Contractor will be required to finish areas of excavation, borrow and embankment in accordance with the specifications. Areas that require installation or construction of temporary water pollution control items will be finished in reasonable close conformity to the alignment, grade and cross section shown on the plans or as established by the Engineer.

CLT = Construction Limit Tract. This area is defined by the entire disturbed area of the project that requires seeding and erosion control measures to be placed. Any impervious areas (i.e. pavement, gravel, riprap, etc.) shall not be included in this measurement.

Slope = Defined by the area of the project that requires Class 1 erosion control material to be placed. This area shall be seeded using the Soil Erosion Mix prior to placement of the material. Drilling seed is preferred, however, broadcasting is acceptable if drilling is not possible.

Channel = Defined by the area of the project that requires Class 2 erosion control material to be placed. This area shall be seeded using the Soil Erosion Mix prior to placement of the material. Drilling seed is preferred, however, broadcasting is acceptable if drilling is not possible.

GENERAL NOTES

The entire disturbed area, excepting the paved or surfaced areas, steep rocky slopes and areas of undisturbed native sod or other desirable vegetation shall be fertilized (limed when required), seeded, and mulched. Soil preparation shall conform to the Standard Specifications.

Temporary seeding shall be done during any time of the year that the soil can be cultivated. After the temporary seeding has been completed on the entire project, permanent seeding shall be done during the normal seeding season.

MULCHING: Mulch shall be spread uniformly over all disturbed areas and punched in the soil, unless otherwise noted on the plans. The rate of application per acre, thickness in place, for the mulching materials is generally as follows:

1¾ - 2¼ Tons per Acre = 1½" loose depth spread uniformly over acre.

Agricultural products, such as native prairie hay, used for mulching and erosion control practices, excluding wood based mulch, shall meet the North American Weed Free Forage Standards. Other vegetative mulches are acceptable only with the Engineer's concurrence.

The above rate is a guide. It will be at the discretion of the Engineer to determine what rate is sufficient for adequate protection of newly seeded areas.

NOTE: Temporary Ditch Check (Rock) at Sta. 37+90, Lt.

SUMMARY OF SEEDING / EROSION CONTROL QUANTITIES						
P.L.S. RATE/ ACRE		ACRES		BID ITEM	QUANTITY	UNIT
CLT	SL/CH	CLT	SL/CH			
	80		0.16	Temporary Fertilizer (15 - 30 - 15)	13	LB
20		0.40		Temporary Seed (Canada Wildrye)		LB
45		0.40		Temporary Seed (Grain Oats)		LB
45		0.40		Temporary Seed (Sterile Wheatgrass)		LB
	108.5		0.16	Soil Erosion Mix	17.4	LB
				Erosion Control (Class 1, Type C)	771	SQ YD
				Erosion Control (Class 2, Type E)	16	SQ YD
				Sediment Removal (Set Price)	1	CU YD
				Synthetic Sediment Barrier		LF
				Temporary Berm (Set Price)	1	LF
				Temporary Ditch Check (Rock)	6	CU YD
				Temporary Inlet Sediment Barrier		EACH
				Temporary Sediment Basin		CU YD
				Temporary Slope Drain		LF
				Temporary Stream Crossing		EACH
				Biodegradable Log (9")		LF
				Biodegradable Log (12")		LF
				Biodegradable Log (20")		LF
				Filter Sock (****)		LF
				Geotextile (Erosion Control)	500	SQ YD
				Silt Fence		LF
				SWPPP Design †		LS
				SWPPP Inspection †		EACH
				Water Pollution Control Manager †		EACH
900 lbs / acre		0.40		Mulch Tacking Slurry		LB
2 tons / acre		0.40		Mulching		TON
				Water (Erosion Control) (Set Price)	1	MGAL

NOTE: Projects less than 1 acre shall be bid as "Seeding" by the lump sum. See Permanent Seeding Summary of Seeding Quantities sheet LA850 for further details.

Geotextile (Erosion Control) shall be removed prior to placement of permanent slope protection.

Regreen and Quick Guard are the approved sterile wheatgrass products.

† If the total disturbed area of the project, not just the seeding area, is 1 acre or more, then these bid items must be included.

**** List size of material.

The amount of mulch and mulch tacking slurry in the bid quantities is estimated. (Mulch = Acres of Seeding X 1.5 X 2 Tons/Acre). (Mulch Tacking Slurry = Acres of Seeding X 1.5 X 900Lbs/Acre). The estimated quantity includes mulching associated with both temporary and permanent seeding operations. The total mulch and mulch tacking slurry required shall be determined in the field. The bid item for mulching and mulch tacking slurry shall be paid for according to the Standard Specifications.

Quantities for all erosion control items are estimated to give full flexibility for compliance with the NPDES permit. Final quantities will be determined in the field.

SOIL EROSION MIX		
PLS RATE	NAME	QTY (lb)
0.5	Seed (Blue Grama (Lovington))	0.08
4.5	Seed (Buffalograss (Treated))	0.72
45	Seed (Perennial Ryegrass)	7.20
0.5	Seed (Sand Dropseed)	0.08
7	Seed (Side Oats Grama (El Reno))	1.12
45	Seed (Tall Fescue (Endophyte Free))	7.20
6	Seed (Western Wheat (Barton))	0.96
108.5	Total (lb)	17.36


The Soil Erosion Mix is to be placed under the Class 1 and/or Class 2 erosion control material.

The Soil Erosion Mix consists of the Shoulder Area of the Permanent Seed Mix used on the project.


STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	29	53

03	08-03-20	Added Note			M.R.D.	M.L.
02	12-01-17	Revised Standard			M.R.D.	S.H.S.
01	06-01-17	Revised Standard			M.R.D.	S.H.S.
NO.	DATE	REVISIONS			BY	APP'D
KANSAS DEPARTMENT OF TRANSPORTATION						
TEMPORARY EROSION AND POLLUTION CONTROL						
LA852A						
FHWA APPROVAL		01-26-18		APP'D.		Scott H. Shields
DESIGNED	M.R.D.	DETAILED	M.R.D.	QUANTITIES	TRACED	
DESIGN CK.	S.H.S.	DETAIL CK.	S.H.S.	QUAN.CK.	TRACE CK.	

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	31	53




TYPICAL PLAN VIEW OF
TEMPORARY BERM AND
TEMPORARY SLOPE DRAIN
NO SCALE




TYPICAL PROFILE OF TEMPORARY SLOPE DRAIN
NO SCALE

- NOTES:
- 1) Temporary Slope Drain and Temporary Berm may be used on either project foreslopes or project backslopes.
 - 2) Discharge of Slope Drains shall be into stabilized ditch or area, or into Sediment Basin.
 - 3) Pipe shall be secured in place as approved by Engineer.
 - 4) Temporary Berms under 2,000 feet shall be bid by Set Price.




SECTION A-A
NO SCALE



SECTION B-B
NO SCALE

TYPICAL PROFILE OF TEMPORARY BERM
NO SCALE




TEMPORARY STREAM CROSSING (ARTICULATED CONCRETE BLOCKS)
NO SCALE

Pipe size may vary.

Place 1 pipe buried 6" into stream bottom, in the lowest point of the channel to allow the passage of aquatic organisms, with additional pipes placed along the remainder of the stream channel bottom such that ordinary high water (OHW) flows designated in the Contract Documents shall flow through the pipes without overtopping the crossing.

Clean aggregate fill will extend a minimum of 50' on the entrance and exit side of the crossing to prevent tracking. The aggregate shall be clean aggregate and a minimum of 6" thick and will be maintained through the use of the crossing.

See KDOT Specifications for more information.



SECTION B-B
TEMPORARY STREAM CROSSING (AGGREGATE)
NO SCALE

Pipe size may vary.


Place 1 pipe buried 6" into stream bottom, in the lowest point of the channel to allow the passage of aquatic organisms, with additional pipes placed along the remainder of the stream channel bottom such that ordinary high water (OHW) flows designated in the Contract Documents shall flow through the pipes without overtopping the crossing.

Clean aggregate fill will extend a minimum of 50' on the entrance and exit side of the crossing to prevent tracking. The aggregate shall be clean aggregate and a minimum of 6" thick and will be maintained through the use of the crossing.


See KDOT Specifications for more information.

NO.	DATE	REVISIONS	BY	APPD
03	01-21-22	Temp Stream Crossing - Clean Aggregate Fill Note Added	M.R.D.	M.L.
02	08-24-21	Temp Stream Crossing - Clean Aggregate Fill Note Added	M.R.D.	M.L.
01	06-11-13	Revised Standard	M.R.M.	S.H.S.
KANSAS DEPARTMENT OF TRANSPORTATION				
TEMPORARY EROSION AND POLLUTION CONTROL				
TEMPORARY SLOPE DRAIN, TEMPORARY STREAM CROSSING (AGGREGATE)				
LA852B				
FHWA APPROVAL		01-21-22	APPD.	Mervin Lare
DESIGNED	DETAIL	QUANTITIES	TRACED	
DESIGN CK.	DETAIL CK.	QUAN. CK.	TRACE CK.	


STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	32	53




PLAN
TEMPORARY I NLET SEDI MENT BARRI ER
(TRI ANGULAR SI LT DI KE METHOD)
NO SCALE



SECTION A - A



SECTION B - B




CURB INLET PROTECTION

1. If multiple gravel bags are required, place them in such a way that no gaps are evident.
2. Height of bags (8" minimum diameter) must not be above top of curb.
3. Alternative products may be used other than gravel bags such as the "Gutter Buddy". Products must be approved by the Engineer.
4. Curb inlet protection will be measured and paid for as Filter Sock.

Bags = synthetic net (3mm mesh) or burlap bags


Rock = approximately 1" to 2" diameter



Drop inlet use
1'-6" TO 1'-8" diameter log
BIODEGRADABLE LOG/FILTER SOCK
DROP INLET PROTECTION

Note: 25% of log shall be keyed into ground during installation.
Stake every 4'

Material Requirements
Use 100% shredded mulch or other non-compost biodegradable material as fill for logs.
No compost or fines.
No hay or straw.
Do not use material which prohibits water infiltration.
Log Mesh: Use mesh with 1/4" openings or larger. Mesh must allow water infiltration but also hold fill material in place.



PLAN
SECTION C - C


TEMPORARY I NLET SEDI MENT BARRI ER
(SI LT FENCE METHOD)
NO SCALE

- SILT FENCE:
1. Stakes shall be 4' (min.) long and of one of the following materials:
 - a. Hardwood - 1 3/4" x 1 3/4";
 - b. Southern Pine (No. 2) - 2 5/8" x 2 5/8";
 - c. Steel U, T, L, or C Section - .95 lbs. per 1'-0"; or
 - d. Synthetic - same strength as wood stakes.
 2. Cross pieces shall be of same material as stakes.
 3. Attach fence fabric securely on 6" centers (max).
 4. Use of high flow material is acceptable.
 5. Refer to plan sheets to estimate the length of silt fence required.





03	09-26-19	Changed Direction of Main Flowline of Ditch Arrow	M.R.D.	S.H.S.
02	03-10-15	Revised Standard	R.A.	S.H.S.
01	06-01-13	Revised Standard	M.R.M.	S.H.S.
NO.	DATE	REVISIONS	BY	APPD

KANSAS DEPARTMENT OF TRANSPORTATION				
TEMPORARY EROSION AND POLLUTION CONTROL, TEMPORARY INLET SEDIMENT BARRIER (SILT FENCE) TEMP. INLET SEDIMENT BARRIER (T.S.D.) LA852C				
DESIGNED	R.A.	DETAILED	R.A.	QUANTITIES
DESIGN CK.	S.H.S.	DETAIL CK.	S.H.S.	QUAN. CK.
FHWA APPROVAL			03-10-15	APPD.
			Scott H. Shields	
			TRACED	
			TRACE CK.	

Drawn By : bfranz
File : 033_la852d.dgn
Plotted : 10-JUN-2024 16:21



SILT FENCE BARRIER
NO SCALE



INSTALLATION NOTES

- SILT FENCE:
- Stakes shall be 4' (min.) long and of one of the following materials:
 - Hardwood - 1 $\frac{3}{16}$ " x 1 $\frac{3}{16}$ ";
 - Southern Pine (No. 2) - 2 $\frac{5}{8}$ " x 2 $\frac{5}{8}$ ";
 - Steel U, T, L, or C Section - .95 lbs. per 1'-0"; or
 - Synthetic - same strength as wood stakes.
 - Attach fence fabric with 3 zip ties within the top 8" of the fence
Alternate attachment methods may be approved by the Engineer on a performance basis.
 - Use of high flow material is acceptable.
 - Refer to plan sheets to estimate the length of silt fence required.

BIODEGRADABLE LOG OR FILTER SOCK

- Place biodegradable logs or filter sock tightly together minimum overlap of 18".
- Wood stakes shall be 2" x 2" (nom.).
- Refer to plan sheets to estimate length of biodegradable log and filter sock required.
- Each log or sock (except compost filter socks) should be keyed into the ground at a minimum of 25% of its height. Compost filter socks should be placed on smooth prepared ground with no gaps between the sock and soil.
- Length of stakes should be 2 times the height of the log at a minimum with minimum ground embedment equal to the height of the log / sock.

Biodegradable Log or Filter Sock Slope Interruptions

		PRODUCT		
		9" Sediment Log or 8" Filter Sock (ft)	12" Sediment Log or 12" Filter Sock (ft)	20" Sediment Log or 18" Filter Sock (ft)
Slope Gradient	≤4H:1V	40	60	80
	3H:1V	30	45	60


Deviations should be approved by the Field Engineer.

BIODEGRADABLE LOG MATERIAL		
	LOW FLOW	HIGH FLOW
9"	Straw/Compost	Excelsior / Wood Chips / Coconut Fiber
12"	Straw/Compost	Excelsior / Wood Chips / Coconut Fiber
18"-20"	Straw/Compost	Excelsior / Wood Chips / Coconut Fiber

GENERAL NOTES

- Slope interruptions shall be placed along contour lines, with a short section turned upgrade at each end of the barrier.
- The maximum length of the slope interruptions shall not exceed 250 feet, and the barrier ends need to be staggered.
- Interruptions damaged by Contractor's negligence, including improper maintenance or lack of maintenance, shall be repaired immediately by Contractor at no additional cost to KDOT.
- Agricultural products, such as native prairie hay, used for mulching and erosion control practices, excluding wood based mulch, shall meet the North American Weed Free Forage Standards.

03	06-28-16	Revised Standard	R.A.	S.H.S.
02	03-01-15	Revised Standard	R.A.	S.H.S.
01	06-01-13	Revised Standard	M.R.M.	S.H.S.
NO.	DATE	REVISIONS	BY	APPD
KANSAS DEPARTMENT OF TRANSPORTATION				
TEMPORARY EROSION AND POLLUTION CONTROL SLOPE INTERRUPTIONS BIODEGRADABLE LOG / SILT FENCE LA852D				
FHWA APPROVAL		09-14-16	APPD.	Scott H. Shields
DESIGNED	S.H.S.	DETAILED	R.A.	QUANTITIES
DESIGN CK.	S.H.S.	DETAIL CK.	QUAN.CK.	TRACE CK.



TYPICAL DITCH CHECK LAYOUT PLAN
NO SCALE

20" BIOLOG CHECK SPACING	
DITCH @ SLOPE (%)	SPACING INTERVAL (FEET)
1.0	125
2.0	60
3.0	40
4.0	30
5.0	25
NOTE: Use this spacing for all except Rock Ditch Checks.	



18" FILTER SOCK CHECK SPACING	
DITCH @ SLOPE (%)	SPACING INTERVAL (FEET)
1.0	110
2.0	55
3.0	35
4.0	25
5.0	20
NOTE: Use this spacing for all except Rock Ditch Checks.	

GENERAL NOTES

- 1) The choice of ditch check methods is at the option of the Contractor.
- 2) Use only rock checks in situations where the ditch slope is 6 percent or greater.
- 2) Ditch checks damaged by Contractor's negligence, including improper maintenance or lack of maintenance, shall be repaired by Contractor at no extra cost to KDOT.

03	08-10-16	Revised Standard			R.A.A.	S.H.S.
02	06-28-16	Revised Standard			R.A.A.	S.H.S.
01	06-01-13	Revised Standard			M.R.M.	S.H.S.
NO.	DATE	REVISIONS			BY	APP'D
KANSAS DEPARTMENT OF TRANSPORTATION						
TEMPORARY EROSION AND POLLUTION CONTROL DITCH CHECKS						
LA852E						
FHWA APPROVAL		09-14-16		APP'D.		Scott H. Shields
DESIGNED	S.H.S.	DETAILED	R.A.A.	QUANTITIES	TRACED	R.A.A.
DESIGN CK.	S.H.S.	DETAIL CK.	S.H.S.	QUAN.CK.	TRACE CK.	S.H.S.

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	35	53



TYPICAL ELEVATION



ROCK DITCH CHECK

NO SCALE

TEMPORARY ROCK DITCH CHECK SPACING	
DITCH ϕ SLOPE (%)	SPACING INTERVAL (FEET)
5.0	60
6.0	50
7.0	43
8.0	36
9.0	33
10.0	29
NOTE: Use this spacing for Rock Ditch Checks only.	

ROCK DITCH CHECK NOTES



1. Rock shall be clean aggregate, D50-6" and aggregate filler.
2. Place rock in such manner that water will flow over, not around ditch check.
3. Do not use rock ditch checks in clear zone.
4. Excavation: The ditch area shall be reshaped to fill any eroded areas. Prior to placement of the rock, the ditch shall be excavated to the dimensions of the Rock Ditch Check and to a minimum depth of 6" (150mm). After placement of the rock, backfill and compact any over-excavated soil to ditch grade. This work shall be subsidiary to the bid item Temporary Ditch Check (Rock).
5. Aggregate excavated on site may be used as an alternate to the 6" rock, if approved by the Engineer.
6. The Engineer may approve the use of larger aggregates for the downstream portion of the check when conditions warrant their use.
7. When the use of larger rock is approved, D50-6" rock will be placed between the larger aggregate and the aggregate filler.
8. Aggregate filler will be placed on the upstream face of the ditch check. Aggregate filler will comply with Filter Course Type I, Division 1114.



TYPICAL ELEVATION

BIODEGRADABLE LOG DITCH CHECK

OR Filter Sock Ditch Check
NO SCALE



ALT. DETAIL
OPTIONAL


BIODEGRADABLE LOG DITCH CHECK NOTES

1. Use as many biodegradable log sections as necessary to ensure water does not flow around end of ditch check.
2. Overlap sections a minimum of 18".
3. Stakes shall be wood or steel according to Section 2114 of the Standard Specifications. Length of stakes shall be a minimum of 2 x the diameter of the log.
4. Use Erosion Control (Class 1) (Type C) as the downstream apron when required.
5. A downstream apron is required when directed by the Engineer. Apron material will be paid at the contract unit price.
6. Each log or sock (except compost filter socks) should be keyed into the ground at a minimum of 25% of its height. Compost filter socks should be placed on smooth prepared ground with no gaps between the sock and soil.


03	11-19-20	Revised Standard	M.R.D.	M.L.
02	08-10-16	Revised Standard	R.A.A.	S.H.S.
01	10-21-15	Revised Standard	R.A.A.	S.H.S.
NO.	DATE	REVISIONS	BY	APPD

KANSAS DEPARTMENT OF TRANSPORTATION				
TEMPORARY EROSION AND POLLUTION CONTROL				
ROCK DITCH CHECKS				
BIODEGRADABLE LOG DITCH CHECKS				
LA852G				
FHWA APPROVAL		11-19-20		APPD
DESIGNED	M.L.	DETAILED	D.K.	QUANTITIES
DESIGN CK.	M.L.	DETAIL CK.	M.L.	QUAN. CK.
		Mervin Lare		
		TRACED	R.A.A.	
		TRACE CK.	R.A.A.	


STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	36	53



PARTIAL PLAN PIPE



Limits of Erosion Control Blanket









PARTIAL PLAN BOX CULVERT

INSTALLATION DETAILS FOR EROSION CONTROL CLASS 1

Erosion Control Blankets shall be laid loosely in the direction of the slope, beginning at the bottom of the slope. In order for blanket to be in contact with the soil, lay blanket loosely, avoiding stretching.


- ANCHOR SLOTS: The top of the blanket should be "slotted in" at the top of the slope and anchored in place with anchors 6 inches apart. The slots should be 6 inches wide x 6 inches deep with the blanket anchored in the bottom of the slot, then backfilled, tamped and seeded.
- LONGITUDINAL SEAMS: The edges of the blanket should overlap each other a minimum of 6 inches, with anchors catching the edges of both blankets.
- SPLICE SEAM: When splices are necessary, overlap end a minimum of 8 inches in direction of water flow. Stagger splice seams.
- TERMINAL FOLD: The bottom edge of the blanket shall be turned under a minimum of 4 inches, then anchored in place with anchors 9 inches apart.
- TYPICAL ANCHORS: Anchor design shall be as recommended by the manufacturer.
- STAPLE CHECK: #Establish Staples in 2 rows 4" on center apart. Staple Checks - shall be 30' apart.

● Erosion Control Class I may be omitted if the area is immediately covered by permanent slope protection (where directed by the plans).



PLAN VIEW - ANCHORING DIAGRAM

NOTE:
Agricultural products, such as native prairie hay, used for mulching and erosion control practices, excluding wood based mulch, shall meet the North American Weed Free Forage Standards.
Single post ring and shank staple is acceptable.



ISOMETRIC VIEW


KANSAS DEPARTMENT OF TRANSPORTATION					
INSTALLATION DETAIL EROSION CONTROL CLASS 1 SLOPE PROTECTION					
LA855					
FHWA APPROVAL 03-10-15 APPD. Scott H. Shields					
03	02-23-15	Revised Standard	R.A.A.	S.H.S.	
02	09-15-14	Revised Standard	M.R.M.	S.H.S.	
NO.	DATE	REVISIONS	BY	APPD	
DESIGNED	R.A.A.	DETAILED	R.A.A.	QUANTITIES	TRACED R.A.A.
DESIGN CK.		DETAIL CK.		QUAN.CK.	TRACE CK. R.A.A.

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	37	53


INSTALLATION DETAILS FOR EROSION CONTROL CLASS 2

Erosion Control Mats shall be laid loosely in the direction of the flow, with the first course at the centerline of channel, where applicable. In order for the mat to be in contact with the soil, lay the mat loosely, avoiding stretching.









- ANCHOR FOLD:** The top of the mat should be folded under, buried and secured with approved anchors placed 6 inches apart. The top edge of the mat should be buried in a slot, 6 inches wide x 6 inches deep; anchored in the bottom of the slot, backfilled, and the mat folded over the top as shown in detail.
- LONGITUDINAL SEAMS:** The adjacent edges of the mat should overlap a minimum of 6 inches, with anchors catching the edges of both mats.
- SPLICE SEAM:** When splices are necessary, overlap end a minimum of 12 inches in direction of water flow. Stagger splice seams.
- STAPLE CHECK:** †Establish Staples in 2 rows 4" on center apart. Staple Checks - shall be 30' apart.
- EDGE ANCHOR:** Lay outside edge of mat into trench at top of side slope. Anchor at 3 foot intervals along trench.
- TERMINUS:** The bottom edge of the mat shall be anchored in place with anchors spaced at 9 inch intervals along the terminating edge.
- TYPICAL ANCHORS:** Anchor design shall be as recommended by the manufacturer.



PLAN VIEW - ANCHORING DIAGRAM



CROSS SECTION (Ditch Lining)




Direction of Water Flow

ISOMETRIC VIEW

04	09-25-15		Modified Staple Check		R.A.A.	S.H.S.
03	09-15-14		Revised Standard		R.A.A.	S.H.S.
02	03-01-13		Revised Standard		M.R.M.	S.H.S.
NO.	DATE		REVISIONS	BY	APPD	
KANSAS DEPARTMENT OF TRANSPORTATION						
INSTALLATION DETAIL						
EROSION CONTROL CLASS 2						
FLEXIBLE CHANNEL LINER						
LA856						
FHWA APPROVAL						
11-02-15 APPD. Scott H. Shields						
DESIGNED	R.A.A.	DETAILED	R.A.A.	QUANTITIES	TRACED	R.A.A.
DESIGN CK.	S.H.S.	DETAIL CK.	S.H.S.	QUAN. CK.	TRACE CK.	

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	38	53



GRASS & WILDFLOWER SEEDING SEASONS	
COOL SEASON GRASSES	WARM SEASON GRASSES & WILDFLOWERS
February 15 thru April 20 August 15 thru September 30	November 15 thru June 1
SPECIES	SPECIES
Bluegrasses	Bermuda Grass
Brome Grasses	Big Bluestem
Canada Wildrye	Blue Grama
Fescues	Buffalo Grass
Prairie Junegrass	Indiangrass
Ryegrasses	Little Bluestem
Sterile Wheatgrass	Sand Bluestem
Tall Dropseed	Sand Dropseed
Western Wheatgrass	Sand Lovegrass
	Side Oats Grama
	Switchgrass
	Wildflower Mixes
<p>When the area to be seeded is 1 acre or more, if Cool Season grasses are mixed with Warm Season grasses, seed the area during the Warm Season.</p> <p>When the area to be seeded is less than 1 acre, seed the area any time of the year.</p>	

GENERAL NOTES

The entire disturbed area, excepting the paved or surfaced areas, steep rocky slopes and areas of undisturbed native sod or other desirable vegetation shall be fertilized (limed when required), seeded and mulched. Soil preparation shall conform to the Standard Specifications except as noted below.

All borrow areas shown on the plans are to be fertilized, seeded, and mulched. However, operation in borrow areas where crops are growing may be omitted when requested by the owner.

If temporary cover has provided stable slopes with no erosion, seed the permanent grasses into the existing cover. If there has been erosion that requires repair prior to seeding, then it may be necessary to regrade the area, resulting in bare ground.

FERTILIZER: A ratio and application rate that equals or exceeds the required minimum rate per acre of N, P₂O₅, K₂O listed in Summary of Seeding Quantities will be acceptable.

MULCHING: Mulch shall be spread uniformly over all disturbed areas and punched in the soil, unless otherwise noted on the plans. The rate of application per acre, thickness in place, for the mulching material is generally as follows:

1¾ - 2¼ Tons per Acre = 1½" loose depth spread uniformly over acre.

Agricultural products, such as native prairie hay, used for mulching and erosion control practices, excluding wood based mulch, shall meet the North American Weed Free Forage Standards.

Other vegetative mulches are acceptable only with the Engineer's concurrence.

The above rate is a guide. It will be at the discretion of the Engineer to determine what rate is sufficient for adequate protection of newly seeded areas.

SODDING SEASONS	
COOL SEASON GRASSES	WARM SEASON GRASSES
March 1 thru April 15 September 1 thru November 15	May 15 thru September 1
SPECIES	SPECIES
Bluegrass Sod	Buffalo Grass Sod
Fescue Sod	

If the soil is workable, the Engineer may allow placement of sod between November 15 and March 1. If sod is placed during this time, maintain the sod until 20 days after the beginning of the spring sodding season.

NATIVE WILDFLOWER MIX 1		
PLS RATE	NAME	QTY (lb)
0.3	Butterfly Milkweed	
0.3	Common Milkweed	
0.3	Black Eyed Susan	
0.5	Blanket Flower	
0.5	False Sunflower	
0.5	Lance-Leaf Coreopsis	
0.2	Maximilian Sunflower	
0.1	New England Aster	
0.2	Pinnate Prairie Coneflower	
0.2	Plains Coreopsis	
0.3	Purple Coneflower	
0.3	Upright Prairie Coneflower	
0.3	Dames Rocket	
0.3	Lemon Mint	
0.2	Pitcher Sage	
0.2	Wild Bergamot	
1.0	Illinois Bundleflower	
0.2	Common Evening Primrose	
0.1	Hoary Verbena	
0.8	Purple Prairie Clover	
0.3	Roundhead Lespedeza	
3.0	Showy Partridge Pea	
0.2	White Prairie Clover	
10.3	Total (lb)	

NATIVE WILDFLOWER MIX 2		
PLS RATE	NAME	QTY (lb)
0.3	Butterfly Milkweed	
0.3	Black Eyed Susan	
0.5	Black Sampson Coneflower	
1.0	Blanket Flower	
0.2	Maximilian Sunflower	
0.2	Plains Coreopsis	
0.2	Upright Prairie Coneflower	
0.2	Western Yarrow	
0.3	Lemon Mint	
0.4	Pitcher Sage	
1.5	Illinois Bundleflower	
0.2	Common Evening Primrose	
1.0	Blue Wild Indigo	
0.4	Leadplant	
0.4	Purple Prairie Clover	
0.3	White Prairie Clover	
7.4	Total (lb)	

Package and deliver the wildflower seed separately from the grass seed mix. Package and deliver the Tall Drop Seed separately from the grass seed and the wildflower mix. Place the grass seed (except Tall Drop Seed) in the large seed box and drill (cover) seed $\frac{1}{8}$ " - $\frac{1}{4}$ ". Place the wildflower seed in a separate seed box and drill (cover) seed $\frac{1}{16}$ " maximum. Place the Tall Drop Seed in a separate (third) seed box and place the seed (using the seed drill) on the soil surface.

OPTION: Broadcast Tall Drop Seed on the soil surface.

P.L.S. RATE/ACRE				ACRES				BID ITEM	QUANTITY	UNIT
SHLDR	OTHER			SHLDR	OTHER					
0.5				0.4				Seed (Blue Grama (Lovington))		Lbs
4.5				0.4				Seed (Buffalograss (Treated))		Lbs
45				0.4				Seed (Perennial Ryegrass)		Lbs
0.5				0.4				Seed (Sand Dropseed)		Lbs
7				0.4				Seed (Side Oats Grama (El Reno))		Lbs
45				0.4				Seed (Tall Fescue (Endophyte Free))		Lbs
6				0.4				Seed (Western Wheat (Barton))		Lbs
								Seeding	Lump Sum	LS
								Mulching *		

SHLDR = Seeded with the Shoulder Mix. Typically 15 feet for 2-lane roads and 30 feet for 4-lane roads. Includes outside roadsides, turfed portions of shoulders, and turfed portion of the median.

OTHER = Seeded with the "Other" Mix. Designated as all other turf areas, except the Shoulder. Usually includes a Native Wildflower Mix.

NOTE: Projects less than 1 acre shall be bid as "Seeding" by the lump sum. All disturbed areas shall be seeded, fertilized and mulched at the listed rate per acre. The acres are estimated.


Refer to the Standard Specifications, Division 900, Section 904 'Seeding', and Section 907 'Sodding', for the seeding and sodding seasons.

* See LA852A for mulching quantity. The quantity of mulch is estimated (Acres of Seeding X 1.5 X 2 Tons/Acre). The total mulch required shall be determined in the field. The bid item for mulching shall be paid for according to the Standard Specifications.

02	11-25-20	Updated Seeding / Sodding Periods Charts	M.R.D.	M.L.
01	08-03-20	Revised Standard	M.R.D.	S.H.S.
NO.	DATE	REVISIONS	BY	APP'D
<p>KANSAS DEPARTMENT OF TRANSPORTATION</p> <p>PERMANENT SEEDING SUMMARY OF SEEDING QUANTITIES</p> <p>LA850</p>				
FHWA APPROVAL		05-06-19	APP'D.	Mervin Lare
DESIGNED	DETAILED	QUANTITIES	TRACED	
DESIGN CK.	DETAIL CK.	QUAN.CK.	TRACE CK.	

Drawn By : bfranz
File : 039_te700.dgn
Plotted : 10-JUN-2024 16:21

- 1) Design Speed: Those items delegated to temporary traffic control should be designed and installed using the posted/legal speed of the roadway prior to work starting.
- 2) Minimum Lane Width: Lane widths shall be a minimum of 11' (measured between centerlines of pavement markings) or as shown on the plans, or as directed by the engineer. A lane width less than 11' may require restricted roadway width signing.
- 3) Consideration should be made to separate pedestrian and, if needed, bicycle movements from both work site activity and vehicular traffic. Unless a reasonable safe route that does not involve crossing the roadway can be provided, pedestrians should be appropriately directed with advance signing that encourages them to cross to the opposite side of the roadway. In urban and suburban areas with high vehicular traffic volumes, these signs should be placed at intersections (rather than midblock locations) so that pedestrians are not confronted with midblock work sites that will induce them to attempt skirting the work site or making a midblock crossing.
- 4) When existing pedestrian facilities are disrupted, closed, or relocated, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility.
- 5) When the driving surface open to traffic is milled or is a temporary surface made of loose material, or when directed by the engineer a W8-15 (Grooved Pavement) or W8-7 (Loose Gravel) sign shall be used on mainline approaches. This sign should be placed a "C" distance after the W20-1 (Road Work Ahead) sign. A W8-15p motorcycle plaque shall be used to supplement the W8-15 or W8-7 signs. All signs shall be displayed as long as the condition is present.
- 6) Alternative temporary rumble strip options may be available. Please contact the Temporary Traffic Control Unit for more information at 785-296-1179 or 785-296-1183.



TYPICAL WORK ZONE COMPONENTS

✱ When concrete barrier system is used, portable channelizing devices are not needed along the tangent barrier section.

Minimum advance warning sign spacing (in feet):

SPEED (MPH) ✱	A	B	C
URBAN (40 MPH OR LOWER)	100	100	100
URBAN (45 MPH OR HIGHER)	350	350	350
RURAL (55 MPH OR LOWER)	500	500	500
RURAL (60 MPH OR HIGHER)	750	750	750
EXPRESSWAY/FREEWAY	1000	1500	2640

- ✱ Posted speed prior to work starting
- The minimum spacing between signs shall be no less than 100', unless directed by the engineer.
- The spacing between any signs may be increased beyond the minimum values in the table above as approved by the engineer in order to maximize visibility.

Taper Formulas:

$L = WS$ for speeds of 45 MPH or more

$L = WS^2/60$ for speeds of 40 MPH or less

Where: L = Minimum length of taper in feet
 S = Numerical value of posted speed prior to work starting in MPH
 W = Width in offset feet

Shifting Taper= $1/2 L$
Shoulder Taper= $1/3 L$

Channelizer Placement:

- The spacing between devices in transition area (taper) should not exceed a distance in feet equal to $1/2$ the posted speed limit in mph prior to work starting.
- The spacing between devices in the advanced warning area and the activity area should not exceed a distance in feet equal to two times the posted speed limit in mph prior to work starting.
- Channelizing devices shall be placed for optimum visibility, normally at right angles to the traffic flow.
- Place directional indicator barricades in series to direct traffic onto the new path. The arrow sign should not be visible to opposing traffic.
- Alternating diagonal orange and white striping must slope downward in the direction traffic is expected to pass.









Buffer Space

SPEED (MPH) ✱	20	25	30	35	40	45	50	55	60	65	70	75
LENGTH (ft)	115	155	200	250	305	360	425	495	570	645	730	820

- ✱ Posted speed prior to work starting
- Neither work activity nor storage of equipment, vehicles, or material should occur in the buffer space. When a protection vehicle is placed in advance of the work space, only the space upstream of the vehicle constitutes the buffer space.
- If temporary concrete safety barrier system is used to separate approaching traffic from the work space, the barrier system shall be considered part of the activity area. A full lane width should be available throughout the length of the buffer space. See typical work zone components above.

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	39	53

02	03-13-18	W8-15p usage changed to Shall	R.W.B.	E.K.G.
01	08-18-15	Channelizer spacing info	R.W.B.	K.E.
NO.	DATE	REVISIONS	BY	APPD
KANSAS DEPARTMENT OF TRANSPORTATION				
TRAFFIC CONTROL GENERAL NOTES				
TE700				
FHWA APPROVAL			03-13-18	APPD.
DESIGNED	B.A.H.	DETAILED	R.W.B.	QUANTITIES
DESIGN CK.	DETAIL CK.	QUAN.CK.	TRACE CK.	



TYPE 2 BARRICADE

For rails less than 36" long, 4" wide stripes may be used.
All stripes shall slope downward to the traffic side for channelization.

VERTICAL PANEL

The stripes shall slope downward to the traffic side for channelization.

DIRECTION INDICATOR BARRICADE

The stripes shall slope downward in the direction traffic is to pass.
The direction indicator barricade shall be used in series to direct the motorist into the intended lane of travel.

PEDESTRIAN CHANNELIZER






- Support device shall not project beyond the detection plate into the pathway.
- Hand trailing edges and detection plates are optional for continuous walls.
- Interconnect pedestrian channelizers to prevent displacement and to provide continuous guidance through or around work.
- Alternate pathways shall be firm, stable, and slip resistant.
- Treat height differentials > 1/2" in the surfaces of alternate paths with a firm, stable, and slip resistant temporary ramp having a slope of 12:1 or flatter and having a width equal to the alternate path.
- Use alternating orange/white on interconnected devices.

Location		Cross-overs	Shoofly Divisions	Tangents	Tapers	Ramps	Head to Head	Object Identifier	Lead-in Devices	Gores
Portable	Drums	Yes	Yes	Yes	Yes	Yes	(1)	Yes	Yes	Yes
	Conical Delineators	Yes	Yes	Yes	Yes	Yes	(1)	Yes	Yes	Yes
	Vertical Panels	(2)	(2)	(2)	(2)	(2)	(1,2)	Yes	(2)	(2)
	Direction Indicator Barricade	No	No	No	Yes	No	No	No	No	No
	Type 2 Barricade	(2)	(2)	(2)	(2)	No	No	Yes	No	No
	Traffic Cones	No	No	(4)	(4)	(4)	No	(4)	(4)	(4)
Fixed										
	Tubular Markers	(3)	(3)	(3)	No	(3)	Yes	No	Yes	Yes
	Vertical Panels	(3)	(3)	(3)	(3)	(3)	(3)	Yes	(2,3)	(2)

- (1) Not allowed on centerline delineation along freeways or expressways.
(2) The stripes shall slope downward to the traffic side for channelization.
(3) May be used upon the approval of the engineer.
(4) Daytime operations only.

NO.	DATE	REVISIONS	BY	APPD
KANSAS DEPARTMENT OF TRANSPORTATION				
TRAFFIC CONTROL CHANNELIZING DEVICES				
TE702				
FHWA APPROVAL 06-01-15 APPD. Kristina Ericksen				
DESIGNED	L.E.R.	DETAILED	R.W.B.	QUANTITIES
DESIGN CK.	DETAIL CK.	QUAN.CK.	TRACE CK.	TRACE CK.

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	41	53



ROAD CLOSED GENERAL NOTES

As shown in Figure 1, at the point where thru traffic must detour and local traffic can proceed to the location where the roadway is completely closed, the R11-3a (ROAD CLOSED # MILES AHEAD LOCAL TRAFFIC ONLY) or R11-4 (ROAD CLOSED LOCAL TRAFFIC ONLY or ROAD CLOSED TO THRU TRAFFIC) sign shall be used with Type 3 barricades (winged position), placed on the shoulders of roadway.

As shown in Figure 3, when local traffic must be allowed access into the work zone, Type 3 barricades shall be longitudinally staggered to maintain the appearance of a closed roadway. A second line of end-to-end Type 3 barricades shall be placed just beyond the last access point in the work zone, to completely close the roadway.

The R11-4 (ROAD CLOSED TO THRU TRAFFIC or ROAD CLOSED LOCAL TRAFFIC ONLY) sign shall be used when the distance to the point of complete closure of the roadway is less than 1 mile.


The R11-3a (ROAD CLOSED # MILES AHEAD LOCAL TRAFFIC ONLY) sign shall be used when the distance to the point of complete closure of the roadway is 1 mile or greater.

The words "BRIDGE OUT" (or BRIDGE CLOSED) may be substituted for the words "ROAD CLOSED" on the R11-3a or R11-4 sign where applicable.

NO.	DATE	REVISIONS					BY	APP'D	
KANSAS' DEPARTMENT OF TRANSPORTATION									
<p style="text-align: center;">TRAFFIC CONTROL CLOSURES</p>									
TE704									
FHWA APPROVAL		06-01-15		APP'D.		Kristina Erickson			
DESIGNED	B.A.H.	DETAILED	R.W.B.	QUANTITIES		TRACED			
DESIGN CK.		DETAIL CK.		QUAN.CK.		TRACE CK.			

Drawn By : bfranz
File : 042_te710.dgn
Plotted : 10-JUN-2024 16:21

SIGN LAYOUT INFORMATION



KG20-2

Std. Size
Expwy/Freeway

6" C
48"x 24"



KG20-5

Std. Size
Expwy/Freeway

6" C
48"x 24"



KM4-20

Std. Size
3" C
24"x 6"

Expwy/Freeway
6" C
48"x 12"



W7-3a

Mileage to be Determined
by the Engineer.



W8-17

Std. Size
Expwy/Freeway
48"x 48"



W8-17P
(Optional)

Std. Size
Expwy/Freeway
30"x 24"



W8-15

Std. Size
Expwy/Freeway


8" D
48"x 48"



W8-7

Std. Size
Expwy/Freeway

8" D
48"x 48"



W8-15p


Std. Size
Expwy/Freeway

30"x 24"



W8-11


Std. Size
Expwy/Freeway
8" D
48"x 48"



SP-01
(Special Sign)

Std. Size
6" C

Expwy/Freeway
10" D




SP-02
(Special Sign)

Std. Size
Uppercase: 6" C
Lowercase: 4.5" C

Expwy/Freeway
Uppercase: 10" D
Lowercase: 8" D

All city names and street names on special signs and destination signs
must have upper and lower case letters.




RURAL

1) Ground-mounted signs shall be mounted at a minimum height of 5' measured from the bottom of sign to the near edge of the pavement.

2) Large signs having an area exceeding 50 square feet installed on multiple breakaway posts shall be mounted a minimum of 7' above the ground.

3) The height of the secondary sign mounted below another sign may be 4' measured from the bottom of the sign to the near edge of the pavement. Signs shall not overlap each other.



URBAN

1) Signs shall be mounted at a minimum height of 7' measured from the bottom of sign to the near edge of the pavement.


2) Neither portable nor permanent sign supports should be located on sidewalks or areas designated for pedestrian or bicycle traffic.

3) Signs mounted lower than 7' should not project more than 4" into pedestrian facilities.

4) The height from of the secondary sign mounted below another sign may be 6' measured from the bottom of sign to the near edge of the pavement. Signs shall not overlap each other.


5) Large signs having an area exceeding 50 square feet installed on multiple breakaway posts shall be mounted a minimum of 7' above the ground.

* 6) Pedestrian detour signing shall be a minimum of 2' measured from the top of the pedestrian pathway to the bottom of the sign and shall not protrude into the walkway nor shall it project beyond the back of curb.




When the sign width is equal to or greater than 9', three or more wood posts may be used with a minimum of 4' between the centerline of each post. All signs less than 9' in width shall use a maximum of two wood posts.

In the case of hitting rock when driving posts
1. Shift the sign location. Do not violate minimum sign spacing.
2. With the engineer's approval, use acceptable alternative sign stands.



KI-104a



KI-105a

Dimensions in inches

Spacings are to start of next letter

Y FONT	LETTER SPACINGS																HT LEN
23.0 D	9.7	6.4	3.2	7.3	6.4	5.4	9.7										8.0
																	28.6
11.0 D	3.9	6.9	7.5	7.3	6.4	4.9	3.9										8.0
																	40.3
4.0 D	3.1	1.6	2.7	3.2	4.3	3.8	3.6	2.8	3.2	3.4	3.8	3.6	3.2	2.7	3.1		4.0
																	41.8

Notes:

Typically, there are two sets of informational signs installed per project: one for each direction of traffic.

Install signs a minimum of 500' in advance of the road work ahead sign. The engineer may designate a more appropriate location if conditions dictate.

The informational signs are not to interfere with the traffic control signs for the project.


STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	42	53

Sign Number	GIVE EM A BRAKE
Width x Height	4'-0" x 4'-0"
Border Width	1.0"
Corner Radius	4.0"
Stripe Width	3.0"
Mounting	Ground
Background	Type: Non-Reflective
Legend/Border	Color: Black
Legend Font	Type: Reflective
Legend Font	Color: White
Legend Font	Dutch 801 Roman SWC
Legend Font	25 Degree Slant
Stripes	Type: Reflective
Stripes	Color: Orange


Sign Number	FINES DOUBLE
Width x Height	4'-0" x 3'-0"
Border Width	0.9"
Corner Radius	3.0"
Mounting	Ground
Background	Type: Reflective
Legend/Border	Color: White
Legend/Border	Type: Non-Reflective
Legend/Border	Color: Black

NO.	DATE	REVISIONS	BY	APPD	
KANSAS DEPARTMENT OF TRANSPORTATION					
TRAFFIC CONTROL SIGN INFORMATION					
TE710					
FHWA APPROVAL 06-01-15 APPD. Kristina Ericksen					
DESIGNED	R.W.B.	DETAILED	R.W.B.	QUANTITIES	TRACED
DESIGN CK.	DETAIL CK.	QUAN CK.	TRACE CK.		


PERFORATED SQUARE STEEL TUBE (P.S.S.T.) POST SETUP




P.S.S.T. Detail



Telescoping P.S.S.T. Detai



Section A-A




Section B-B


Details for 2", 2 1/4", or 2 1/2" sign posts

Place bolts in the same corner along each sign post

WOOD POST SETUP




Side Elevation



Side Elevation

4" x 6" Wood Post in Soil




Section A-A

Section B-B

Front Elevation

See TE710 for Additional
Details and Requirements


3 LB/F U-CHANNEL SETUP



Notes

Place two bolts at both ends of the splice through the holes nearest the ends of the splice.

Use manufacturer recommended spacers over the bolts between the spliced pieces of U-Channel.



NO.	DATE	REVISIONS						BY	APP'D
KANSAS DEPARTMENT OF TRANSPORTATION									
<div style="text-align: center;"><h1>TRAFFIC CONTROL SIGN POSTS</h1></div>									
TE712									
FHWA APPROVAL		06-01-15		APP'D		Kristina Erickson			
DESIGNED	B.A.H.	DETAILED	R.W.B.	QUANTITIES		TRACED			
DESIGN CK.		DETAIL CK.		QUAN.CK.		TRACE CK.			

Drawn By : bfranz
File : 045-XS_CL_5Scale_Sheets.dgn

Plotted : 10-JUN-2024 16:22

Scale

Centerline

STA. 33 + 50.00 TO STA. 35 + 38.55

SCALE = 1:5

CADconform

Certify This File

53

45

80

75

70

65

60

55

50

45

40

35

30

25

20

15

10

5

0

5

10

15

20

25

30

35

40

45

50

55

60

65

70

75

80

80

75

70

65

60

55

50

45

40

35

30

25

20

15

10

5

0

5

10

15

20

25

30

35

40

45

50

55

60

65

70

75

80

80

75

70

65

60

55

50

45

40

35

30

25

20

15

10

5

0

5

10

15

20

25

30

35

40

45

50

55

60

65

70

75

80

80

75

70

65

60

55

50

45

40

35

30

25

20

15

10

5

0

5

10

15

20

25

30

35

40

45

50

55

60

65

70

75

80

80

75

70

65

60

55

50

45

40

35

30

25

20

15

10

5

0

5

10

15

20

25

30

35

40

45

50

55

60

65

70

75

80

80

75

70

65

60

55

50

45

40

35

30

25

20

15

10

5

0

5

10

15

20

25

30

35

40

45

50

55

60

65

70

75

80

80

75

70

65

60

55

50

45

40

35

30

25

20

15

10

5

0

5

10

15

20

25

30

35

40

45

50

55

60

65

70

75

80

80

75

70

65

60

55

50

45

40

35

30

25

20

15

10

5

0

5

10

15

20

25

30

35

40

45

50

55

60

65

70

75

80

80

75

70

65

60

55

50

45

40

35

30

25

20

15

10

5

0

5

10

15

20

25

30

35

40

45

50

55

60

65

70

75

80

80

75

70

65

60

55

50

45

40

35

30

25

20

15

10

5

0

5

10

15

20

25

30

35

40

45

50

55

60

65

70

75

80

80

75

70

65

60

55

50

45

40

35

30

25

20

15

10

5

0

5

10

15

20

25

30

35

40

45

50

55

60

65


70

75

80

80


Drawn By : bfranz
File : 045-XS_CL_5Scale_Sheets.dgn
Plotted : 10-JUN-2024 16:22



Centerline
STA. 35 + 52.98 TO STA. 36 + 00.00
SCALE = 1:5


STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	46	53

Drawn By : bfranz
File : 045-XS_CL_5Scale_Sheets.dgn
Plotted : 10-JUN-2024 16:22



STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	47	53

Drawn By : bfranz
File : 045-XS_CL_5Scale_Sheets.dgn
Plotted : 10-JUN-2024 16:22




Centerline
STA. 37 + 50.00 TO STA. 37 + 89.52
SCALE = 1:5

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	48	53

CADconform Certify This File


Drawn By : bfranz
File : 045-XS_CL_5Scale_Sheets.dgn
Plotted : 10-JUN-2024 16:22



Centerline
STA. 38 + 00.00 TO STA. 38 + 41.45
SCALE = 1:5


STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	78 C-5229-01	2024	49	53

Drawn By : bfranz
Plotted : 10-JUN-2024 16:22
File : 045-XS_CL_5Scale_Sheets.dgn




CADconform Certify This File

Drawn By : bfranz
Plotted : 10-JUN-2024 16:22
File : 051_XS_Chnl_5Scale_Sheets.dgn



Drawn By : bfranz
Plotted : 10-JUN-2024 16:22
File : 051_XS_Chnl_5Scale_Sheets.dgn



CADconform Certify This File

