

INDEX OF SHEETS

1. TITLE SHEET
2. GRADING TYPICAL SECTION
3. PLAN AND PROFILE
- 4-8. GUARDRAIL DETAILS
- 9-18. BRIDGE DETAILS
19. BRIDGE PROJECT MARKER DETAILS
20. BRIDGE EXCAVATION
21. STANDARD PILE DETAILS
22. SUPPORTS & SPACERS FOR REINFORCING STEEL
23. SUMMARY OF QUANTITIES
- 24-31. TEMPORARY EROSION & POLLUTION CONTROL
32. SEEDING
33. OBJECT MARKER DETAILS
- 34-39. TRAFFIC CONTROL
- 40-45. MAINLINE CROSS SECTIONS

DESIGN DESIGNATION

AADT 30
V 45 mph

CONVENTIONAL SIGNS

COUNTY LINE	CENTER LINE OF PROJECT
CITY LIMITS	TERRACE
STATE OR NATIONAL LINE	CULVERTS
TOWNSHIP, SECTION or GRANT LINE	DROP INLET & STORM SEWER
PROPERTY LINE	ACCESS CONTROL
HIGHWAY FENCE	POWER POLE
EXISTING FENCE	TELEPHONE POLE
GUARDRAIL	MARSH
CONSTRUCTION LIMITS	HEDGE
RIGHT OF WAY LINE	TREES
TRAVELED WAY	PROFILE ELEVATION
RAILROADS	STREAM or CREEK

GROSS LENGTH OF PROJECT	450.00 FT. (Includes Equations)
EXCEPTIONS	NONE
NET LENGTH OF PROJECT	450.00 FT. 0.085 MILES
NET LENGTH OF BRIDGES	102.50 FT. 0.019 MILES
NET LENGTH OF ROAD	347.50 FT. 0.066 MILES

NOTE: This project will be closed to all traffic during construction.




RECOM. FOR APPROVAL DATE
LOCAL PUBLIC OFFICIAL

KIRKHAM MICHAEL

200 E. Iron Ave., SALINA, KANSAS 67401
(785) 376-6730 FAX (785) 472-3817

STATE OF KANSAS
DEPARTMENT OF TRANSPORTATION
PLAN AND PROFILE OF PROPOSED
LINCOLN OS 107

GRADING
BRIDGE
SEEDING



Sta. 52+00.00 END
Lincoln Co. OS 107

Sta. 50+00.00
Br. No. 000530731204368
30'-40'-30" R.C. Haunched
Slab Span Bridge (RCSH)
28'-0" Roadway.

Sta. 47+50.00 BEGIN
Lincoln Co. OS 107

Plotted by : bwlknsn 2-JAN-2025 10:25
File : 2311855 ru-01.dgn

Plotted by: dwilkinson
File: 2311855_rpp.dgn

2-JAN-2025 10:27

DATE	BY	REFERENCE NOTES
		REFERENCE CHECKED

UTILITIES
Telephone ATTD 316-776-6010
Overhead Power Rolling Hills Electric 785-534-1601

CP #1 Sta. 46+36.83, 16.77' LT.
N 547.902.743 E 6.495.610.485
2 App. E of N-S Rd. 15.3' E
3 N Face of PP 88.3' SE
4 W Face of PP 188.3' NE

P.O.T. Sta. 45+00.00
N = 547765.818 E = 6495626.463
1. Not Set


CP #2 Sta. 53+16.51, 42.08' LT.
N 548.582.561 E 6.495.589.121
1 Set 5/8" Rebar @ Surface
2 App. E of N-S Rd. 45.8' E
3 App. E of Entrance 30.2' N
4 Top S. End of RCP 28.7' NE

CP#3 Sta. 54+98.84, 14.45' LT.
N 548.764.722 E 6.495.617.807
1 Set 5/8" Rebar @ Surface
2 App. E of N-S Rd. 16.0' E
3 App. E of Entrance 150.9' S
4 Top N. End of RCP 125.5' S

STATE KANSAS PROJECT NO. 53-C-5270-01 YEAR 2025 SHEET NO. 3 TOTAL SHEETS 45

DATUM BENCHMARK
BASE 1 is the datum benchmark. An OPUS solution was collected for BASE 1. BASE 1 is a 5/8" rebar with a pink Kirkham Michael Cap set flush located 2661 feet north of the centerline of 183rd Rd. BASE 1 Elev. = 1461.155 feet
BASE 1 WGS 84 Coordinates:
Latitude = 39°00'46.01275" N
Longitude = 98°09'54.84575" W
Ellipsoid Height = 1,372.120 feet
The Contractor shall remove the existing 1-59.0' SLTS bridge (16' roadway). Br. No. 000530731204367. All items of the existing structure shall become property of the Contractor and shall be removed from the site.


The Contractor shall excavate the channel at the bridge site to the limits shown prior to construction of the bridge. All fencing within Construction Limits will be removed prior to the beginning of project.
The Contractor shall complete the Embankment as shown on the bridge excavation sheet prior to the driving of the abutment piling.
All trees, hedge rows, shelterbelts, and woody shrubs not shown to be removed and located between the construction limits and the right-of-way line or easement line shall be spared unless directed by the Engineer to be removed.
Excavation shown to be wasted shall be wasted on sites provided by the Contractor. These sites shall be approved by the Engineer as to suitability, appearance, and site location. Locations that in the opinion of the Engineer will leave an unsightly appearance will not be approved.
All disposal sites must be approved by the Kansas Department of Health and Environment. Material either stockpiled or disposed of in a flood plain would require a Kansas State Dept. of Agriculture permit. Any material dumped in waters of the United States or wetlands is subject to U.S. Corps of Engineers permitting regulations.



Note to Designer - Design guardrail installations using guidance shown on KDOT's 'Guardrail Typical Alignments' Standard Drawings. 'Flared' guardrail installations are preferred over 'Parallel' or 'Zero Flare' installations. Where 'Flared' or 'Parallel' installations are used, the flare rate of the guardrail end terminal typically matches the flare rate of the remaining guardrail installation. For 'Zero Flare' installations, 'Parallel' guardrail end terminals should be designed using typical flare rates of 50:1 or flatter for the length of the end terminal. However, while 50:1 or flatter flare rates are typical for 'Parallel' guardrail end terminals, these end terminals may be flared as steep as 25:1 or flatter in order to offset the end terminal head as far from the edge of the through traveled lane as practicable.


Plotted by: bwillkinson 2-JAN-2025 10:27
File: 2311855_rgr-02_rde06.dgn

GUARDRAIL CLEAR AREA
Applies to all guardrail installations unless otherwise shown in the plans.




- Keep Area Free of Stockpiled Material, Equipment, or Other Obstacles, Such as Temporary Signs, Regardless of Crash Worthiness. This Clear Area Extends 105 Feet in Advance of and 50 Feet behind the First Post of the Guardrail End Terminal and Then, in Order to Maintain Full Post Spacing, Continues 5 Feet behind the Face of the Guardrail through the W-Beam Portion of the Installation as Shown in the 'Guardrail Clear Area' Detail on this Sheet.
- ▲ Normal Project Side Slope.
⊗ Deflection Distance for Normal Post Spacing

FLARED GUARDRAIL DETAIL
Applies to CGS AND MGS (MGS Shown)



PARALLEL GUARDRAIL DETAIL
Applies to CGS AND MGS (MGS Shown)



- ⊗ See Guardrail Layout Sheets for Details
◆ On Guardrail Layout Sheets, Show Station AND Offset from the Roadway Alignment to the Face of Post at these Locations.
★ Length of Need (Begins at Post 3)

GENERAL NOTES

Install the guardrail end terminals according to the Manufacturer's Installation Manual. The Contractor will furnish a copy of the Manufacturer's Installation Manual to the Engineer prior to the start of the installation.

Use approved steel (preferred) or wood posts provided by the Manufacturer. The guardrail end terminal post type may be independent of the post type used in the remainder of the installation. However, no mixing of post types is permitted in the remaining w-beam and thrie-beam installation.

Use approved polymer (preferred) or wood blockouts provided by the Manufacturer. The guardrail end terminal blockout size and type may be independent of the blockout size and type used in the remainder of the installation. For blockout size and types for the remaining w-beam and thrie-beam portion of the installation see the details shown on KDOT's 'Guardrail Post Details' and 'Guardrail Thrie-Beam Transition Details' Standard Drawings.

Apply retroreflective sheeting to the end terminal impact head before installation.

Tighten all cable anchor assemblies as per the Manufacturer's Installation Manual.


Lap w-beam and thrie-beam guardrail splices, in the direction of permanent traffic, even where temporary traffic may be carried in the opposite direction of the final traffic configuration. Lap end terminal splices per the Manufacturer's Installation Manual in the direction of permanent traffic, even where temporary traffic may be carried in the opposite direction of the final configuration.

The minimum length of w-beam guardrail required between the thrie-beam transition and the guardrail end terminal is 12'-6" for all installations; unless otherwise stated in the Manufacturer's Installation Manual.


Where pavement with a thickness less than or equal to 8" is encountered during installation, use the details shown on KDOT's 'Guardrail Post Details' Standard Drawings to provide openings in the pavement for the guardrail posts. Where pavement with a thickness greater than 8" or geologic rock is encountered during installation, follow the Manufacturer's Installation Manual for guidance. Where the Manufacturer's Installation Manual does not address pavement with a thickness greater than 8" or geologic rock, contact the manufacturer for instructions or install the guardrail posts as directed by the Engineer.

All work and materials required for w-beam and thrie-beam guardrail installations are paid for under the appropriate bid items for either CGS or MGS guardrail depending on the type of installation.


All work and materials required for guardrail end terminal installations are paid for under the bid item for the selected guardrail end terminal. See the table on this sheet for the appropriate end terminal bid item information.




CGS TO MGS TRANSITION DETAILS (PLAN)



CGS TO MGS TRANSITION DETAILS (ELEVATION)



MGS OMITTED POST DETAIL



CGS OMITTED POST DETAIL

MIDWEST GUARDRAIL SYSTEM (MGS) END TERMINALS










END TERMINAL BID ITEM	FLARED OR PARALLEL	MOUNTING HEIGHT	CRASH TESTING CRITERIA	STEEL POST DESIGN AVAILABLE	WOOD POST DESIGN AVAILABLE	ENERGY ABSORBING	MANUFACTURER	DESIGN LENGTH	MANUFACTURER SYSTEM LENGTH
Guardrail End Terminal (MGS-FLEAT)	Flared	31"	NCHRP 350	Yes	Yes	Yes	Road Systems	40'-7 1/2"	37'-6"
Guardrail End Terminal (MGS-SRT)	Flared	31"	NCHRP 350	Yes	Yes	No	Valtir	40'-7 1/2"	37'-6"
Guardrail End Terminal (MGS-MSKT)	Parallel	31"	MASH	Yes	No	Yes	Road Systems	46'-10 1/2"	46'-10 1/2"
Guardrail End Terminal (MGS-SOFTSTOP)	Parallel	31"	MASH	Yes	No	Yes	Valtir	46'-10 1/2"	50'-9 1/2"

CONVENTIONAL GUARDRAIL SYSTEM (CGS) END TERMINALS

END TERMINAL BID ITEM	FLARED OR PARALLEL	MOUNTING HEIGHT	CRASH TESTING CRITERIA	STEEL POST DESIGN AVAILABLE	WOOD POST DESIGN AVAILABLE	ENERGY ABSORBING	MANUFACTURER	DESIGN LENGTH	MANUFACTURER SYSTEM LENGTH
Guardrail End Terminal (FLEAT)	Flared	28"	NCHRP 350	Yes	Yes	Yes	Road Systems	37'-6"	37'-6"
Guardrail End Terminal (SRT)	Flared	28"	NCHRP 350	Yes	Yes	No	Valtir	37'-6"	37'-6"
Guardrail End Terminal (SKT)	Parallel	28"	NCHRP 350	Yes	Yes	Yes	Road Systems	50'-0"	50'-0"



02	09-05-18	ADD OMITTED POST AND TRANS. DETAILS	A.L.R.	T.T.R.
01	05-05-18	INITIAL RELEASE	A.L.R.	T.T.R.
MO	DATE	REVISIONS	BY	APPD
KANSAS DEPARTMENT OF TRANSPORTATION				
GUARDRAIL AUXILIARY DETAILS				
RD606				
DESIGNED	09-25-18	APPROVED	Scott W. King	
DRAWN		QUANTITIES	TRACED	
CHECKED		DETAILS	TRACE CK	

Notes to Designer: For posts installed in pavement thicker than 8" or posts installed in rock formations refer to AASHTO's Roadside Design Guide for details then revise this drawing and all supporting drawings appropriately.




STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	53 C-5270-01	2025	6	45

See Standard Drawing RD613 for Thrie-Beam Transition Section Details.



Non-Metallic (Polymer) or Treated Wood Block



Galvanize all bolts, nuts, and washers in accordance with the KDOT's Standard Specifications.

NO.	DATE	DESCRIPTION	BY	APP'D
13	09-05-18	Added Det. Post In Pavement	A.L.R.	T.T.R.
12	12-14-10	Revised notes, 28" w-be.	S.W.K.	J.D.R.
11	06-09-04	Remove steel blockout and notes.	S.W.K.	J.D.R.
10		REVISIONS		

KANSAS DEPARTMENT OF TRANSPORTATION


RD611

DESIGNED	02-25-18	APP'D	Scott W. King
DRAWN		QUANTITIES	TRACED
CHECKED		DETAILS	TRACED
DESIGN		QUANT	TRACED


Sh. No. 6

Notes to Designer: Guardrail length of need shall be determined in accordance with the AASHTO Roadside Design Guide using $L_1 = 25'$ for flare rate of a:b and $L_2 = 12.5'$ for flare rate of 2a:b for a typical installation as shown on this sheet. This sheet shall be used when the flared guardrail design for typical layout shown (FLEAT or SRT) is selected. Material for asphalt widening shall be included in the plan quantities.

Plotted by: b.wilkinson 2-JAN-2025 10:28
File: 2311855_rgr-04_rdg615a.dgn



TWO LANES




FOUR LANES - DIVIDED

DESIGN PARAMETERS				
Design Speed (mph)	Flare Rate (a:b)	Radius (R)	Flare Rate (2a:b)	Radius (R)
70	15:1	375.55'	30:1	375.14'
60	14:1	350.59'	26:1	325.16'
55	12:1	300.69'	24:1	300.17'
50	11:1	275.76'	21:1	262.70'
45	10:1	250.83'	18:1	225.23'
40	8:1	201.04'	16:1	200.26'

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	53 C-5270-01	2025	7	45


GENERAL NOTE

For guardrail and rubrail sections, details, and general notes see KDOT's 'W-Beam with Rubrail Bridge Approach Transition Details' Standard Drawings. For post details see KDOT's 'Guardrail Post Details' Standard Drawings. The ratio of a:b may be specified as zero for long runs of guardrail in high fill areas. Widening, slopes & transition for Four Lane will be similar to that shown on two lane detail.




ALTERNATE TREATMENT - TWO LANES


Flare Rate = 2a:b
(GUARDRAIL LENGTHS OF 62.5' AND 75')



PLAN VIEW TWO LANE



PLAN VIEW FOUR LANE



ENLARGEMENT - AREA OF CONCERN

DETAILS OF GUARDRAIL PROTECTION AT ROADSIDE OBSTACLE

- * See table on this sheet for radius and flare rate.
- ▲ Normal project side slope. See typical sections.
- ◆ See KDOT's 'Guardrail Auxiliary Details' Standard Drawing.
- ∇ 4" Asphalt material placed on 4'-0" embankment widening unless flume inlet and slope drain is constructed.

REV	DATE	DESCRIPTION	BY	APPD
06	06-05-18	Revised Flare beyond the Flare	A.L.B.	T.T.R.
07	05-15-17	Removed K-1 LITE	A.L.B.	S.W.K.
08	07-02-09	Added roadside obstacle details	S.W.K.	J.O.B.
NO	DATE	REVISIONS	BY	APPD


KANSAS DEPARTMENT OF TRANSPORTATION

W-BEAM WITH RUBRAIL
BRIDGE APPROACH TRANSITION
TYPICAL ALIGNMENTS (FLARED)

RD615A

THWA APPROVAL	06-19-18	APPD	Scott W. King
DESIGNED	DETAILS	QUANTITIES	TRACED
DESIGN CK	DETAIL CK	QUANT CK	TRAC CK

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	53 C-5270-01	2025	8	45



GENERAL NOTE

Include all material and work for this installation in the pay item "Steel Plate Guardrail" paid by the lineal foot.

Use 10 or 12 gauge steel guardrail elements unless otherwise called out, see standard specifications.

Bridge Rail Transition consists of one 12'-6" W-beam section nested in back of one 25'-0" section. Furnished remaining rail elements in either 12'-6" or 25'-0" sections.

Guardrail parts furnished under this specification shall be interchangeable with similar parts regardless of the source or manufacturer.

Shop fabricate tubular steel rubrail from ASTM A36 structural steel, form angles in rubrail by shop bending or welding. Rubrail is subsidiary to the bid item "Steel Plate Guardrail".

Galvanize rail elements, post fittings, bolts, nuts, washers and anchor bolts after fabrication in accordance with the standard specifications.

Shop or field drill holes in posts and/or tubular steel rubrail for attachment. When holes are field drilled touch up any damage to the galvanized coating with zinc based paint.






Shop bend rail when radius is less than 150'.

Fabricate Special End Shoe from 10 gauge steel in accordance with standard specifications.

The Special End Shoe has the same section as guardrail and is subsidiary to guardrail.

Lap guardrail splices, including Special End Shoe, in the direction of traffic. Where traffic is temporarily carried in the opposite direction of final configuration, lap rail splices in the direction of permanent traffic.

See Std. Drawing RD611 for additional details of posts not shown on this sheet.



NO.	DATE	REVISIONS	BY	APPD.
14	12-14-10	Revised notes 28' rail height	SWK	JDB
13	04-02-08	Removed Galvanized callout	SWK	JDB
12	02-06-07	Corrected spelling error	SWK	JDB
11	02-06-07	Corrected spelling error	SWK	JDB
10	02-06-07	Corrected spelling error	SWK	JDB
9	02-06-07	Corrected spelling error	SWK	JDB
8	02-06-07	Corrected spelling error	SWK	JDB
7	02-06-07	Corrected spelling error	SWK	JDB
6	02-06-07	Corrected spelling error	SWK	JDB
5	02-06-07	Corrected spelling error	SWK	JDB
4	02-06-07	Corrected spelling error	SWK	JDB
3	02-06-07	Corrected spelling error	SWK	JDB
2	02-06-07	Corrected spelling error	SWK	JDB
1	02-06-07	Corrected spelling error	SWK	JDB

RD616

Plotted by: b.wilkinson
2-JAN-2025 10:28
File: 2311855_rgr-05_rd616.dgn

Std. Base File:
Plotted By: bulkinson
File: 231055_Abr-01_General Notes and Quantities.dgn
Plot Date: 2-JAN-2025 10:28

SUMMARY OF QUANTITIES										
Item Location	Excavation		Concrete		Reinforcing Steel	* Piles Steel HP12x53 Lin. Ft.	Contractor Furnished PDA Each	Slope Protection (Riprap Stone) Cu. Yds.		
	Class I Cu. Yds.	Class II Cu. Yds.	(Grade 4.0) (AE) (SW) Cu. Yds.	(Grade 4.0) (AE) Cu. Yds.	(Grade 60) Lbs.					
Abutment No. 1	51		**		**	202	1	112		
Pier No. 1	3	62		53.4	1,690	329				
Pier No. 2	5	62		53.4	1,690	381	1			
Abutment No. 2	51		**		**	184		246		
Substr. Total	110	124		106.8	3,380	1,096	2			
Superstr. Total			205.8		56,900					
Total	110	124	205.8	106.8	60,280	1,096	2	358		

** Quantities are included in
the Superstr. Total Quantity.

* Summary of Piling
Abutment No. 1 3 @ 48' & 1 @ 58' for use with the PDA
Pier No. 1 7 @ 47'
Pier No. 2 6 @ 53' & 1 @ 63' for use with the PDA
Abutment No. 2 4 @ 46'

* NOTE: Only steel pile HP12X53
shall be used on this project.

GENERAL NOTES

EMBANKMENT: Complete the embankment at the abutments as shown on the Bridge Excavation sheet prior to driving the abutment piling or commencing with the abutment footing excavation.

BRIDGE EXCAVATION: Elevation 1361.50 shall designate the Excavation Boundary Plane of Class I and Class II Excavation; Class I above the plane, Class II below the plane. See the Bridge Excavation sheet for the limits of pay excavation.

BACKFILL COMPACTION: Compact backfill at the abutments.

PILING: Drive all piling to a minimum elevation of 1327.0 ft at Abut. 1, 1329.0 ft at Pier 1, 1323.0 at Pier 2, and 1329.0 ft at Abut. 2. Driving shall stop when in the opinion of the Engineer additional driving may damage the piling. Drive all piling to the Pile Driving Formula Load of:

Abutment No. 1	57	Tons
Pier No. 1	90	Tons
Pier No. 2	90	Tons
Abutment No. 2	57	Tons

As a minimum drive each pile to the load and penetration, but in no case shall the pile be driven to more than 110% of Pile Driving Formula Driving Load. At any location where problems are experienced, pile damage is suspected, or the Pile Driving Formula Load occurs significantly above the design pile tip elevation, the Engineer may request that the Pile Driving Analyzer (PDA) equipment be used.

CONTRACTOR FURNISHED PDA: Use the Pile Driving Analyzer equipment at the locations shown on the Construction Layout. Use Pile Driving Analyzer equipment and methods compliant with KDOT Special Provisions. The piling shall remain in place as permanent piling. Drive the piling to the resistance value of 88 tons at the Abutments and 138 tons at the Piers (Strength I divided by Phi).

PILING SPLICE LOCATION: Integral pile splice locations and weld testing criteria for, Abutments No. 1 and No. 2 and Piers No. 1 and No. 2 will follow the "Standard Pile Details" Sheet (BR110).

CORRAL RAIL: Build the corral rail after the falsework is struck.

REMOVAL OF EXISTING STRUCTURE: Removal of existing structure is included in the bid item, "Removal of Existing Structures", Lump Sum. All materials removed from the existing structure shall become the property of the Contractor. Remove this material from the site.

CONCRETE: Superstructure concrete is bid as Concrete (Grade 4.0)(AE)(SW). Substructure concrete is bid as Concrete (Grade 4.0)(AE). Bevel all exposed edges of all concrete with a ¼" triangular molding, except as otherwise noted on the plans. Construction joints are optional with the Contractor, but if used, place only at locations shown, or at locations approved by the Engineer.

REINFORCING STEEL: All reinforcing steel dimensions are to the centerline of bars unless otherwise noted. All reinforcing steel shall conform to the requirements of ASTM A615, Grade 60.

CAMBER: Provide camber as shown on the Camber Diagram unless the Contractor uses either long span steel beam falsework (concrete dead load deflection greater than ¼") or timber falsework with greater than 12'-0" clear span. If either case exists, submit falsework plans which show the additional required camber.

FALSEWORK PLANS: A licensed Professional Engineer shall design the falsework details. Details shall bear the seal of a licensed Professional Engineer. Submit electronic plans conforming to Section 105 of the Standard Specification with details in compliance with KDOT Specifications to the Field Engineer for review.

FALSEWORK INSPECTION: This project has falsework plan requirements which are considered "Category 2" by KDOT specifications. If falsework deficiencies or variations from the approved and sealed plans are found, the falsework design Engineer of Record will provide written approval of the changes. If for the convenience of the Contractor the falsework becomes "Category 1" by the use of non-typical supports; then the inspection and review requirement of "Category 1" will be fully enforced, but at no cost to the State. "Category 2" falsework inspection is not paid for directly, but is subsidiary to other bid items.

DEMOLITION PLANS: This is a Category A Demolition. Submit detailed Demolition Plans to the Field Engineer per KDOT Specifications. No Demolition work will begin without approved Demolition Plans. A Licensed Professional Engineer is not required.

FALSEWORK: Leave the falsework in place for the entire unit until 15 days after the last concrete pour for the unit or longer as directed by the Engineer.

CONCRETE PLACING SEQUENCE: The sequence of placing concrete in the slab and curbs shall be as shown, or the Contractor may submit an alternate placing sequence for review. Submit the alternate placing sequence to the Engineer at the Preconstruction Conference. Include the proposed rate of concrete placement in C.Y./h, the plant capacity, placement direction, construction joint location, a description of the equipment used in placing the concrete, proposed admixtures, and the quantity of concrete in each placing segment. Any additional cost for the Contractor's alternate plan of placing concrete, including admixtures, shall be at the Contractor's expense and shall be considered subsidiary to the bid item, "Concrete (Grade 4.0)(AE)(SW)". Approval of the Contractor's alternate sequence is required prior to placement of concrete in the deck.

CONSTRUCTION LOADS: Limited traffic is permitted on the new sub-deck, one-course deck or any concrete overlay during the curing period, keep any exposed deck wet during the curing period. See KDOT Specifications Section 710 Tables 710-1 & 710-2 for additional information.

TEMPERATURE: The design temperature for all dimensions is 60° F.

QUANTITIES: Items not listed separately in the Summary of Quantities are subsidiary to other items in the proposal.

DIMENSIONS: All dimensions shown on the design plans are horizontal dimensions unless otherwise noted. Make necessary allowances for roadway grade and cross slope.

CONSTRUCTION JOINTS: The construction joints shown are optional with the Contractor. If used, place the construction joints only at locations shown or at locations approved by the Engineer.

CONSTRUCTION SPECIFICATIONS: Kansas Department of Transportation, Standard Specifications for Road and Bridge Construction, 2015 Version, and Special Provisions.

SLOPE PROTECTION (Riprap Stone): Place Slope Protection (Riprap Stone) to the limits and thickness shown on the plans or as directed by the Engineer. Use Riprap Stone Classified as Light 200 pounds as described Division 1100, placed to the limits shown on the plans. Place a 10 foot wide mat of geotextile under the riprap embankment on the berm and berm slopes and centered on the drip lines of the slab. The geotextile shall be considered subsidiary to the bid item "Slope Protection (Riprap Stone)".

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	53 C-5270-01	2025	9	45

INDEX TO BRIDGE DRAWINGS	
Sheet No.	Drawing
9	General Notes and Quantities
10	Contour Map
11	Construction Layout
12	Engineering Geology
13	Abutment Details
14	Pier Details
15-16	Superstructure Details
17	Corral Rail Details
18	Bill of Reinforcing Steel and Bending Diagrams
19	Bridge Project Marker Details
Standards	
20	Bridge Excavation
21	Standard Pile Details
22	Supports and Spacers for Reinforcing Steel

DESIGN DATA

DESIGN SPECIFICATIONS: AASHTO Specifications, 2017 Edition and latest Interim Specifications. Load and Resistance Factor Design.

DESIGN LOADING: HL-93

Design Dead Load includes an allowance of 25 psf for a future wearing surface.

UNIT STRESSES:
Concrete (Grade 4.0)(AE) f'c = 4 ksi
Concrete (Grade 4.0)(AE)(SW) f'c = 4 ksi
Reinforcing Steel (Grade 60) fy = 60 ksi

LRFD DESIGN PILE LOAD:
Design Loading (Tons/Pile) Strength Service Phi
Abutments 1&2: 57 38 0.65
Piers 1&2: 90 63 0.65

CONTRACTOR CONSTRUCTION STAKING: Contractor Construction Staking for clear span bridges requires two independent surveys. See KDOT Specifications.

#	DATE	DESCRIPTION	BY	APP'D
1	10/24/23	Update Notes & add NOT19040 text	MLL	DNS
2	2/3/25	Made NOT19040 & NOT1940 default	MLL	MAH
3	10/09/15	Added Abutment NOT19221 Option	JPU	CER
4	2/4/15	Modified Per 2015 Specification	JPU	CER
5	4/1/14	Current Release	JPU	CER
6	2/2/14	Added Benchmark	JPU	CER
NO.	DATE	REVISIONS	BY	APP'D
KANSAS DEPARTMENT OF TRANSPORTATION				
Br. No. 000530731204368 S+0.50+00.00				
GENERAL NOTES AND QUANTITIES				
Proj. No. 53 C-5270-01 Lincoln Co.				
SHEET NO.	OF	SCALE	APP'D	
DESIGNED	DETAILED	QUANTITIES	TCADD	
DESIGN CK.	DRAW. CK.	QUAN. CK.	TCADD CK.	

Telephone **UTILITIES**
ATTD 316-776-6010
Overhead Power Rolling Hills Electric 785-534-1601


CP #1 Sta. 46+36.83, 16.77' Lt.
N 547,902.743 E 6,495,610.485
1. Set 5/8" Rebar @ Surface
2. App. ϵ of N-S Rd. 15.3' E
3. N. Face of PP 88.3' SE
4. W. Face of PP 188.3' NE

CP #2 Sta. 53+16.51, 42.08' Lt.
N 548,582.561 E 6,495,589.121
1. Set 5/8" Rebar @ Surface
2. App. ϵ of N-S Rd. 45.8' E
3. App. ϵ of Entrance 30.2' N
4. Top S. End of RCP 28.7' NE

CP#3 Sta. 54+98.84, 14.45' Lt.
N 548,764.722 E 6,495,617.807
1. Set 5/8" Rebar @ Surface
2. App. ϵ of N-S Rd. 16.0' E
3. App. ϵ of Entrance 150.9' S
4. Top N. End of RCP 125.5' S

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	53 C-5270-01	2025	10	45

SCALE: 1" = 50'
Contour Interval = 2'



Plotted by: bwilkinson 2-JAN-2025 10:28
File: 2311855_dbr-02_ContourMap.dgn

BM #1 Top of Driven "T" Post 2' W. of PP
17.38' Rt., Sta. 48+22.07, Elev. = 1375.67

BM #2 Top of Driven "T" Post 2' W. of PP
20.76' Rt., Sta. 51+00.81, Elev. = 1374.00

BM #3 Top of Driven "T" Post 2' W. of PP
22.96' Rt., Sta. 53+40.74, Elev. = 1375.78

NO.	DATE	REVISIONS	BY	APPD.
KANSAS DEPARTMENT OF TRANSPORTATION				
Br. No. 000530731204368			Sta. 50+00.00	
CONTOUR MAP				
Proj. No. 53 C-5270-01			Lincoln County	
DESIGNED	DETAILED	QUANTITIES	CADD	
DESIGNER	DETAILER	QUANTITY	CADD CR.	

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	53 C-5270-01	2025	11	45

SCALE: 1" = 10'-0"
Contour Interval = 2'

DRAINAGE DATA:

Drainage Area	73.7	Sq. Mi.
Design Frequency	50	Yr.
Design Discharge @ (Q ₅₀)	8,940	cfs
Design Velocity @ (Q ₅₀)	10.9	fps
Design High Water Elevation	1375.0	Ft.
Overtopping Elevation (Sta. 46+40)	1376.3	Ft.
Overtopping Discharge	11,200	cfs
Overtopping Frequency	100	Yr.
Discharge @ (Q ₁₀₀)	11,200	cfs
Change in Backwater @ (Q ₁₀₀)	0.3	Ft.
Backwater Elevation @ (Q ₁₀₀)	1377.9	Ft.
Historic Highwater Elevation	NA	
Ordinary Highwater Elevation	1,360.0	Ft.
Total Waterway Provided	1,085	Sq. Ft.
Design Waterway Provided	885.4	Sq. Ft.
Estimated Ordinary Highwater Discharge	239	cfs

Total Velocity Existing	Proposed
@ Q2 4.1 ft/s	4.3 ft/s
@ Qdes 11.3 ft/s	10.9 ft/s
@ Q100 13.5 ft/s	12.4 ft/s



Place a 10 foot wide mat of geotextile under the riprap embankment on the berm and berm slopes and centered on the drip lines of the slab. All equipment, material and labor necessary to install the geotextile mat shall subsidiary to the bid item "Slope Protection (Riprap Stone)".


NOTE: The Contractor shall place a header board at each EWS in accordance with Section 710.3.c.1 of the Specifications for Bridges With Tied Approaches. This work shall not be paid for directly, but shall be subsidiary to other items in the contract.

NO.	DATE	REVISIONS	BY	APPD
KANSAS DEPARTMENT OF TRANSPORTATION				
Br. No. 000530731204368			Sta. 50+00.00	
CONSTRUCTION LAYOUT				
Proj. No. 53 C-5270-01			Lincoln County	
DESIGNED	DETAILED	QUANTITIES	CADD	
DESIGN CK	DRAW CK	QUANT CK	CADD CK	

Sh. No. 11

VERTICAL CURVE DATA

Station	Elevation
P.T. Sta. 48+00.00	Elev. = 1377.46
P.I. Sta. 50+00.00	Elev. = 1378.60
P.T. Sta. 51+00.00	Elev. = 1377.38



Plotted by: bwilkinson 2-JAN-2025 10:28
File: 2311855_dbr-03_ConstructionLayout.dgn

PLAN

14'-0" 14'-0" 28'-0" Roadway

1'-0" 1'-0"


Bullfoot Creek

9

1

ATTD


STATE	PROJECT NO.	YEAR
KANSAS	53 C-5270-01	2025




NO	DATE	REVISIONS						BY	APPRO		
KANSAS DEPARTMENT OF TRANSPORTATION											
Br. No. 000507312D4368								Sta. 50+00.00			
 GEOLOGY SHEET 											
Proj. No. 53 C-5270-01								Lincoln County			
DRAWN - DESIGNED BY	DETAILED DETAIL CR.		QUANTITIES QUAN CR.				CADD CADD CR.				

Plotted by : bwilkinson 2-JAN-2025 10:29
File : 2311855_bbr-04_GeologySheet.dgn


STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	53 C-5270-01	2025	13	45



PLAN



ELEVATION
(Along Centerline of Abutment)



TYPICAL SECTION

Note: Top of piling elevations are based on 2'-0" maximum embedment.



Legend
EF = Each Face

4	7/29/09	Remove Factored Resistance	DRT	KPH
3	03/24/09	Add Factored Resist to Pile Loading	DRT	KPH
2	3/6/07	correct Abut. Dim 'A' for 54-72-54	DRT	KPH
1	4/6/06	Adj. Abut. Vol. & DL	DRT	KPH
NO	DATE	REVISIONS	BY	APP'D

KANSAS DEPARTMENT OF TRANSPORTATION				
Br. No. 000530731204368			Sta. 50+00.00	
ABUTMENT DETAILS				
Proj. No. 53 C-5270-01			Lincoln Co.	
SHEET NO.	OF	SCALE	APP'D	
DESIGNED	DRT	DETAILED	DRT	
CHECKED	DRT	QUANTITIES	CADD	RCJ
DESIGN CK.	DETAIL CK.	QUANT CK.	CADD CK.	

STATE	PROJECT NO	YEAR	SHEET NO	TOTAL SHEETS
KANSAS	53 C-5270-01	2025	14	45

Note: Top of Pile elevation is based on 1'-6" embedment into the Pier Beam.



LEGEND
EF = Each Face

NO.	DATE	REVISIONS	BY	APP'D
1				
2				
3				

KANSAS DEPARTMENT OF TRANSPORTATION
Br. No. 000530731204368 Sta. 50+00.00
PIER DETAILS
Proj. No. 53 C-5270-01 Lincoln Co.



SHEET NO.	OF	SCALE	APP'D
DESIGNED	DETAILS	QUANTITIES	CADD
DESIGNED	DETAILS	QUANTITIES	CADD

File: 2311555_dbr-477_Superstructure Details.dgn	Plot Location:
Plot Date: 2-JUN-2023 10:29	

LFD & LRFD RATING FACTOR			
Truck	Ln.	Oper.	Inv.
HS-20	1.84	3.07	1.87
HT	1.45	1.45	1.47
LRFD	1.40	1.40	1.45

Plotted By: twilkinson	Plot Location:
File: 2311555_dbr-477_Superstructure Details.dgn	
Plot Date: 2-JUN-2023 10:29	

Note:
See longitudinal section for
transverse reinforcing steel.




CONCRETE PLACING SEQUENCE

When long span steel beams having a concrete dead load deflection greater than $\frac{1}{4}$ " are used or when timber falsework with greater than 12'-0" clear span is used, follow the placing sequence shown. Segmental, combined or continuous pours are allowed, but stop a discontinuous pour at a construction joint short of a pier.

When timber falsework with 12'-0" or less clear span is used, the Contractor, subject to the approval of the Engineer, may use a continuous pour or may discontinue the pour at any construction joint shown.

The Contractor may place the corral rail continuously from one end of the bridge to the other.



DEAD LOAD CAMBER DIAGRAM AT TENTH POINTS


Long Term Deflections = Initial Deflections x 3.5
(Initial Deflections Based on $E_c = 3.644 \times 10^6$ p.s.i.)
(camber values in feet)

4	08/22/23	Summary of Quantities corrections	MLL	MAH
3	03/12/12	ADDED TOP Elevation Table	JPU	TLF
2	02/08/11	ADDED QUANTITIES	JPU	TLF
1	DATE	REVISIONS	BY	APPD


KANSAS DEPARTMENT OF TRANSPORTATION
Br. No. 000530731204368 Sta. 50+00.00
SUPERSTRUCTURE DETAILS
Proj. No. 53 C-5270-01 Lincoln Co.

SHEET NO.	OF	SCALE	APP'D
DESIGNED BY	CHK'D	DETAILS	QUANTITIES
DESIGNER	MEH	DETAILS	QUANTITIES


STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	53 C-5270-01	2025	17	45



BRIDGE NUMBER PLATE PLACEMENT DETAIL
(If Required)




PARTIAL ELEVATION
(Along Traffic Face)




DETAIL A


(For bridges w/o an approach slab curb, detail top of wing at curb line as shown)




ELEVATION
(Dimensions at traffic face of rail)




PLAN




SECTION A-A




SECTION C-C



SECTION B-B



TYPICAL INTERIOR POST



SECTION THRU POST

LEGEND
NF = Near Face
FF = Far Face
EF = Each Face

03	12-50-21	Changed Bridge Number Plate detail	MLL	MLL
01	06-20-05	Current Release		
NO	DATE	REVISIONS	BY	APPD
KANSAS DEPARTMENT OF TRANSPORTATION				
Br. No. 000530731204368			Sta. 50+00.00	
27" KANSAS CORRAL RAIL (W-BEAM WITH RUBRAIL)				
R.C. HAUNCHED SLAB (Without Curb)				
Proj. 53 C-5270-01			Lincoln Co.	
DESIGNED	DETAILED	QUANTITIES	CADD	
CHECKED	CHECKED	CHECKED	CADD	

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	53 C-5270-01	2025	19	45

COMMISSIONERS
DEBORA SMITH
DENNIS RAY
RYLEY HEMBRY

OFF-SYSTEM BRIDGE NO. 107

PUBLIC WORKS DIRECTOR
DALE HLAD

ENGINEERS
KIRKHAM MICHAEL & ASSOCIATES, INC.

CONTRACTOR
XXXXXXXXXXXXXXXXXX

HL-93 LOADING 2025


BRIDGE PLAQUE

NOTES:
Furnish a rubbing of the Bridge Plaque to the Engineer for approval prior to casting.
Marker to be furnished and installed by the Contractor, subsidiary to the bid item "Concrete (Grade 4.0)(AE)(SW)" (1 Required).
Plate is to be black with bronze lettering and border.
The Contractor shall provide a shop drawing to the County and Engineer prior to ordering the marker.


BRIDGE PLAQUE DETAILS

Plotted by : b.wilkinson 2-JAN-2025 10:30
File : 2311855_Bridge Project Marker.dgn


* Note: The Grading Contractor shall excavate the channel to the limits shown prior to the construction of the box bridge, unless otherwise noted in the plans.




EXCAVATION DETAILS FOR REINFORCED CONCRETE BOX CULVERT
Note: Excavation for culverts less than bridge length and the additional excavation for "Embedded Structures" shall not be paid for as Class III Excavation, but shall be subsidiary to Grade 4.0 Concrete.




EXCAVATION DETAILS FOR TYPICAL PIERS
See detail when rock or shale (rock) is encountered. ®




EXCAVATION DETAILS FOR ABUTMENTS WITH FLARED WINGWALLS




CLASS II EXCAVATION QUANTITIES
See detail when rock or shale (rock) is encountered. ®



EXCAVATION DETAILS FOR TYPICAL ABUTMENTS
See detail when rock or shale (rock) is encountered. ®



EXCAVATION DETAIL FOR FOOTINGS IN ROCK OR SHALE (ROCK)
(Piers and Abutments)
Note: Excavation below top of rock, hard shale or below top of footing, whichever is lower, shall be to neat lines of the concrete construction.



DRILLED SHAFT DETAILS
Note: Whenever the limits of the drilled shaft construction are greater than the Column Diameter + 2X, the limits of Class I, II or III Excavation shall be the limits of the drilled shaft construction. (See Detail B)

Note: All bridge excavation shall be computed on the basis of the cross-hatch areas and boundary lines indicated on this sheet and the Excavation Boundary Plane on the Construction Layout.

Sides of trenches in hard or compacted soil including embankments shall be shored, sheeted, braced or otherwise supported when the trench is more than 5 feet in depth and 8 feet or more in length. In lieu of the shoring, the sides of the trench above the 5 foot level may be sloped to preclude collapse. The slope for average soils shall be 1:1. If the angle of repose of the soil is less, flatter slopes shall be required.

Dimension "X" shall be 2'-0" unless indicated otherwise on the general plans.
Dimension "Y" shall be 1'-6" unless indicated otherwise on the general plans.

05	08-13-12	Embedded Excavation Subsidiary	J.P.J.	T.L.F.
05	05-15-12	Revised Wing Excavation	J.P.J.	T.L.F.
04	03-03-10	Revised Wing Excavation	J.P.J.	T.L.F.
NO.	DATE	REVISIONS	BY	APPD.
KANSAS DEPARTMENT OF TRANSPORTATION				
BRIDGE EXCAVATION (LRFD)				
BR100B				
PLANS APPROVAL	04-11-10	APPD.	TRACED	TRACED
DESIGNED	04-11-10	QUANTITIES	TRACED	TRACED
DESIGNER	04-11-10	QUANTITIES	TRACED	TRACED

Plotted by: b.wilkinson 2-JAN-2025 10:30
File: 2311855_bss-01_br100b.dgn


O D	10 3/4"	T ₁ = ††
O D	12 3/4"	T ₁ = ††
O D	14"	T ₁ = ††

†† See the Geology Report or 'Summary of Quantities' for Pipe Pile wall thickness

Note: Pile shall be driven with a steel head having a projecting ring fitting inside the pipe. Clearance between ring and pipe should be 1/4".

Note: Pile pipe may be spiral welded, longitudinal welded, or seamless steel pipe.



PLAIN ROUND CAST-IN-PLACE CONCRETE PILES



PICK-UP POINTS FOR PRESTRESSED PILING

Max. length - 55' single point pick-up
Max. length - 80' double point pick-up
Note: Piles shall be marked at Pick-up points to indicate proper points for attaching handling lines.

12" OR 14" PRESTRESSED CONCRETE PILES



SHELL PILE POINT

H-Pile Point

CAST STEEL PILE POINT

The pile point shall be a one-piece unit of cast steel. Weld pile points in accordance with manufacturer's recommendations to each steel pile before driving.

Weld Symbol Definition

Use grinder to bevel edges of splice as shown in weld symbology and drawing. In addition to bevels, produce clean, bare, and shiny surfaces at and around the splice welding location.


Lay full penetration root weld from beveled side of splice.

Back gouge root weld from side opposite of root welding application making sure to remove all foreign materials, porous steel, and inclusions from root weld. Finish welding the non beveled side of the splice.

Finish welding beveled side of the splice while removing slag, foreign materials, porous steel, and inclusions in between welding passes, use of a grinder may be needed.

Verify that enough filler metal has been correctly placed in all weld locations to obtain a flush or convex surface with no concavity produced upon completion of the final welds.

Note: If additional driving is required, use 1" pitch as shown.



FOR INFORMATION ONLY EQUIVALENT POINT BEARING PILES		
STEEL PILES	CONCRETE PILES	
	Pipe	Pre-stress
HP10x42	10 3/4"	
HP12x53	12 3/4"	
HP14x73	14	12
HP14x102		14
HP14x117		16

PRESTRESSED PILES: Fabricate prestressed concrete pile splices in accordance with the Manufacturer's recommendations subject to the approval of the Engineer.

Method of attachment of pile to build-up may be by any of the methods given in the notes on "Alternate Methods." If mild reinforcing steel is used for attachment, the area shall be no less than that used in the build-up.

- ALTERNATE METHODS: Method of attachment of a pile to build-up may be by any of the following methods:
1. Cut off at least 2'-0" of pile and expose a minimum of 2'-0" of strands.
 2. Cast 8-#6, or 8-#5 bars (equally spaced) into pile head. All bars shall extend into pile head and project from pile head a minimum of 2'-0".
 3. Drill 8 holes in pile head (equally spaced) for installation of 8 grouted dowel bars of same size and length as in 2.
 4. Provide cored holes for bars as in 3.

No bars or strands are to extend from head of pile or build-up into footing or pile cap unless approved by the Engineer.

TEST PILES: Drive test piles where called for on the bridge plans. The test piles located within the limits of the substructure will become a part of the bridge pile system.

DRIVING FORMULA: Driving formula shall conform to the Standard Specifications.

MEASUREMENT AND PAYMENT: Measurement and payment for all piles shall comply with the Standard Specifications.

REINFORCEMENT: Use reinforcing steel conforming to ASTM A615, Grade 60. Hoops and spirals may be either plain or deformed bars.

PRESTRESSING STEEL: Use uncoated seven-wire low relaxation prestressing strand conforming to ASTM A416, Gr. 270.

STEEL PILE: Steel pile shall conform to the requirements of the Standard Specifications.

PILE POINTS: Pile points shall conform to the dimensions shown and to requirements of the Standard Specifications.

SPLICES: Splices for steel piles and shell piling shall be in accordance with details shown on this sheet and the Standard Specifications.


For integral pile bent abutments and piers, if a pile splice is required, do not locate the pile splice within a region extending 2'-0" above and 10'-0" below the bottom of the concrete web wall. For abutments, locate the pile splice at least 10'-0" below top of fill.

With the approval of the Engineer, one splice per bent may be allowed in the region described above without testing. If additional splices are anticipated, based on the geology, the Contractor prior to driving, will locate the splice so that the splice will not fall within the regions described above.

† For integral pile bent abutments and piers, if a splice is located within the regions described above, then the Contractor will test the welds by Radiograph (RT) test methods. Repair and retest any welds not passing the test(s). Each weld tested will have written confirmation of results. Report these results to the Engineer. This work is not paid for directly, but is subsidiary to "Piles".

* Minimum as required by welding process.

BG = Backgouge



GENERAL NOTES

SPECIFICATIONS: Standard Specifications for State Road and Bridge Construction as currently used by the Kansas Department of Transportation.

CONCRETE: Concrete for cast-in-place shall be f'c = 3,500 PSI. Concrete for prestressed shall be f'c = 5,000 PSI.

WELDING: All field welding shall meet the requirements of the Standard Specifications.

Use only Shielded Metal Arch Welding SMAW (stick welding) for pile splices.

Use only low hydrogen E7018, 7016, or 7015 series welding rod (electrode) for all welding applications during pile splicing.

New electrodes are to be purchased for each KDOT project. The electrodes shall arrive on the project in factory hermetically sealed containers, opened and labeled with indelible ink in front of the engineer. The label shall include the current date and the project number. If the container seal is questionable or shows signs of damage the electrode is to be dried in an oven at least one hour at a temperature of 700°F to 800°F.

Upon removal from intact hermetically sealed factory packaging or the drying oven the electrode is to be placed in a storage oven with a minimum temperature of 250°F.

When electrodes are removed from the hermetically sealed container or storage oven and exposed to the atmosphere for less than 4 hours place into the storage oven for at least 4 hours before removing for use.

If electrode is exposed to the atmosphere for 4 hours or more (or 9 hours for moisture resistant electrodes designated with an R in their labeling) then electrode can be dried in a drying oven at a temperature of 450°F to 550°F.

If the electrode is exposed to the atmosphere for 4 hours or more a second time or the rod becomes wet discard rod.

CAST-IN-PLACE SHELLS: Steel shells for cast-in-place concrete piles shall conform to the requirements of the Standard Specifications.

All piles driven without a mandrel shall be of the minimum thicknesses shown. Piles driven with a mandrel shall be of sufficient strength and thickness to withstand driving without injury and to resist harmful distortion and/or buckling due to soil pressure after the mandrel is removed.

Remove, replace or correct to the satisfaction of the Engineer improperly driven, broken or otherwise defective pipe piles. Otherwise drive an additional pile at no extra cost.

The Contractor shall maintain a light suitable for visual inspection of the pile on the job at all times prior to and during the filling of the pipe.

PAINT: All paint shall comply with the Standard Specifications, or as specified on the plans.

MILL TEST REPORTS: Steel piles test reports and steel shell test reports shall comply with the Standard Specifications.

04	08-16-18	Add splice web section, clarify note	M.L.L.	J.P.J.
03	09-15-15	Clarify Notes	J.P.J.	C.E.B.
02	06-16-12	Clarify C. 100 type, use and weld	J.P.J.	T.L.F.
NO	DATE	REVISIONS	BY	APPD
KANSAS DEPARTMENT OF TRANSPORTATION				
STANDARD PILE DETAILS				
BR110				
DESIGNED	J.P.J.	10-04-12	APPD	Terry L. Hick
CHECKED	J.P.J.	10-04-12	QUANTITIES	TRACED
DESIGN CK	J.P.J.	10-04-12	QUANT CK	TRACED CK

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	53 C-5270-01	2025	22	45

GENERAL NOTES

Reference is made to the latest edition of the CRSI "Manual of Standard Practice" for recommended industry practices concerning reinforcing steel.

Use only the following types of bar supports:

- 1) Wire Bar Supports:
 - a) Epoxy coated reinforcing: Class 1 Protection
 - b) Non-epoxy coated reinforcing: Class 1, 2, or 3 Protection
- 2) Plastic Bar Supports
- 3) Supplementary bars

When securing epoxy coated reinforcement, use tie wires or metal clips that are epoxy or plastic coated.

Do not weld reinforcing steel to bar supports or to other reinforcing steel. Shop weld spacer frames for haunched slabs.

Tie bars at all intersections around the perimeter of each mat and at not less than 2'-0" centers or at every intersection, whichever is greater.




Where more than one length of bar support is required, lap the end legs so they are locked or tied together.

Use proper height supports to maintain the distance between the reinforcing and the formed surface or the top surface of deck slabs within 1/4" of that indicated on the plans.

Spacings shown are maximums. Use sufficient supports, as determined by the Engineer, to retain the reinforcing steel in position.

Construct any platforms, required for the support of workers and/or equipment during concrete placement, directly on the forms and not on the reinforcing steel.

Designs and arrangements of Supports or Spacers other than as shown on this sheet, may be used with the permission of the Engineer.



NO.	DATE	REVISIONS	BY	APPD.
05	11-10-10	Column Bar Supports Required	J.P.J.	T.L.F.
04	12-01-05	Drilled Shaft Spiral Steel Placement	J.P.J.	K.F.H.
03	08-21-00	Added Pre-Cast Panel Detail	R.A.M.	K.F.H.
02	08-21-00	Added Pre-Cast Panel Detail	R.A.M.	K.F.H.
01	08-21-00	Added Pre-Cast Panel Detail	R.A.M.	K.F.H.

Plotted by: b.wilkinson 2-JAN-2025 10:31
File: 2311855_bss-03_br120.dgn

[illegible]

For Summary of Guardrail See Sheet No. 4
For Temporary Erosion & Pollution Control See Sheet No. 24
For Seeding Quantities See Sheet No. 32
For Traffic Control Plans & Quantities See Sheet No. 39


Sh. No. 23

SURFACING MATERIAL (AB-3)		
STATION TO STATION	QUANTITY	UNIT
47+50.00 to 49+48.75	118.1	Tons
50+51.25 to 52+00.00	87.2	Tons
Total	205	Tons

* Common Excavation Includes 89 yards to be wasted.
Common Excavation includes 355 cubic yards of channel excavation for abutment berms

▲ See General note.

Plotted by : bwilkinson 2-JAN-2025 10:31
File : rd050.dgn



FERTILIZER: A ratio and application rate that equals or exceeds the required minimum rate per acre of N, P₂O₅, K₂O listed in Summary of Quantities will be acceptable.

- * - N = Nitrogen Rate of Application
- ** - P₂O₅ = Phosphorous Rate of Application
- *** - K₂O = Potassium Rate of Application

The Contractor will be required to finish areas of excavation, borrow and embankment in accordance with the specifications. Areas that require installation or construction of temporary water pollution control items will be finished in reasonable close conformity to the alignment, grade and cross section shown on the plans or as established by the Engineer.

CLT = Construction Limit Tract. This area is defined by the entire disturbed area of the project that requires seeding and erosion control measures to be placed. Any impervious areas (i.e. pavement, gravel, riprap, etc.) shall not be included in this measurement.

Slope = Defined by the area of the project that requires Class 1 erosion control material to be placed. This area shall be seeded using the Soil Erosion Mix prior to placement of the material. Drilling seed is preferred, however, broadcasting is acceptable if drilling is not possible.

Channel = Defined by the area of the project that requires Class 2 erosion control material to be placed. This area shall be seeded using the Soil Erosion Mix prior to placement of the material. Drilling seed is preferred, however, broadcasting is acceptable if drilling is not possible.

GENERAL NOTES

The entire disturbed area, excepting the paved or surfaced areas, steep rocky slopes and areas of undisturbed native sod or other desirable vegetation shall be fertilized (limed when required), seeded, and mulched. Soil preparation shall conform to the Standard Specifications.

Temporary seeding shall be done during any time of the year that the soil can be cultivated. After the temporary seeding has been completed on the entire project, permanent seeding shall be done during the normal seeding season.

MULCHING: Mulch shall be spread uniformly over all disturbed areas and punched in the soil, unless otherwise noted on the plans. The rate of application per acre, thickness in place, for the mulching materials is generally as follows:

1½ - 2¼ Tons per Acre = 1½" loose depth spread uniformly over acre.

Agricultural products, such as native prairie hay, used for mulching and erosion control practices, excluding wood based mulch, shall meet the North American Weed Free Forage Standards.

Other vegetative mulches are acceptable only with the Engineer's concurrence.

The above rate is a guide. It will be at the discretion of the Engineer to determine what rate is sufficient for adequate protection of newly seeded areas.

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	53 C-5270-01	2025	24	45

SUMMARY OF SEEDING / EROSION CONTROL QUANTITIES

P.L.S. RATE/ ACRE		ACRES		BID ITEM	QUANTITY	UNIT
CLT	SL/CH	CLT	SL/CH			
	200		0.26	Fertilizer (13-13-13)	52.0	LB
				Temporary Seed (Canada Wildrye)		
				Temporary Seed (Grain Oats)		
				Temporary Seed (Sterile Wheatgrass)		
	109.9		0.26	Soil Erosion Mix	28.7	LB
				Erosion Control (Class 1, Type C)	1,245	SQ YD
				Erosion Control (Class 2, Type Y)		SQ YD
				Sediment Removal (Set Price)	1	CU YD
				Synthetic Sediment Barrier		LF
				Temporary Berm (Set Price)	1	LF
				Temporary Ditch Check (Rock)		CU YD
				Temporary Inlet Sediment Barrier		EACH
				Temporary Sediment Basin		CU YD
				Temporary Slope Drain		LF
				Temporary Stream Crossing		EACH
				Biodegradable Log (9")		LF
				Biodegradable Log (12")		LF
				Biodegradable Log (20")		LF
				Filter Sock (18")	140	LF
				Geotextile (Erosion Control)		SQ YD
				Silt Fence	200	LF
				SWPPP Design †		LS
				SWPPP Inspection †		EACH
				Water Pollution Control Manager †		EACH
900 lbs / acre				Mulch Tacking Slurry		LB
2 tons / acre				Mulching		TON
				Water (Erosion Control) (Set Price)	1	MGAL

NOTE: Projects less than 1 acre shall be bid as "Seeding" by the lump sum. See Permanent Seeding Summary of Seeding Quantities sheet LA850 for further details.

Geotextile (Erosion Control) shall be removed prior to placement of permanent slope protection.

Regreen and Quick Guard are the approved sterile wheatgrass products.

† If the total disturbed area of the project, not just the seeding area, is 1 acre or more, then these bid items must be included.

**** List size of material.

The amount of mulch and mulch tacking slurry in the bid quantities is estimated. (Acres of Seeding X 1.5 X 2 Tons/Acre). The estimated quantity includes mulching associated with both temporary and permanent seeding operations. The total mulch and mulch tacking slurry required shall be determined in the field. The bid item for mulching and mulch tacking slurry shall be paid for according to the Standard Specifications.

Quantities for all erosion control items are estimated to give full flexibility for compliance with the NPDES permit. Final quantities will be determined in the field.

SOIL EROSION MIX

PLS RATE	NAME	QTY (lb)
0.5	Seed (Blue Grama Grass) (Livingston)	0.13
4.5	Seed (Buffalograss) (Treated)	1.27
45	Seed (Perennial Ryegrass)	11.7
2.6	Seed (Prairie Junegrass)	0.68
6.3	Seed (Slide Oats Grama) (El Reno)	1.64
45	Seed (Tall Fescue) (Endophyte Free)	11.7
6	Seed (Western Wheatgrass) (Barton)	1.56
109.9	Total (lb)	28.7

The Soil Erosion Mix is to be placed under the Class 1 and/or Class 2 erosion control material.

The Soil Erosion Mix consists of the Shoulder Area of the Permanent Seed Mix used on the project.

03	08-03-20	Added Note	M.R.D.	M.L.
02	12-01-17	Revised Standard	M.R.D.	S.H.S.
01	06-01-17	Revised Standard	M.R.D.	S.H.S.
NO.	DATE	REVISIONS	BY	APPD
KANSAS DEPARTMENT OF TRANSPORTATION				
TEMPORARY EROSION AND POLLUTION CONTROL				
LA852A				
DESIGNED	M.R.D.	01-26-18	APPD	Scott H. Shields
DESIGNED	M.R.D.	01-26-18	APPD	SCOTT H. SHIELDS
DESIGNED	M.R.D.	01-26-18	APPD	SCOTT H. SHIELDS
DESIGNED	M.R.D.	01-26-18	APPD	SCOTT H. SHIELDS



STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	53 C-5270-01	2025	25	45

[illegible]




Plotted by: bwilkinson 2-JAN-2025 10:32
File: 2311855_eec-01_1a852a-ec.dgn

NO.	DATE	REVISIONS						BY	APP'D
KANSAS DEPARTMENT OF TRANSPORTATION									
EROSION CONTROL SEEDING-SODDING									
LA852A-EC									
THRU APPROVAL							APPROV.		
DESIGNED		M.M.M.	DETAILS		M.M.M.	QUANTITIES		SCOUT H. SHADIN	
DESIGN CH.		G.H.S.	DETAIL CH.		S.H.B.	QUAN. CHK.		TRACEY C. S.H.S.	

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	53 C-5270-01	2025	26	45



- NOTES:
- 1) Temporary Slope Drain and Temporary Berm may be used on either project foreslopes or project backslopes.
 - 2) Discharge of Slope Drains shall be into stabilized ditch or area, or into Sediment Basin.
 - 3) Pipe shall be secured in place as approved by Engineer.
 - 4) Temporary Berms under 2,000 feet shall be bid by Set Price.




Pipe size may vary.

Place 1 pipe buried 6" into stream bottom, in the lowest point of the channel to allow the passage of aquatic organisms, with additional pipes placed along the remainder of the stream channel bottom such that ordinary high water (OHW) flows designated in the Contract Documents shall flow through the pipes without overtopping the crossing.

Clean aggregate fill will extend a minimum of 50' on the entrance and exit side of the crossing to prevent tracking. The aggregate shall be clean aggregate and a minimum of 6" thick and will be maintained through the use of the crossing.

See KDOT Specifications for more information.



Pipe size may vary.



Place 1 pipe buried 6" into stream bottom, in the lowest point of the channel to allow the passage of aquatic organisms, with additional pipes placed along the remainder of the stream channel bottom such that ordinary high water (OHW) flows designated in the Contract Documents shall flow through the pipes without overtopping the crossing.

Clean aggregate fill will extend a minimum of 50' on the entrance and exit side of the crossing to prevent tracking. The aggregate shall be clean aggregate and a minimum of 6" thick and will be maintained through the use of the crossing.


See KDOT Specifications for more information.

NO.	DATE	REVISIONS	BY	APP'D
03	01-21-22	Temp Stream Crossing - Clean Aggregate Fill Note Added	M.S.D.	M.L.
02	09-24-21	Temp Stream Crossing - Clean Aggregate Fill Note Added	M.S.D.	M.L.
01	06-11-13	Revised Standard	M.R.M.	S.H.S.
KANSAS DEPARTMENT OF TRANSPORTATION				
TEMPORARY EROSION AND POLLUTION CONTROL				
TEMPORARY SLOPE DRAIN, TEMPORARY STREAM CROSSING (AGGREGATE)				
LA852B				
DESIGNED	01-21-22	APP'D	MOORE/LA	
DETAIL CK		QUANTITIES	TRACED	
		QUAN CK	TRACE CK	


STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	53 C-5270-01	2025	27	45




Plotted by: bwilkinson 2-JAN-2025 10:32
File: 2311855_ewp-03_la852c.dgn





NO SCALE




OR



SECTION B-B



OPTIONAL



BIODEGRADABLE LOG SLOPE INTERRUPTIONS

OR Filter Sock

INSTALLATION NOTES

SILT FENCE:

- Stakes shall be 4' (min.) long and of one of the following materials:
 - Hardwood - 1 3/4" x 1 3/4";
 - Southern Pine (No. 2) - 2 5/8" x 2 5/8";
 - Steel U, T, L, or C Section - .95 lbs. per 1'-0"; or
 - Synthetic - same strength as wood stakes.
- Attach fence fabric with 3 zip ties within the top 8" of the fence. Alternate attachment methods may be approved by the Engineer on a performance basis.
- Use of high flow material is acceptable.
- Refer to plan sheets to estimate the length of silt fence required.

BIODEGRADABLE LOG OR FILTER SOCK

- Place biodegradable logs or filter sock tightly together minimum overlap of 18".
- Wood stakes shall be 2" x 2" (nom.).
- Refer to plan sheets to estimate length of biodegradable log and filter sock required.
- Each log or sock (except compost filter socks) should be keyed into the ground at a minimum of 25% of its height. Compost filter socks should be placed on smooth prepared ground with no gaps between the sock and soil.
- Length of stakes should be 2 times the height of the log at a minimum with minimum ground embedment equal to the height of the log / sock.

Biodegradable Log or Filter Sock Slope Interruptions

Slope Gradient	PRODUCT		
	9" Sediment Log or 8" Filter Sock (ft)	12" Sediment Log or 12" Filter Sock (ft)	20" Sediment Log or 18" Filter Sock (ft)
≤4H:1V	40	60	80
3H:1V	30	45	60

Deviations should be approved by the Field Engineer.

BIODEGRADABLE LOG MATERIAL		
	LOW FLOW	HIGH FLOW
9"	Straw/Compost	Excelsior / Wood Chips / Coconut Fiber
12"	Straw/Compost	Excelsior / Wood Chips / Coconut Fiber
18"-20"	Straw/Compost	Excelsior / Wood Chips / Coconut Fiber

GENERAL NOTES


- Slope interruptions shall be placed along contour lines, with a short section turned upgrade at each end of the barrier.
- The maximum length of the slope interruptions shall not exceed 250 feet, and the barrier ends need to be staggered.
- Interruptions damaged by Contractor's negligence, including improper maintenance or lack of maintenance, shall be repaired immediately by Contractor at no additional cost to KDOT.
- Agricultural products, such as native prairie hay, used for mulching and erosion control practices, excluding wood based mulch, shall meet the North American Weed Free Forage Standards.

03	09-28-16	Revised Standard	R.A.	S.H.S.
02	09-01-15	Revised Standard	R.A.	S.H.S.
01	06-01-13	Revised Standard	M.R.M.	S.H.S.
NO	DATE	REVISIONS	BY	APPD

KANSAS DEPARTMENT OF TRANSPORTATION
TEMPORARY EROSION AND POLLUTION CONTROL
SLOPE INTERRUPTIONS
BIODEGRADABLE LOG / SILT FENCE
LA852D

DESIGNED	S.H.S.	DETAILS	R.A.	QUANTITIES	TRACED
CHECKED	S.H.S.	DETAILS	QUAN	CK	TRACED

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	53 C-5270-01	2025	29	45



TYPICAL DITCH CHECK LAYOUT PLAN
NO SCALE

20" BIOLOG CHECK SPACING	
DITCH & SLOPE (%)	SPACING INTERVAL (FEET)
1.0	125
2.0	60
3.0	40
4.0	30
5.0	25
NOTE: Use this spacing for all except Rock Ditch Checks.	

18" FILTER SOCK CHECK SPACING	
DITCH & SLOPE (%)	SPACING INTERVAL (FEET)
1.0	110
2.0	55
3.0	35
4.0	25
5.0	20
NOTE: Use this spacing for all except Rock Ditch Checks.	



GENERAL NOTES

- 1) The choice of ditch check methods is at the option of the Contractor.
- 2) Use only rock checks in situations where the ditch slope is 6 percent or greater.
- 2) Ditch checks damaged by Contractor's negligence, including improper maintenance or lack of maintenance, shall be repaired by Contractor at no extra cost to KDOT.

Plotted by: b.wilkinson 2-JAN-2025 10:33
File: 2311855_swp-05_la852e.dgn

03	08-10-16	Revised Standard	R.A.A.	S.H.S.
02	06-28-16	Revised Standard	R.A.A.	S.H.S.
01	06-01-13	Revised Standard	M.B.M.	S.H.S.
NO.	DATE	REVISIONS	BY	APPD
KANSAS DEPARTMENT OF TRANSPORTATION				
TEMPORARY EROSION AND POLLUTION CONTROL DITCH CHECKS				
LA852E				
DESIGNED: S.H.S. / DETAIL: R.A.A. / QUANTITIES: S.H.S. / TRACED: R.A.A. / DESIGN CK: S.H.S. / DETAIL CK: S.H.S. / QUAN CK: S.H.S. / TRACED CK: S.H.S.				

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	53 C-5270-01	2025	30	45




ROCK DITCH CHECK
NO SCALE



TEMPORARY ROCK DITCH CHECK SPACING	
DITCH @ SLOPE (%)	SPACING INTERVAL (FEET)
5.0	60
6.0	50
7.0	43
8.0	36
9.0	33
10.0	29
NOTE: Use this spacing for Rock Ditch Checks only.	

ROCK DITCH CHECK NOTES

1. Rock shall be clean aggregate, D50-6" and aggregate filler.
2. Place rock in such manner that water will flow over, not around ditch check.
3. Do not use rock ditch checks in clear zone.
4. Excavation: The ditch area shall be reshaped to fill any eroded areas. Prior to placement of the rock, the ditch shall be excavated to the dimensions of the Rock Ditch Check and to a minimum depth of 6" (150mm). After placement of the rock, backfill and compact any over-excavated soil to ditch grade. This work shall be subsidiary to the bid item Temporary Ditch Check (Rock).
5. Aggregate excavated on site may be used as an alternate to the 6" rock, if approved by the Engineer.
6. The Engineer may approve the use of larger aggregates for the downstream portion of the check when conditions warrant their use.
7. When the use of larger rock is approved, D50-6" rock will be placed between the larger aggregate and the aggregate filler.
8. Aggregate filler will be placed on the upstream face of the ditch check. Aggregate filler will comply with Filter Course Type I, Division 1114.



BIODEGRADABLE LOG DITCH CHECK
OR Filter Sock Ditch Check
NO SCALE



BIODEGRADABLE LOG DITCH CHECK NOTES

1. Use as many biodegradable log sections as necessary to ensure water does not flow around end of ditch check.
2. Overlap sections a minimum of 18".
3. Stakes shall be wood or steel according to Section 2114 of the Standard Specifications. Length of stakes shall be a minimum of 2 x the diameter of the log.
4. Use Erosion Control (Class 1) (Type C) as the downstream apron when required.
5. A downstream apron is required when directed by the Engineer. Apron material will be paid at the contract unit price.
6. Each log or sock (except compost filter socks) should be keyed into the ground at a minimum of 25% of its height. Compost filter socks should be placed on smooth prepared ground with no gaps between the sock and soil.

03	11-19-20	Revised Standard	M.R.D.	M.L.		
02	08-10-16	Revised Standard	R.A.A.	C.H.S.		
01	10-21-15	Revised Standard	R.A.A.	S.H.S.		
NO	DATE	REVISIONS		BY APPD		
KANSAS DEPARTMENT OF TRANSPORTATION TEMPORARY EROSION AND POLLUTION CONTROL ROCK DITCH CHECKS BIODEGRADABLE LOG DITCH CHECKS LA852G						
FIRMA APPROVAL		11-19-20	APPD	Morgan Lang		
DESIGNED	M.L.	DETAILED	D.K.	QUANTITIES	TRAFFIC	R.A.A.
DESIGN CK	M.L.	DETAIL CK	M.L.	QUAN CK	TRACE CK	R.A.A.

Plotted by: b.wilkinson 2-JAN-2025 10:33
File: 2311855_ewp-06_la852g.dgn

AL NOTES

surfaced areas, steep rocky slopes and areas of undisturbed
 (limed when required), seeded and mulched.
 modifications except as noted below.

The entire disturbed area, excepting the paved or surfaced areas, steep rocky slopes and areas of undisturbed native soil or other desirable vegetation shall be fertilized (lined when required), seeded and mulched. Soil preparation shall conform to the Standard Specifications except as noted below.

All borrow areas shown on the plans are to be fertilized, seeded, and mulched. However, operation in borrow areas where crops are growing may be omitted when requested by the owner.

If temporary cover has provided stable slopes with no erosion, seed the permanent grasses into the existing cover. If there has been erosion that requires repair prior to seeding, then it may be necessary to regrade the area, resulting in bare ground.

FERTILIZER: A ratio and application rate that equals or exceeds the required minimum rate per acre of N, P₂O₅, K₂O listed in Summary of Seeding Quantities will be acceptable.

MULCHING: Mulch shall be spread uniformly over all disturbed areas and punched in the soil, unless otherwise noted on the plans. The rate of application per acre, thickness in place, for the mulching material is generally as follows:

1¾ - 2¼ Tons per Acre = 1½" loose depth spread uniformly over acre.

Agricultural products, such as native prairie hay, used for mulching and erosion control practices, excluding wood based mulch, shall meet the North American Weed Free Forage Standards.

Other vegetative mulches are acceptable only with the Engineer's concurrence.

The above rate is a guide. It will be at the discretion of the Engineer to determine what rate is sufficient for adequate protection of newly seeded areas.

When seeding is less than 1 acre, temporary and permanent seeding shall be combined and seeded at the same time.

There is no seasonal restriction when seeding projects less than one acre.

COOL SEASON GRASSES	WARM SEASON GRASSES & WILDFLOWERS
February 15 thru April 20 August 15 thru September 30	November 15 thru June 1

When the area to be seeded is 1 acre or more, if Cool Season grasses are mixed with Warm Season grasses, seed the area during the Warm Season.

When the area to be seeded is less than 1 acre, seed the area any time of the year.

COOL SEASON GRASSES	WARM SEASON GRASSES
March 1 thru April 15 September 1 thru November 15	May 15 thru September 1

If the soil is workable, the Engineer may allow placement of sod between November 15 and March 1. If sod is placed during this time, maintain the sod until 20 days after the beginning of the spring sodding season.



Package and deliver the wildflower seed separately from the grass seed mix. Package and deliver the Tall Drop Seed separately from the grass seed and the wildflower mix. Place the grass seed (except Tall Drop Seed) in the large seed box and drill (cover) seed $\frac{1}{8}$ "- $\frac{1}{4}$ ". Place the wildflower seed in a separate seed box and drill (cover) seed $\frac{1}{8}$ " maximum. Place the Tall Drop Seed in a separate (third) seed box and place the seed (using the seed drill) on the soil surface.

OPTION: Broadcast Tall Drop Seed on the soil surface.

[illegible]

SHILDR = Seeded with the Shoulder Mix. Typically 15 feet for 2-lane roads and 30 feet for 4-lane roads. Includes outside roadsides, turfed portions of shoulders, and turfed portion of the median.

OTHER = Seeded with the "Other" Mix. Designated as all other turf areas, except the Shoulder. Usually includes a Native Wildflower Mix.


NOTE: Projects less than 1 acre shall be bid as "Seeding" by the lump sum. All disturbed areas shall be seeded, fertilized and mulched at the listed rate per acre. The acres are estimated.

Refer to the Standard Specifications, Division 900, Section 904 'Seeding', and Section 907 'Sodding', for the seeding and sodding seasons.


* See LA852A for mulching quantity. The quantity of mulch is estimated (Acres of Seeding X 1.5 X 2 Tons/Acre). The total mulch required shall be determined in the field. The bid item for mulching shall be paid for according to the Standard Specifications.

Sh. No. 32

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	53 C-5270-01	2025	33	45



TYPE 3 OBJECT MARKER



TYPE 2 OBJECT MARKER

All dimensions are in inches unless otherwise noted.

NO.	DATE	REVISIONS	BY	APPD.
KANSAS DEPARTMENT OF TRANSPORTATION				
DESIGN DETAILS FOR OBJECT MARKERS TYPE 2 AND TYPE 3				
TF416 10-01-19				
DESIGNED BY: J. W. N. DETAILED BY: J. W. N. QUANTITIES BY: J. W. N. CHECKED BY: J. W. N. TRACED BY: J. W. N.				

Plotted by : bwilkinson 2-JAN-2025 10:34
File : 2311855_css-01_te700.dgn

1) Design Speed: Those items delegated to temporary traffic control should be designed and installed using the posted/legal speed of the roadway prior to work starting.


2) Minimum Lane Width: Lane widths shall be a minimum of 11' (measured between centerlines of pavement markings) or as shown on the plans, or as directed by the engineer. A lane width less than 11' may require restricted roadway width signing.

3) Consideration should be made to separate pedestrian and, if needed, bicycle movements from both work site activity and vehicular traffic. Unless a reasonable safe route that does not involve crossing the roadway can be provided, pedestrians should be appropriately directed with advance signing that encourages them to cross to the opposite side of the roadway. In urban and suburban areas with high vehicular traffic volumes, these signs should be placed at intersections (rather than midblock locations) so that pedestrians are not confronted with midblock work sites that will induce them to attempt skirting the work site or making a midblock crossing.

4) When existing pedestrian facilities are disrupted, closed, or relocated, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility.

5) When the driving surface open to traffic is milled or is a temporary surface made of loose material, or when directed by the engineer a W8-15 (Grooved Pavement) or W8-7 (Loose Gravel) sign shall be used on mainline approaches. This sign should be placed a "C" distance after the W20-1 (Road Work Ahead) sign. A W8-15p motorcycle plaque shall be used to supplement the W8-15 or W8-7 signs. All signs shall be displayed as long as the condition is present.

6) Alternative temporary rumble strip options may be available. Please contact the Temporary Traffic Control Unit for more information at 785-296-1179 or 785-296-1183.



TYPICAL WORK ZONE COMPONENTS

* When concrete barrier system is used, portable channelizing devices are not needed along the tangent barrier section.

Minimum advance warning sign spacing (in feet):

SPEED (MPH) *	A	B	C
URBAN (40 MPH OR LOWER)	100	100	100
URBAN (45 MPH OR HIGHER)	350	350	350
RURAL (55 MPH OR LOWER)	500	500	500
RURAL (60 MPH OR HIGHER)	750	750	750
EXPRESSWAY/FREEWAY	1000	1500	2640

* Posted speed prior to work starting

The minimum spacing between signs shall be no less than 100', unless directed by the engineer.

The spacing between any signs may be increased beyond the minimum values in the table above as approved by the engineer in order to maximize visibility.

Taper Formulas:

$L = WS$ for speeds of 45 MPH or more

$L = WS^2/60$ for speeds of 40 MPH or less

Where: L = Minimum length of taper in feet
S = Numerical value of posted speed prior to work starting in MPH
W = Width in offset feet

Shifting Taper=1/2 L

Shoulder Taper=1/3 L

Channelizer Placement:

- (1) The spacing between devices in transition area (taper) should not exceed a distance in feet equal to 1/2 the posted speed limit in mph prior to work starting.
- (2) The spacing between devices in the advanced warning area and the activity area should not exceed a distance in feet equal to two times the posted speed limit in mph prior to work starting.
- (3) Channelizing devices shall be placed for optimum visibility, normally at right angles to the traffic flow.
- (4) Place directional indicator barricades in series to direct traffic onto the new path. The arrow sign should not be visible to opposing traffic.
- (5) Alternating diagonal orange and white striping must slope downward in the direction traffic is expected to pass.

Buffer Space

SPEED (MPH) *	20	25	30	35	40	45	50	55	60	65	70	75
LENGTH (ft)	115	155	200	250	305	360	425	495	570	645	730	820


* Posted speed prior to work starting

Neither work activity nor storage of equipment, vehicles, or material should occur in the buffer space. When a protection vehicle is placed in advance of the work space, only the space upstream of the vehicle constitutes the buffer space.


If temporary concrete safety barrier system is used to separate approaching traffic from the work space, the barrier system shall be considered part of the activity area. A full lane width should be available throughout the length of the buffer space. See typical work zone components above.

RE	03-13-18	W8-15p usage changed to Shall	R.W.B.	E.K.G.
01	08-18-15	Channelizer spacing info	R.W.B.	K.E.
NO.	DATE	REVISIONS	BY	APPRO
KANSAS DEPARTMENT OF TRANSPORTATION				
TRAFFIC CONTROL GENERAL NOTES				
TE700				
DESIGNED	BAH	03-13-18	APPD	ENC:Kocher
DRAWN BY	DETAIL	R.W.B.	QUANTITIES	TRACED
DETAIL	DETAIL	QUANT	QUANT	TRACE


STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	53 C-5270-01	2025	35	45




DRUM




CONICAL
DELINEATOR



TUBULAR MARKER
Striping as shown for up to 42"




TRAFFIC CONE




TYPE 2 BARRICADE

For rails less than 36" long, 4" wide stripes may be used. All stripes shall slope downward to the traffic side for channelization.




VERTICAL PANEL

The stripes shall slope downward to the traffic side for channelization.



DIRECTION INDICATOR BARRICADE

The stripes shall slope downward in the direction traffic is to pass. The direction indicator barricade shall be used in series to direct the motorist into the intended lane of travel.



PEDESTRIAN CHANNELIZER

- Support device shall not project beyond the detection plate into the pathway.
- Hand trailing edges and detection plates are optional for continuous walls.
- Interconnect pedestrian channelizers to prevent displacement and to provide continuous guidance through or around work.
- Alternate pathways shall be firm, stable, and slip resistant.
- Treat height differentials $> 1/2"$ in the surfaces of alternate paths with a firm, stable, and slip resistant temporary ramp having a slope of 12:1 or flatter and having a width equal to the alternate path.
- Use alternating orange/white on interconnected devices.

Location		Cross-overs	Shoofly Diversions	Tangents	Tapers	Ramps	Head to Head	Object Identifier	Lead-in Devices	Gores
Item										
Portable	Drums	Yes	Yes	Yes	Yes	Yes	(1)	Yes	Yes	Yes
	Conical Delineators	Yes	Yes	Yes	Yes	Yes	(1)	Yes	Yes	Yes
	Vertical Panels	(2)	(2)	(2)	(2)	(2)	(1,2)	Yes	(2)	(2)
	Direction Indicator Barricade	No	No	No	Yes	No	No	No	No	No
	Type 2 Barricade	(2)	(2)	(2)	(2)	No	No	Yes	No	No
	Traffic Cones	No	No	(4)	(4)	(4)	No	(4)	(4)	(4)
Fixed	Tubular Markers	(3)	(3)	(3)	No	(3)	Yes	No	Yes	Yes
	Vertical Panels	(3)	(3)	(3)	(3)	(3)	Yes	(2,3)	(2)	

- Not allowed on centerline delineation along freeways or expressways.
- The stripes shall slope downward to the traffic side for channelization.
- May be used upon the approval of the engineer.
- Daytime operations only.

NO.	DATE	REVISIONS	BY	APPD.
KANSAS DEPARTMENT OF TRANSPORTATION				
TRAFFIC CONTROL CHANNELIZING DEVICES				
TE702				
DESIGNED	L.E.R.	DETAILS	R.W.B.	QUANTITIES
DESIGN CK.	DETAIL CK.	QUAN CK.	TRACE CK.	TRACE CK.

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	53 C-5270-01	2025	36	45




FIGURE 1: TYPICAL SIGNING FOR ROAD CLOSURE (MAINLINE OR SIDE ROAD)




FIGURE 2: TYPICAL SIGNING FOR SIDE ROAD OPEN




FIGURE 3: TYPICAL SIGNING FOR ROAD CLOSURE - LOCAL TRAFFIC ACCESS





FIGURE 4: TYPICAL SIGNING FOR SIDEWALK CLOSED WITH OPPOSITE SIDEWALK AVAILABLE



1. Support device shall not project beyond the detection plate into the pathway.
2. Barricades shall be used to close the entire width of the pathway.
3. Do not use warning lights on pedestrian barricades.
4. Do not use warning lights on audible devices.

When barricades are placed end-to-end or staggered, a Type "A" low intensity warning light shall be mounted to the vertical post near each outside corner of the end barricades.

ROAD CLOSED GENERAL NOTES

As shown in Figure 1, at the point where thru traffic must detour and local traffic can proceed to the location where the roadway is completely closed, the R11-3a (ROAD CLOSED # MILES AHEAD LOCAL TRAFFIC ONLY) or R11-4 (ROAD CLOSED LOCAL TRAFFIC ONLY or ROAD CLOSED TO THRU TRAFFIC) sign shall be used with Type 3 barricades (winged position), placed on the shoulders of roadway.

As shown in Figure 3, when local traffic must be allowed access into the work zone, Type 3 barricades shall be longitudinally staggered to maintain the appearance of a closed roadway. A second line of end-to-end Type 3 barricades shall be placed just beyond the last access point in the work zone, to completely close the roadway.

The R11-4 (ROAD CLOSED TO THRU TRAFFIC or ROAD CLOSED LOCAL TRAFFIC ONLY) sign shall be used when the distance to the point of complete closure of the roadway is less than 1 mile.

The R11-3a (ROAD CLOSED # MILES AHEAD LOCAL TRAFFIC ONLY) sign shall be used when the distance to the point of complete closure of the roadway is 1 mile or greater.

The words "BRIDGE OUT" (or BRIDGE CLOSED) may be substituted for the words "ROAD CLOSED" on the R11-3a or R11-4 sign where applicable.

NO.	DATE	REVISIONS						BY	APP'D
KANSAS DEPARTMENT OF TRANSPORTATION									
TRAFFIC CONTROL CLOSURES									
TE704									
FORK APPROVAL		BE-01-S		APPRO		Minimum Truckload			
REQUIRED B.A.H.		DETAILED REV-B		QUANTITIES		TRUCKED			
DESIGN CK		DETAIL CK		QUAN CK		TRACE CK			

Plotted by : bwlknsn 2-JAN-2025 10:34
File : 2311855_cas-04_te710.dgn

SIGN LAYOUT INFORMATION



Std. Size
Expwy/Freeway
6" C
48"x 24"



Std. Size
Expwy/Freeway
6" C
48"x 24"



Std. Size
Expwy/Freeway
3" C
24"x 6"




Mileage to be Determined
by the Engineer.




Std. Size
Expwy/Freeway
48"x 48"




Std. Size
Expwy/Freeway
30"x 24"



W8-17P
(Optional)



SP-01
(Special Sign)



SP-02
(Special Sign)

All city names and street names on special signs and destination signs must have upper and lower case letters.



W8-15




W8-7



W8-15p



W8-11




RURAL

- 1) Ground-mounted signs shall be mounted at a minimum height of 5' measured from the bottom of sign to the near edge of the pavement.
- 2) Large signs having an area exceeding 50 square feet installed on multiple breakaway posts shall be mounted a minimum of 7' above the ground.
- 3) The height of the secondary sign mounted below another sign may be 4' measured from the bottom of the sign to the near edge of the pavement. Signs shall not overlap each other.




URBAN

- 1) Signs shall be mounted at a minimum height of 7' measured from the bottom of sign to the near edge of the pavement.
- 2) Neither portable nor permanent sign supports should be located on sidewalks or areas designated for pedestrian or bicycle traffic.
- 3) Signs mounted lower than 7' should not project more than 4" into pedestrian facilities.
- 4) The height from of the secondary sign mounted below another sign may be 6' measured from the bottom of sign to the near edge of the pavement. Signs shall not overlap each other.
- 5) Large signs having an area exceeding 50 square feet installed on multiple breakaway posts shall be mounted a minimum of 7' above the ground.
- * 6) Pedestrian detour signing shall be a minimum of 2' measured from the top of the pedestrian pathway to the bottom of the sign and shall not protrude into the walkway nor shall it project beyond the back of curb.




When the sign width is equal to or greater than 9', three or more wood posts may be used with a minimum of 4' between the centerline of each post. All signs less than 9' in width shall use a maximum of two wood posts.

- In the case of hitting rock when driving posts
1. Shift the sign location. Do not violate minimum sign spacing.
 2. With the engineer's approval, use acceptable alternative sign stands.



KI-104a



KI-105a

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	53 C-5270-01	2025	37	45

Sign Number	GIVE EM A BRAKE
Width x Height	4'-0" x 4'-0"
Border Width	1.0"
Corner Radius	4.0"
Stripe Width	3.0"
Mounting	Ground
Background	Type: Non-Reflective
Legend/Border	Type: Reflective
Legend Font	Color: White
Legend Font	Dutch 801 Roman SWC
Legend Font	25 Degree Slant
Stripes	Type: Reflective
Stripes	Color: Orange

Sign Number	FINES DOUBLE
Width x Height	4'-0" x 3'-0"
Border Width	0.9"
Corner Radius	3.0"
Mounting	Ground
Background	Type: Reflective
Legend/Border	Type: Non-Reflective
Legend/Border	Color: Black

Dimensions in inches

Spacings are to start of next letter

Y FONT	LETTER SPACINGS																HT LEN
23.0 D	F	I	N	E	S												8.0
	9.7	6.4	3.2	7.3	6.4	5.4	9.7										28.6
11.0 D	D	O	U	B	L	E											8.0
	3.9	6.9	7.5	7.3	7.3	6.4	4.9	3.9									40.3
4.0 D	I	N	W	O	R	K	Z	O	N	E	S						4.0
	3.1	1.6	2.7	3.2	4.3	3.8	3.6	2.8	3.2	3.4	3.8	3.6	3.2	2.7	3.1		41.8

Notes:


Typically, there are two sets of informational signs installed per project: one for each direction of traffic.

Install signs a minimum of 500' in advance of the road work ahead sign. The engineer may designate a more appropriate location if conditions dictate.


The informational signs are not to interfere with the traffic control signs for the project.

NO.	DATE	REVISIONS	BY	APP'D
KANSAS DEPARTMENT OF TRANSPORTATION				
TRAFFIC CONTROL SIGN INFORMATION				
TE710				
DESIGNED	BY	DATE	QUANTITIES	TRACED
DESIGNED	BY	DATE	QUANTITIES	TRACED


PERFORATED SQUARE STEEL TUBE (P.S.S.T.) POST SETUP




P.S.S.T. Detail



Telescoping P.S.S.T. Detail




Section A-A




Section B-B

Details for 2", 2 1/4", or 2 1/2" sign posts
Place bolts in the same corner along each sign post.


WOOD POST SETUP




Side Elevation
4" x 4" Wood Post in Soil




Side Elevation
4" x 6" Wood Post in Soil



Section A-A




Section B-B




Front Elevation

See TE710 for Additional
Details and Requirements

3 LB/F U-CHANNEL
SETUP



Notes:
Place two bolts at both ends of the splice through the holes nearest the ends of the splice.
Use manufacturer recommended spacers over the bolts between the spliced pieces of U-Channel.



Section A-A

REVISIONS			
NO.	DATE	BY	APPD.
KANSAS DEPARTMENT OF TRANSPORTATION			
TRAFFIC CONTROL SIGN POSTS			
TE712			
DESIGNED	BAH	08-01-13	APPROVED
DRAWN	BAH	08-01-13	TRACED
CHECKED	BAH	08-01-13	QUANTITIES
REVIEWED	BAH	08-01-13	TRACE

